

BALANCE CARD

Project: R-2911C

County: ROWAN

STATION	UNCLASSIFIED EXCAVATION				UNDERCUT EXCAV.	EMBANKMENT				TOTAL EMB. + 20%	BORROW	WASTE				
	TOTAL	SUITABLE EARTH	ROCK	UNSUITABLE		TOTAL	EARTH	ROCK	REPLACE UNDERCUT			SUITABLE EARTH	ROCK	UNSUIT.		
SUMMARY #6																
-L2- 115+50.00 TO -L2- 141+00.00 LT	6,072	6,072				1,456	1,456			1,747				4,325		
-L2- 115+50.00 TO -L2- 141+00.00 RT	35,808	35,808				10,915	10,915			13,098				22,710		
SUBTOTAL: SUMMARY #6	41,880	41,880				12,371	12,371			14,845				27,035		
SUMMARY #7																
-L2- 141+00.00 TO -L2- 169+00.00 LT	4,375	4,375				1,953	1,953			2,344				2,031		
-L2- 141+00.00 TO -L2- 169+00.00 RT	19,369	19,369				23,436	23,436			28,123	8,754					
-Y12- 10+35.63 TO -Y12- 13+50.00	1,462	1,462				69	69			83				1,379		
-DR5- 10+00.00 TO -DR5- 11+51.33	1,082	1,082				4	4			5				1,077		
-Y13- 14+50.00 TO -Y13- 17+51.78	280	280				86	86			103				177		
-Y13- 18+82.19 TO -Y13- 26+00.00	1,017	1,017				975	975			1,170	153					
SUBTOTAL: SUMMARY #7	27,585	27,585				26,523	26,523			31,828	8,907			4,664		
SUMMARY #8																
-L2- 169+00.00 TO -L2- 198+00.00 LT	7,440	7,440				1,325	1,325			1,590				5,850		
-L2- 169+00.00 TO -L2- 198+00.00 RT	28,025	28,025				8,087	8,087			9,704				18,321		
SUBTOTAL: SUMMARY #8	35,465	35,465				9,412	9,412			11,294				24,171		
SUMMARY #9																
-L2- 198+00.00 TO -L2- 225+00.00 LT	8,089	8,089				711	711			853				7,236		
-L2- 198+00.00 TO -L2- 225+00.00 RT	16,472	16,472				26,468	26,468			31,762	15,290					
SUBTOTAL: SUMMARY #9	24,561	24,561				27,179	27,179			32,615	15,290			7,236		
SUMMARY #10																
-DET1- 10+00.00 TO -DET1- 20+64.85	36	36														
-DET2- 10+00.00 TO -DET2- 23+66.28	219	219				802	802			962	743			36		
SUBTOTAL: SUMMARY #10	255	255				802	802			962	743			36		
SUMMARY #11																
-DET1- BACKFILL AND REMOVAL						36	36			43	43					
-DET2- BACKFILL AND REMOVAL	802	802				219	219			263				539		
SUBTOTAL: SUMMARY #11	802	802				255	255			306	43			539		