

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	3 ACR		
0005	0015000000-N	205	SEALING ABANDONED WELLS	4 EA		
0006	0022000000-E	225	UNCLASSIFIED EXCAVATION	254,100 CY		
0007	0036000000-E	225	UNDERCUT EXCAVATION	5,500 CY		
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,400 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	2,400 LF		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	5,600 SY		
0012	0192000000-N	260	PROOF ROLLING	13 HR		
0013	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0014	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0015	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS II	1,800 CY		
0016	0241000000-E	SP	GENERIC GRADING ITEM PRIMARY GEOGRID REINFORCEMENT	1,100 SY		
0017	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCE- MENT	600 SY		
0018	0245000000-E	SP	GENERIC GRADING ITEM DECONTAMINATION WATER FOR DIS- POSAL	100 GAL		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, DISPOSAL OF CONTAMINATED SOIL	1,100 TON		
0020	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,375 TON		
0021	0343000000-E	310	15" SIDE DRAIN PIPE	340 LF		
0022	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,024 LF		
0023	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,616 LF		
0024	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	5,284 LF		
0025	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	2,696 LF		
0026	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	184 LF		
0027	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	664 LF		
0028	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	96 LF		
0029	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	204 LF		
0030	0426000000-E	310	72" RC PIPE CULVERTS, CLASS III	56 LF		
0031	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (60")	236 LF		
0032	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	160 LF		
0033	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	172 LF		
0034	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	124 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	0726000000-E	310	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	236 LF		
0036	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0037	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	3 EA		
0038	0808000000-E	310	24" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	7 EA		
0039	0809000000-E	310	30" BIT COAT CS PIPE ELBOWS, T YPE B 0.079" THICK	4 EA		
0040	0980000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (54", 0.750")	140 LF		
0041	0980000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (60", 0.875")	144 LF		
0042	0995000000-E	340	PIPE REMOVAL	2,365 LF		
0043	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0044	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0045	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	1,500 LB		
0046	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	50,900 SY		
0047	1066000000-E	501	LIME FOR LIME TREATED SOIL	510 TON		
0048	1110000000-E	510	STABILIZER AGGREGATE	500 TON		
0049	1121000000-E	520	AGGREGATE BASE COURSE	37,000 TON		
0050	1176000000-E	542	*** SOIL CEMENT BASE (7")	27,400 SY		
0051	1187000000-E	542	PORTLAND CEMENT FOR SOIL CE- MENT BASE	760 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	1198000000-E	SP	AGGREGATE FOR SOIL CEMENT BASE	350 TON		
0053	1209000000-E	543	ASPHALT CURING SEAL	11,800 GAL		
0054	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0055	1231000000-E	560	SHOULDER BORROW	21,650 CY		
0056	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	24,500 SY		
0057	1330000000-E	607	INCIDENTAL MILLING	1,600 SY		
0058	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,310 TON		
0059	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	13,765 TON		
0060	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	37,400 TON		
0061	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,200 TON		
0062	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	29,200 TON		
0063	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,590 TON		
0064	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,755 TON		
0065	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	300 TON		
0066	2000000000-N	806	RIGHT OF WAY MARKERS	185 EA		
0067	2022000000-E	815	SUBDRAIN EXCAVATION	340 CY		
0068	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0069	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0071	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0072	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0073	2143000000-E	818	BLOTTING SAND	15 TON		
0074	2209000000-E	838	ENDWALLS	13 CY		
0075	2220000000-E	838	REINFORCED ENDWALLS	22 CY		
0076	2253000000-E	840	PIPE COLLARS	19 CY		
0077	2264000000-E	840	PIPE PLUGS	3.5 CY		
0078	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	160 EA		
0079	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	76.7 LF		
0080	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2 EA		
0081	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	9 EA		
0082	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	97 EA		
0083	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0084	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0085	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	15 EA		
0086	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	21 EA		
0087	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0088	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	7,950 LF		
0089	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	11,400 LF		
0090	2556000000-E	846	SHOULDER BERM GUTTER	520 LF		
0091	2619000000-E	850	4" CONCRETE PAVED DITCH	170 SY		
0092	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,290 SY		
0093	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	98 LF		
0094	2739000000-E	852	GENERIC PAVING ITEM 1/2" CORRUGATED CONCRETE IS- LAND	80 SY		
0095	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	4 EA		
0096	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0097	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	2 EA		
0098	3030000000-E	862	STEEL BM GUARDRAIL	7,962.5 LF		
0099	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	300 LF		
0100	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0101	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0102	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	7 EA		
0103	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	21 EA		
0104	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	7 EA		
0105	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	28,000 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	1,710 EA		
0107	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	470 EA		
0108	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		
0109	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (3)	650 LF		
0110	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	1,225 LF		
0111	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (5)	4,600 LF		
0112	3628000000-E	876	PLAIN RIP RAP, CLASS I	650 TON		
0113	3649000000-E	876	PLAIN RIP RAP, CLASS B	1,520 TON		
0114	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,150 SY		
0115	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0116	4054000000-E	902	PLAIN CONCRETE SIGN FOOTINGS	1 CY		
0117	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	252 LB		
0118	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	3,581 LF		
0119	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0120	4102000000-N	904	SIGN ERECTION, TYPE E	200 EA		
0121	4108000000-N	904	SIGN ERECTION, TYPE F	9 EA		
0122	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1 EA		
0123	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	2 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	3 EA		
0125	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	93 EA		
0126	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	2 EA		
0127	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5 EA		
0128	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	839 SF		
0129	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	200 SF		
0130	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	314 SF		
0131	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0132	4430000000-N	1130	DRUMS	450 EA		
0133	4445000000-E	1145	BARRICADES (TYPE III)	336 LF		
0134	4450000000-N	1150	FLAGGER	960 HR		
0135	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		
0136	4510000000-N	SP	POLICE	192 HR		
0137	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,124 EA		
0138	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	74,554 LF		
0139	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	21,045 LF		
0140	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,884 LF		
0141	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	337 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	93 EA		
0143	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	267,152 LF		
0144	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	7,942 LF		
0145	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	420 LF		
0146	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,920 LF		
0147	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	20 EA		
0148	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	219 EA		
0149	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	240 EA		
0150	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	879 EA		
0151	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	435 TON		
0152	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	435 TON		
0153	5354000000-E	1510	4" DI WATER PIPE, PC 350	15 LF		
0154	5360000000-E	1510	6" DI WATER PIPE, PC 350	1,483 LF		
0155	5366000000-E	1510	8" DI WATER PIPE, PC 350	25 LF		
0156	5378000000-E	1510	12" DI WATER PIPE, PC 350	1,121 LF		
0157	5384000000-E	1510	16" DI WATER PIPE, PC ***** (PC 350)	8,120 LF		
0158	5408000000-E	1510	***** COPPER WATER PIPE, TYPE K (2")	6 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	5 LF		
0160	5432000000-E	1510	2" PVC WATER PIPE, SDR ***** (SDR 9)	6 LF		
0161	5480000000-E	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	21,515 LB		
0162	5492000000-E	SP	3/4" PE WATER TUBING, SDR 9, *****WP (200# WP)	108.5 LF		
0163	5498000000-E	SP	**** PE WATER TUBING, SDR 9, *****WP (2", 200# WP)	15 LF		
0164	5510000000-E	1510	3/4" CORPORATION STOP	1 EA		
0165	5528000000-E	1510	2" CORPORATION STOP	3 EA		
0166	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (2", 200# WP)	2 EA		
0167	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (4", 200#WP)	1 EA		
0168	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	20 EA		
0169	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200# WP)	5 EA		
0170	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200# WP)	4 EA		
0171	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 2")	1 EA		
0172	5582000000-E	1510	***X*** TAPPING SADDLE (16" X 2")	1 EA		
0173	5582000000-E	1510	***X*** TAPPING SADDLE (16" x 3/4")	1 EA		
0174	5582000000-E	1510	***X*** TAPPING SADDLE (6" X 2")	1 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0175	5648000000-N	1510	RELOCATE EXISTING WATER METER	5 EA		
0176	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	20 EA		
0177	5726000000-E	1520	8" DI SEWER PIPE, PC 350	494 LF		
0178	5774000000-E	1525	*** DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH (4')	2 EA		
0179	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (16", DI-WATER)	6,570 LF		
0180	5816000000-N	1530	BREAK DOWN, PLUG, & FILL ABAN- DONED UTILITY MANHOLE	1 EA		
0181	5882000000-N	SP	GENERIC UTILITY ITEM 16" BUTTERFLY VALVE & MANHOLE	5 EA		
0182	5882000000-N	SP	GENERIC UTILITY ITEM BLOW OFF ASSEMBLY	4 EA		
0183	6000000000-E	1605	TEMPORARY SILT FENCE	6,000 LF		
0184	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	565 TON		
0185	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10,185 TON		
0186	6012000000-E	1610	SEDIMENT CONTROL STONE	4,015 TON		
0187	6015000000-E	1615	TEMPORARY MULCHING	77 ACR		
0188	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	2,750 LB		
0189	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	11 TON		
0190	6024000000-E	1622	TEMPORARY SLOPE DRAINS	685 LF		
0191	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	22 EA		
0192	6029000000-E	SP	SAFETY FENCE	4,000 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0193	6030000000-E	1630	SILT EXCAVATION	43,000 CY		
0194	6036000000-E	1631	MATTING FOR EROSION CONTROL	21,600 SY		
0195	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,950 SY		
0196	6042000000-E	1632	1/4" HARDWARE CLOTH	3,080 LF		
0197	6045000000-E	SP	*** TEMPORARY PIPE (18")	850 LF		
0198	6069000000-E	1638	STILLING BASINS	180 CY		
0199	6084000000-E	1660	SEEDING & MULCHING	76 ACR		
0200	6087000000-E	1660	MOWING	46 ACR		
0201	6090000000-E	1661	SEED FOR REPAIR SEEDING	700 LB		
0202	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.5 TON		
0203	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,850 LB		
0204	6108000000-E	1665	FERTILIZER TOPDRESSING	56.75 TON		
0205	6109000000-E	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BLUEGRASS)	1 ACR		
0206	6111000000-E	SP	IMPERVIOUS DIKE	155 LF		
0207	6114000000-N	SP	SPECIALIZED HAND MOWING	22.5 HR		
0208	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	20 EA		
0209	7060000000-E	1705	SIGNAL CABLE	3,935 LF		
0210	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	31 EA		
0211	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	11 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0212	7264000000-E	1710	MESSENGER CABLE (3/8")	2,625 LF		
0213	7288000000-E	1715	TRENCHING (PAVED)	235 LF		
0214	7300000000-E	1715	TRENCHING (UNPAVED)	3,510 LF		
0215	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	20 EA		
0216	7360000000-N	1720	WOOD POLE	5 EA		
0217	7372000000-N	1721	GUY ASSEMBLY	16 EA		
0218	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0219	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,790 LF		
0220	7456000000-E	1726	LEAD-IN CABLE	10,720 LF		
0221	7576000000-N	1740	METAL STRAIN SIGNAL POLE	8 EA		
0222	7613000000-N	SP	SOIL TEST	8 EA		
0223	7614000000-E	SP	DRILLED PIER FOUNDATION (***) DIA) (42")	120 LF		
0224	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		
0225	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0226	7688000000-N	SP	CABINET BASE ADAPTER	2 EA		
0227	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0228	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	13 EA		

CULVERT ITEMS

0229	8126000000-N	414	CULVERT EXCAVATION, STA ***** (152 + 76.60 -L2-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0230	8126000000-N	414	CULVERT EXCAVATION, STA ***** (193 + 55.70 -L2-)	Lump Sum	L.S.	
0231	8126000000-N	414	CULVERT EXCAVATION, STA ***** (62 + 25.00 -L1-)	Lump Sum	L.S.	
0232	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	259 TON		
0233	8196000000-E	420	CLASS A CONCRETE (CULVERT)	382.5 CY		
0234	8245000000-E	425	REINFORCING STEEL (CULVERT)	53,905 LB		

1208/Nov15/Q1262593.45/D872248700000/E234

Total Amount Of Bid For Entire Project :

C201068 (R-2911C)
ROWAN COUNTY

2/16/99

Contract No: C201068

County: Rowan

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General