

## FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
		THERMOPLASTIC (4", 90 mils)		
TA	WHITE EDGELINE		35593'	
TB	YELLOW EDGELINE		28258'	63851'
		THERMOPLASTIC (4", 120 mils)		
TC	10' WHITE SKIP		7088'	
TD	2' WHITE MINISKIP		784'	
TE	WHITE SOLID LANE LINE		3369'	
TH	YELLOW SINGLE CENTERLINE		609'	
TI	YELLOW DOUBLE CENTERLINE		6384'	18234'
		THERMOPLASTIC (8", 90 mils)		
TP	WHITE GORELINE		2619'	
TQ	WHITE DIAGONAL		727'	
TT	YELLOW DIAGONAL		36'	3382'
		THERMOPLASTIC (24", 120 mils)		
T3	WHITE CROSSWALK LINE		96'	
T2	WHITE STOP BAR		658'	754'
		THERMOPLASTIC SYMBOLS (90 mils)		
UA	LEFT TURN ARROW		37 EA	
UB	RIGHT TURN ARROW		23 EA	
UC	STRAIGHT ARROW		47 EA	
UD	COMBO STRAIGHT / LEFT		1 EA	
UE	COMBO STRAIGHT / RIGHT		3 EA	
UG	COMBO STRAIGHT / LEFT / RIGHT		1 EA	112 EA
		THERMOPLASTIC SYMBOLS (120 mils)		
UI	THERMOPLASTIC THICK CHARACTER		12 EA	12 EA
		PAINT (4")		
PA	WHITE EDGELINE		2850'	
PB	YELLOW EDGELINE		1750'	
PC	WHITE SKIP		250'	
PI	YELLOW DOUBLE CENTERLINE		2300'	7150'
		PAINT (8")		
PV	YELLOW DIAGONAL		350'	350'
		SNOWPLOWABLE RAISED PAVEMENT MARKERS		
	YELLOW & YELLOW		165	
	CRYSTAL & YELLOW		865	1030

APPROVED: <i>Phonda B. Early</i> DATE: 8-15-04	<b>PAVEMENT MARKING SCHEDULE</b>	
	SCALE:	REVISIONS
	DATE: 0827/04	
	DWG. BY: MAS	
	DESIGN BY: JMH	
REVIEWED BY: RBE		