RALC8W5W41

COMPUTED BY: C. HIGHFILL DATE: 7/30/2004

CHECKED BY: D. BASS DATE: 7/30/2004

PROJECT NO.	SHEET NO.
R-2911D	3-H

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)

| STATION | LOCATION (LT, RT, OR CL) | STRUCTURE NO. FROM | STRUCTURE NO. TO | TOP ELEVATION | INVERT ELEVATION | INVERT ELEVATION | SLOPE CRITICAL | CLASS III R.C. PIPE (UNLESS NOTED OTHERWISE) 12" | 15" | 18" | 24" | 30" | 36" | 42" | 48" | BITUMINOUS COATED C.S. PIPE TYPE B (UNLESS NOTED OTHERWISE) 12" .064 | 15" .064 | 18" .064 | 24" .064 | 30" .079 | 30" .079 | 36" .079 | 36" .109 | 42" .109 | WELDED STEEL 24" .500 | WELDED STEEL 24" .500 | 15" SIDE DRAIN PIPE | 18" SIDE DRAIN PIPE | 24" SIDE DRAIN PIPE | ENDWALLS STD. 838.01 OR STD. 838.11 (UNLESS NOTED OTHERWISE) CU. YARDS R.C.P. | ENDWALLS CU. YARDS C.S.P. | QUANTITIES FOR DRAINAGE STRUCTURES *TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (1.3 X COL.'B') PER EACH (0' THRU 5.0') | LIN. FT. A 5.0' THRU 10.0' | LIN. FT. B 10.0' AND ABOVE | C.B. STD. 840.01 OR STD. 840.02 | FRAME, GRATES, AND HOOD STANDARD 840.03 TYPE OF GRATE E | F | G | D.I. STD. 840.14 OR STD. 840.15 | D.I. FRAME AND GRATE STD. 840.16 | M.D.I. TYPE "A" STD. 840.17 OR 840.26 | M.D.I. TYPE "B" STD. 840.18 OR 840.27 | M.D.I. TYPE "D" STD. 840.19 OR 840.28 | M.D.I. FRAME WITH GRATE STD. 840.20 | M.D.I. (N.S.) FRAME WITH TWO GRATES STD. 840.24 | M.D.I. (N.S.) FRAME WITH GRATE STD. 840.24 | M.D.I. FRAME WITH TWO GRATES STD. 840.22 | J.B. STD. 840.31 OR 840.32 | M.D.I. (N.S.) FRAME WITH TWO FLAT GRATES STD. 840.29 | MANHOLE STD. 840.51 | M.H. STD. 840.51 OR 840.53 | M.H. FRAME AND COVER STD. 840.54 | 18" X 18" X 18" PERFORATED TEE RISER | CONVERT 2GI W/LID TO 2GI W/FRAME AND GRATE | CORR. STEEL ELBOWS NO. & SIZE | CONC. COLLARS CL. "B" C.Y. STD. 840.72 | CONC. & BRICK PIPE PLUG, C.Y. STD. 840.71 | PIPE REMOVAL LIN. FT. | REMARKS |
|---|---|---