

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200968

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	3649000000-E	876	10	TON	PLAIN RIP RAP, CLASS B	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+60.00)	3656000000-E	876	195	SY	FILTER FABRIC FOR DRAINAGE	6108000000-E	1665	0.5	TON	FERTILIZER TOPDRESSING
0043000000-N	226	Lump Sum		GRADING	3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	4400000000-E	1110	377	SF	WORK ZONE SIGNS (STATIONARY)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	4410000000-E	1110	45	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
0134000000-E	240	6	CY	DRAINAGE DITCH EXCAVATION	4425000000-N	1125	6	EA	WARNING FLAG SETS					
0318000000-E	300	16	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	4445000000-E	1145	96	LF	BARRICADES (TYPE III)					
0366000000-E	310	48	LF	15" RC PIPE CULVERTS, CLASS III	4810000000-E	1205	8,000	LF	PAINT PAVEMENT MARKING LINES (4")					
0390000000-E	310	72	LF	36" RC PIPE CULVERTS, CLASS III	6000000000-E	1605	1,010	LF	TEMPORARY SILT FENCE					
0708000000-E	310	28	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	6006000000-E	1610	50	TON	STONE FOR EROSION CONTROL, CLASS A					
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6009000000-E	1610	115	TON	STONE FOR EROSION CONTROL, CLASS B					
1220000000-E	545	100	TON	INCIDENTAL STONE BASE	6012000000-E	1610	45	TON	SEDIMENT CONTROL STONE					
1489000000-E	610	350	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	6015000000-E	1615	1	ACR	TEMPORARY MULCHING					
1525000000-E	SP	435	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING					
1560000000-E	620	44	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING					
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES	6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS					
2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					
2556000000-E	846	230	LF	SHOULDER BERM GUTTER	6029000000-E	SP	150	LF	SAFETY FENCE					
3030000000-E	862	412.5	LF	STEEL BM GUARDRAIL	6030000000-E	1630	100	CY	SILT EXCAVATION					
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6036000000-E	1631	1,010	SY	MATTING FOR EROSION CONTROL					
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH					
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6048000000-E	SP	60	SY	FLOATING TURBIDITY CURTAIN					
3628000000-E	876	10	TON	PLAIN RIP RAP, CLASS I	6084000000-E	1660	1	ACR	SEEDING & MULCHING					
					6087000000-E	1660	0.5	ACR	MOWING					
					6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING					
					6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING					