

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	3 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	98,000 CY		
0005	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (237+73.00)	Lump Sum	L.S.	
0006	0036000000-E	225	UNDERCUT EXCAVATION	1,500 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	300 TON		
0008	0106000000-E	230	BORROW EXCAVATION	40,500 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,700 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	24,200 SY		
0011	0195000000-E	265	SELECT GRANULAR MATERIAL	8,000 CY		
0012	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	7,500 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	820 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	2,736 LF		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	520 LF		
0016	0345000000-E	310	24" SIDE DRAIN PIPE	284 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,348 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,400 LF		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	512 LF		
0020	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	96 LF		
0021	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	188 LF		
0022	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	76 LF		
0023	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	48 LF		
0024	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	36 LF		
0025	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	524 LF		
0026	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	32 EA		
0027	0980000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (24", 0.375")	180 LF		
0028	0995000000-E	340	PIPE REMOVAL	2,983 LF		
0029	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0030	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	4,500 LB		
0031	1110000000-E	510	STABILIZER AGGREGATE	450 TON		
0032	1121000000-E	520	AGGREGATE BASE COURSE	4,700 TON		
0033	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0034	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***** DEPTH (2")	1,500 SY		
0035	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,000 TON		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	20,000 TON		
0037	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	625 TON		
0038	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	11,250 TON		
0039	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,725 TON		
0040	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	20,250 TON		
0041	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,625 TON		
0042	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,325 TON		
0043	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0044	1840000000-E	665	MILLED RUMBLE STRIPS	51,000 LF		
0045	2000000000-N	806	RIGHT OF WAY MARKERS	109 EA		
0046	2022000000-E	815	SUBDRAIN EXCAVATION	225 CY		
0047	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0048	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		
0049	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30 EA		
0050	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0051	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0052	2209000000-E	838	ENDWALLS	22 CY		
0053	2220000000-E	838	REINFORCED ENDWALLS	10.6 CY		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	2253000000-E	840	PIPE COLLARS	16 CY		
0055	2264000000-E	840	PIPE PLUGS	1.32 CY		
0056	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	43 EA		
0057	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	9.63 LF		
0058	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	6 EA		
0059	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	31 EA		
0060	2396000000-N	840	FRAME WITH COVER, STD 840.54	6 EA		
0061	2462000000-E	SP	*** SLUICE GATE (18")	2 EA		
0062	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS WASTE RETENTION BASIN	Lump Sum	L.S.	
0063	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	1,160 LF		
0064	2556000000-E	846	SHOULDER BERM GUTTER	5,485 LF		
0065	2830000000-N	858	ADJUSTMENT OF MANHOLES	32 EA		
0066	3030000000-E	862	STEEL BM GUARDRAIL	7,825 LF		
0067	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0068	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0069	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	48 EA		
0070	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,410 LF		
0071	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	4 EA		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0073	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	400 LF		
0074	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	34 EA		
0075	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	8 EA		
0076	3554000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, DOUBLE GATE (48")	4 EA		
0077	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	500 LF		
0078	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 6' WIDE, 12' OPENING)	2 EA		
0079	3649000000-E	876	PLAIN RIP RAP, CLASS B	2,100 TON		
0080	3651000000-E	SP	BOULDERS	15 TON		
0081	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,475 SY		
0082	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0083	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	944 SF		
0084	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	576 SF		
0085	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	174 SF		
0086	4425000000-N	1125	WARNING FLAG SETS	11 EA		
0087	4430000000-N	1130	DRUMS	100 EA		
0088	4435000000-N	1135	CONES	100 EA		
0089	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	4450000000-N	1150	FLAGGER	2,400	HR	
0091	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6	EA	
0092	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	6	EA	
0093	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	5	EA	
0094	4485000000-E	1170	PORTABLE CONCRETE BARRIER	700	LF	
0095	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	900	LF	
0096	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	700	LF	
0097	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	400	LF	
0098	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	450	LF	
0099	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	850	EA	
0100	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	384,000	LF	
0101	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	600	LF	
0102	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	300	LF	
0103	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	250	EA	
0104	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	150,000	LF	
0105	4847110000-E	SP	POLYUREA PAVEMENT MARKING LINES (8")	300	LF	
0106	4847140000-E	SP	POLYUREA PAVEMENT MARKING LINES (24")	100	LF	

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	4847220000-N	SP	POLYUREA PAVEMENT MARKING SYMBOL	100	EA	
0108	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,500	LF	
0109	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	500	EA	
0110	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	50	TON	
0111	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	50	TON	
0112	5348000000-E	1510	*** DI WATER PIPE, PC ***** (20", PC 350)	769	LF	
0113	5378000000-E	1510	12" DI WATER PIPE, PC 350	15	LF	
0114	5432000000-E	1510	2" PVC WATER PIPE, SDR ***** (SDR 21, 200# WP)	381	LF	
0115	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	4,210	LB	
0116	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (2", 200# WP)	1	EA	
0117	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (20", 200# WP)	2	EA	
0118	5582000000-E	1510	***X*** TAPPING SADDLE (20" X 2")	1	EA	
0119	5750000000-E	1520	*** DI FORCE MAIN SEWER PIPE, PC ***** (6", PC 350)	456	LF	
0120	5756000000-E	1520	DUCTILE IRON SEWER PIPE FITTINGS, ***** (250# MIN WP)	235	LB	
0121	5882000000-N	SP	GENERIC UTILITY ITEM 2" UNIVERSAL SEWER AIR RELEASE VALVE & 4' PRECAST DOGHOUSE MANHOLE	1	EA	

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	5882000000-N	SP	GENERIC UTILITY ITEM 6" COMBINATION AIR RELEASE VALVE & 5' PRECAST DOGHOUSE MANHOLE	1	EA	
0123	6000000000-E	1605	TEMPORARY SILT FENCE	5,305	LF	
0124	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	940	TON	
0125	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	13,285	TON	
0126	6012000000-E	1610	SEDIMENT CONTROL STONE	4,220	TON	
0127	6015000000-E	1615	TEMPORARY MULCHING	46	ACR	
0128	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,650	LB	
0129	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	6.5	TON	
0130	6024000000-E	1622	TEMPORARY SLOPE DRAINS	980	LF	
0131	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	37	EA	
0132	6029000000-E	SP	SAFETY FENCE	1,500	LF	
0133	6030000000-E	1630	SILT EXCAVATION	34,685	CY	
0134	6036000000-E	1631	MATTING FOR EROSION CONTROL	25,725	SY	
0135	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,865	SY	
0136	6042000000-E	1632	1/4" HARDWARE CLOTH	1,425	LF	
0137	6045000000-E	SP	*** TEMPORARY PIPE (18")	75	LF	
0138	6045000000-E	SP	*** TEMPORARY PIPE (24")	100	LF	
0139	6070000000-N	SP	SPECIAL STILLING BASINS	10	EA	



County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	6084000000-E	1660	SEEDING & MULCHING	47.5	ACR	
0141	6087000000-E	1660	MOWING	27.5	ACR	
0142	6090000000-E	1661	SEED FOR REPAIR SEEDING	400	LB	
0143	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1	TON	
0144	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	1,100	LB	
0145	6108000000-E	1665	FERTILIZER TOPDRESSING	35.5	TON	
0146	6109000000-E	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS)	1.2	ACR	
0147	6111000000-E	SP	IMPERVIOUS DIKE	270	LF	
0148	6114000000-N	SP	SPECIALIZED HAND MOWING	26	HR	
0149	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	24	EA	
0150	6123000000-E	1670	REFORESTATION	2	ACR	
0151	6126000000-E	SP	STREAMBANK REFORESTATION	0.3	ACR	
0152	7060000000-E	1705	SIGNAL CABLE	300	LF	
0153	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	22	EA	
0154	7264000000-E	1710	MESSENGER CABLE (3/8")	290	LF	
0155	7360000000-N	1720	WOOD POLE	3	EA	
0156	7372000000-N	1721	GUY ASSEMBLY	4	EA	
0157	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2	EA	
0158	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2	EA	
0159	7636000000-N	1745	SIGN FOR SIGNALS	4	EA	

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0160	7912000000-N	SP	BEACON CONTROLLER ASSEMBLY & CABINET (***** (F1)	2 EA		
<b>CULVERT ITEMS</b>						
0161	8126000000-N	414	CULVERT EXCAVATION, STA ***** (25+91.40 -L-)	Lump Sum	L.S.	
0162	8126000000-N	414	CULVERT EXCAVATION, STA ***** (251+65.22 -L-)	Lump Sum	L.S.	
0163	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	95 TON		
0164	8196000000-E	420	CLASS A CONCRETE (CULVERT)	189.9 CY		
0165	8245000000-E	425	REINFORCING STEEL (CULVERT)	19,832 LB		
<b>STRUCTURE ITEMS</b>						
0166	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (236+73.00-L-)	Lump Sum	L.S.	
0167	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (236+73.00-L-)	Lump Sum	L.S.	
0168	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (236+73.00-L-)	Lump Sum	L.S.	
0169	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	115 LF		
0170	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	50 LF		
0171	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	106.04 LF		
0172	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		

County : Yadkin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0173	8116000000-E	SP	CSL TUBES	720 LF		
0174	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (236+73.00 -L-)	Lump Sum	L.S.	
0175	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,487.4 SF		
0176	8161000000-E	420	GROOVING BRIDGE FLOORS	12,458.3 SF		
0177	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	142.8 CY		
0178	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (236+73.00 -L-)	Lump Sum	L.S.	
0179	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,718 LB		
0180	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,552 LB		
0181	8265000000-E	430	54" PRESTRESSED CONCRETE GIRDERS	1,439.09 LF		
0182	8364000000-E	450	HP12X53 STEEL PILES	550 LF		
0183	8503000000-E	460	CONCRETE BARRIER RAIL	415.83 LF		
0184	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	685 TON		
0185	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	761 SY		
0186	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0187	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1400/Nov10/Q1081279.91/D799196790000/E187			Total Amount Of Bid For Entire Project :			

**C201008 (R-3427)**  
YADKIN COUNTY

2/16/99

Contract No: C201008

County: Yadkin

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General