

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200906

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	2355000000-N	840	3	EA	FRAME WITH GRATE, STD 840.29	6012000000-E	1610	360	TON	SEDIMENT CONTROL STONE
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+80.00)	2556000000-E	846	340	LF	SHOULDER BERM GUTTER	6015000000-E	1615	4.5	ACR	TEMPORARY MULCHING
0043000000-N	226	Lump Sum		GRADING	3030000000-E	862	600	LF	STEEL BM GUARDRAIL	6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6021000000-E	1620	0.75	TON	FERTILIZER FOR TEMPORARY SEEDING
0134000000-E	240	3.5	CY	DRAINAGE DITCH EXCAVATION	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6024000000-E	1622	40	LF	TEMPORARY SLOPE DRAINS
0318000000-E	300	37	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6027000000-N	1622	3	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
0343000000-E	310	148	LF	15" SIDE DRAIN PIPE	3557000000-E	866	225	LF	ADDITIONAL BARBED WIRE	6030000000-E	1630	1,000	CY	SILT EXCAVATION
0366000000-E	310	148	LF	15" RC PIPE CULVERTS, CLASS III	3559000000-E	866	225	LF	** STRAND BARBED WIRE FENCE WITH POSTS (5)	6036000000-E	1631	2,020	SY	MATTING FOR EROSION CONTROL
0708000000-E	310	45	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	3563000000-E	SP	165	LF	TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (48")	6042000000-E	1632	360	LF	1/4" HARDWARE CLOTH
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	3565000000-E	866	1	EA	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (48" HIGH, 10' WIDE, 20' OPEN)	6070000000-N	SP	6	EA	SPECIAL STILLING BASINS
1121000000-E	520	500	TON	AGGREGATE BASE COURSE	3649000000-E	876	20	TON	PLAIN RIP RAP, CLASS B	6084000000-E	1660	5	ACR	SEEDING & MULCHING
1220000000-E	545	200	TON	INCIDENTAL STONE BASE	3656000000-E	876	525	SY	FILTER FABRIC FOR DRAINAGE	6087000000-E	1660	2.5	ACR	MOWING
1275000000-E	600	370	GAL	PRIME COAT	3659000000-N	SP	2	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
1489000000-E	610	785	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4400000000-E	1110	98	SF	WORK ZONE SIGNS (STATIONARY)	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1498000000-E	610	700	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4405000000-E	1110	96	SF	WORK ZONE SIGNS (PORTABLE)	6096000000-E	1662	100	LB	SEED FOR SUPPLEMENTAL SEEDING
1514000000-E	610	810	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5A	4410000000-E	1110	36	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6108000000-E	1665	3.75	TON	FERTILIZER TOPDRESSING
1560000000-E	620	125	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4430000000-N	1130	70	EA	DRUMS	6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
1693000000-E	654	10	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4435000000-N	1135	20	EA	CONES	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
2000000000-N	806	37	EA	RIGHT OF WAY MARKERS	4445000000-E	1145	48	LF	BARRICADES (TYPE III)	6123000000-E	1670	0.5	ACR	REFORESTATION
2022000000-E	815	44.8	CY	SUBDRAIN EXCAVATION	4450000000-N	1150	384	HR	FLAGGER					
2033000000-E	815	33.6	CY	SUBDRAIN FINE AGGREGATE	4475000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)					
2044000000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE	4810000000-E	1205	36,960	LF	PAINT PAVEMENT MARKING LINES (4")					
2055000000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6000000000-E	1605	1,025	LF	TEMPORARY SILT FENCE					
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	6006000000-E	1610	120	TON	STONE FOR EROSION CONTROL, CLASS A					
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	6009000000-E	1610	460	TON	STONE FOR EROSION CONTROL, CLASS B					
2286000000-N	840	3	EA	MASONRY DRAINAGE STRUCTURES										

5/28/99

15-MAR-2004 10:53 AM
R:\Roadway\Proj\AT\RD187132\DRAINS\SUM.DGN