

SUMMARY OF QUANTITIES



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200908

| ItemNumber | Sec # | Quantity | Unit | Description | ItemNumber | Sec # | Quantity | Unit | Description | ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|---|-------------|-------|----------|------|--|-------------|-------|----------|------|---|
| 000100000-N | 800 | Lump Sum | | MOBILIZATION | 327000000-N | SP | 4 | EA | GUARDRAIL ANCHOR UNITS, TYPE 350 | 556400000-E | SP | 1 | EA | *** BUTTERFLY VALVE & VALVE BOX (16") |
| 004300000-N | 226 | Lump Sum | | GRADING | 362800000-E | 876 | 65 | TON | PLAIN RIP RAP, CLASS I | 558200000-E | 1510 | 1 | EA | ***X*** TAPPING SADDLE (16", 3/4") |
| 005000000-E | 226 | 1 | ACR | SUPPLEMENTARY CLEARING & GRUBBING | 364900000-E | 876 | 7 | TON | PLAIN RIP RAP, CLASS B | 558200000-E | 1510 | 2 | EA | ***X*** TAPPING SADDLE (6", 3/4") |
| 013400000-E | 240 | 80 | CY | DRAINAGE DITCH EXCAVATION | 365600000-E | 876 | 350 | SY | FILTER FABRIC FOR DRAINAGE | 564800000-N | 1510 | 3 | EA | RELOCATE EXISTING WATER METER |
| 031800000-E | 300 | 40 | TON | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 440000000-E | 1110 | 359 | SF | WORK ZONE SIGNS (STATIONARY) | 566600000-E | 1510 | 1 | EA | FIRE HYDRANT, ****# WP (200#) |
| 036600000-E | 310 | 100 | LF | 15" RC PIPE CULVERTS, CLASS III | 441000000-E | 1110 | 94 | SF | WORK ZONE SIGNS (BARRICADE MOUNTED) | 567200000-N | 1510 | 1 | EA | RELOCATE EXISTING FIRE HYDRANT |
| 037200000-E | 310 | 272 | LF | 18" RC PIPE CULVERTS, CLASS III | 442500000-N | 1125 | 4 | EA | WARNING FLAG SETS | 581000000-E | 1530 | 518 | LF | FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI) |
| 099500000-E | 340 | 48 | LF | PIPE REMOVAL | 443000000-N | 1130 | 25 | EA | DRUMS | 600000000-E | 1605 | 370 | LF | TEMPORARY SILT FENCE |
| 112100000-E | 520 | 22 | TON | AGGREGATE BASE COURSE | 443500000-N | 1135 | 15 | EA | CONES | 600600000-E | 1610 | 75 | TON | STONE FOR EROSION CONTROL, CLASS A |
| 122000000-E | 545 | 100 | TON | INCIDENTAL STONE BASE | 444500000-E | 1145 | 96 | LF | BARRICADES (TYPE III) | 600900000-E | 1610 | 160 | TON | STONE FOR EROSION CONTROL, CLASS B |
| 148900000-E | 610 | 400 | TON | ASPHALT CONC BASE COURSE, TYPE B25.0B | 445000000-N | 1150 | 80 | HR | FLAGGER | 601200000-E | 1610 | 70 | TON | SEDIMENT CONTROL STONE |
| 149800000-E | 610 | 225 | TON | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 481000000-E | 1205 | 4,702 | LF | PAINT PAVEMENT MARKING LINES (4") | 601500000-E | 1615 | 1.5 | ACR | TEMPORARY MULCHING |
| 152500000-E | SP | 195 | TON | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 483000000-E | 1205 | 90 | LF | PAINT PAVEMENT MARKING LINES (16") | 601800000-E | 1620 | 50 | LB | SEED FOR TEMPORARY SEEDING |
| 156000000-E | 620 | 41 | TON | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 483500000-E | 1205 | 70 | LF | PAINT PAVEMENT MARKING LINES (24") | 602100000-E | 1620 | 0.25 | TON | FERTILIZER FOR TEMPORARY SEEDING |
| 169300000-E | 654 | 17 | TON | ASPHALT PLANT MIX, PAVEMENT REPAIR | 484000000-N | 1205 | 4 | EA | PAINT PAVEMENT MARKING CHARACTER | 603000000-E | 1630 | 335 | CY | SILT EXCAVATION |
| 200000000-N | 806 | 16 | EA | RIGHT OF WAY MARKERS | 530000000-E | 1505 | 52 | TON | FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI) | 603600000-E | 1631 | 835 | SY | MATTING FOR EROSION CONTROL |
| 226400000-E | 840 | 0.1 | CY | PIPE PLUGS | 530600000-E | SP | 52 | TON | BEDDING MATERIAL, UTILITIES CLASS ***** (IV) | 604200000-E | 1632 | 60 | LF | 1/4" HARDWARE CLOTH |
| 228600000-N | 840 | 3 | EA | MASONRY DRAINAGE STRUCTURES | 536600000-E | 1510 | 447.2 | LF | 6" DI WATER PIPE, PC 350 | 604500000-E | SP | 140 | LF | *** TEMPORARY PIPE (24") |
| 236420000-N | 840 | 3 | EA | FRAME WITH TWO GRATES, STD 840.20 | 538400000-E | 1510 | 528.8 | LF | 16" DI WATER PIPE, PC ***** (250) | 606900000-E | 1638 | 34 | CY | STILLING BASINS |
| 257700000-E | 846 | 355 | LF | CONCRETE EXPRESSWAY GUTTER | 541400000-E | 1510 | 14 | LF | 3/4" COPPER WATER PIPE, TYPE K | 608400000-E | 1660 | 1.5 | ACR | SEEDING & MULCHING |
| 283000000-N | 858 | 1 | EA | ADJUSTMENT OF MANHOLES | 548000000-E | 1510 | 3,465 | LB | DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP | 608700000-E | 1660 | 1 | ACR | MOWING |
| 284500000-N | 858 | 2 | EA | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 551000000-E | 1510 | 3 | EA | 3/4" CORPORATION STOP | 609000000-E | 1661 | 50 | LB | SEED FOR REPAIR SEEDING |
| 303000000-E | 862 | 350 | LF | STEEL BM GUARDRAIL | 554000000-E | 1510 | 7 | EA | 6" GATE VALVE & VALVE BOX, 200# WP | 609300000-E | 1661 | 0.25 | TON | FERTILIZER FOR REPAIR SEEDING |
| 315000000-N | 862 | 5 | EA | ADDITIONAL GUARDRAIL POSTS | | | | | | 609600000-E | 1662 | 50 | LB | SEED FOR SUPPLEMENTAL SEEDING |
| | | | | | | | | | | 611100000-E | SP | 85 | LF | IMPERVIOUS DIKE |
| | | | | | | | | | | 611400000-N | SP | 1.5 | HR | SPECIALIZED HAND MOWING |
| | | | | | | | | | | 611700000-N | 1675 | 8 | EA | RESPONSE FOR EROSION CONTROL |