

PROJ. NO. - 8.2495501
ID NO. - B-3649
COUNTY - GUILFORD

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	16' RT	16+60	2.80-4.30	A-7-6(6)	47	19	28.3	23.5	23.9	24.3	89	71	48	-	-
SS-2	16' RT	16+60	8.40-9.30	A-4(0)	33	NP	9.1	59.7	25.1	6.1	100	99	46	-	-
SS-3	16' RT	16+60	12.80-14.30	A-6(3)	35	15	33.6	24.3	15.8	26.3	97	76	45	-	-

B2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-11	11' LT	17+64	2.60-4.10	A-6(8)	40	15	17.4	25.1	27.1	30.4	96	86	62	-	-
SS-12	11' LT	17+64	7.60-9.10	A-4(0)	21	6	28.9	33.4	19.4	18.2	96	81	41	-	-

B2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-6	19' RT	17+84	6.30-7.80	A-2-6(0)	30	12	43.7	23.9	12.1	20.2	70	49	26	-	-
SS-7	19' RT	17+84	11.30-12.30	A-2-4(0)	20	NP	51.2	31.4	7.3	10.1	92	70	18	-	-
SS-8	19' RT	17+84	12.30-12.80	A-1-b(0)	23	NP	65.6	22.5	7.9	4.0	86	44	12	-	-

EB2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-9	23' LT	18+00	2.70-3.40	A-2-4(0)	22	4	33.8	33.0	17.0	16.2	91	72	35	-	-
SS-10	23' LT	18+00	3.40-4.20	A-4(3)	37	10	9.5	49.4	18.8	22.3	100	97	50	-	-

EB2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-4	22' RT	18+29	2.80-4.30	A-2-4(0)	29	NP	30.8	52.6	12.6	4.0	100	92	23	-	-
SS-5	22' RT	18+29	7.80-9.30	A-4(0)	21	7	33.0	30.0	18.8	18.2	99	80	41	-	-