

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT _ U-2734

COUNTY NewHanover

DATE: 01/08/04

SHEET 1 OF 2 SHEETS

RD10S01C

LINE	STATION	STATION	TOTAL EXCAV. (UNCL.)	ROCK EXCAV.	UNDERCUT	UNSUIT. EXCAV.	SUITABLE EXCAV.	TOTAL EMB.	ROCK EMB.	EARTH EMB.	EMBANK. 25%	BORROW	SUITABLE WASTE	UNSUIT. WASTE	TOTAL WASTE
Summary No. 1															
-L- RT.	13+20	22+20	1363		1630	1766	1227	3257		1627	4071	2844		1766	1766
-L- LT.	(CONST. BY OTHERS)														
GRASSED MEDIAN ISLAND								521		521	651	651			
Summary Subtotal			1363			1766	1227	3778		2148	4722	3495		1766	1766
Summary No. 2															
-L- LT.	27+80	31+20	1742			174	1568	2830		2830	3538	1970		174	174
-L- RT.	22+20	31+20	1355		2030	2165	1220	11710		9680	14638	13418		2165	2165
GRASSED MEDIAN ISLAND								1381		1381	1726				
Summary Subtotal			3097		2030	2339	2788	15921		13891	19902	17114		2339	2339
Summary No. 3															
-L- LT.	31+20	40+20	989		890	989	890	4970		4080	6213	5323		989	989
-L- RT.	31+20	40+20	1665		200	366	1499	4299		4099	5374	3875		366	366
-Y3-	10+00	11+00	10			1	9	302		302	378	369		1	1
-Y4-	(CONST. BY OTHERS)														
-Y10-	9+80	11+40	463			46	417	48		48	60		357	46	403
GRASSED MEDIAN ISLAND								583		583	729	729			
Summary Subtotal			3127		1090	1402	2815	10202		9112	12754	10296	357	1402	1759
Summary No. 4															
-L- LT.	40+20	49+20	2394			239	2155	2152		2152	2690	535		239	239
-L- RT.	40+20	49+20	558			56	502	3267		3267	4084	3582		56	56
-Y5-	10+00	11+16	289			29	260	335		335	419	159		29	29
-Y13-	10+10	10+42	54			5	49	22		22	28		21	5	26
-Y6-	10+10	10+30	28			3	25	6		6	8		17	3	20
GRASSED MEDIAN ISLAND								1057		1057	1321	1321			
Summary Subtotal			3323			332	2991	6839		6839	8550	5597	38	332	370
SHEET TOTALS:			10910		3120	5839	9821	36740		31990	45928	36502	395	5839	6234