

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201072														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29	6030000000-E	1630	350	CY	SILT EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+37.40)	2556000000-E	846	35	LF	SHOULDER BERM GUTTER	6036000000-E	1631	900	SY	MATTING FOR EROSION CONTROL
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	3030000000-E	862	475	LF	STEEL BM GUARDRAIL	6038000000-E	SP	180	SY	PERMANENT SOIL REINFORCEMENT MAT
0057000000-E	226	200	CY	UNDERCUT EXCAVATION	3045000000-E	862	50	LF	STEEL BM GUARDRAIL, SHOP CURVED	6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
0063000000-N	SP	Lump Sum		GRADING	3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	6070000000-N	SP	10	EA	SPECIAL STILLING BASINS
0106000000-E	230	4,300	CY	BORROW EXCAVATION	3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	6084000000-E	1660	3	ACR	SEEDING & MULCHING
0134000000-E	240	90	CY	DRAINAGE DITCH EXCAVATION	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6087000000-E	1660	1.5	ACR	MOWING
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL	3270000000-N	SP	5	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	3628000000-E	876	40	TON	PLAIN RIP RAP, CLASS I	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
0318000000-E	300	27	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3649000000-E	876	209	TON	PLAIN RIP RAP, CLASS B	6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
0343000000-E	310	64	LF	15" SIDE DRAIN PIPE	3656000000-E	876	1,058	SY	FILTER FABRIC FOR DRAINAGE	6108000000-E	1665	2	TON	FERTILIZER TOPDRESSING
0344000000-E	310	24	LF	18" SIDE DRAIN PIPE	3656000000-E	876	1,058	SY	FILTER FABRIC FOR DRAINAGE	6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
0414000000-E	310	104	LF	60" RC PIPE CULVERTS, CLASS III	4400000000-E	1110	426	SF	WORK ZONE SIGNS (STATIONARY)	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
0708000000-E	310	56	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4410000000-E	1110	57	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)					
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4425000000-N	1125	4	EA	WARNING FLAG SETS					
0995000000-E	340	107	LF	PIPE REMOVAL	4445000000-E	1145	96	LF	BARRICADES (TYPE III)					
1121000000-E	520	12	TON	AGGREGATE BASE COURSE	4810000000-E	1205	6,200	LF	PAINT PAVEMENT MARKING LINES (4")					
1220000000-E	545	300	TON	INCIDENTAL STONE BASE	6000000000-E	1605	470	LF	TEMPORARY SILT FENCE					
1489000000-E	610	320	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A					
1498000000-E	610	280	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	6009000000-E	1610	300	TON	STONE FOR EROSION CONTROL, CLASS B					
1525000000-E	SP	180	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6012000000-E	1610	315	TON	SEDIMENT CONTROL STONE					
1560000000-E	620	39	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6015000000-E	1615	2.5	ACR	TEMPORARY MULCHING					
2000000000-N	806	13	EA	RIGHT OF WAY MARKERS	6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING					
2220000000-E	838	11.4	CY	REINFORCED ENDWALLS	6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING					
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES	6024000000-E	1622	125	LF	TEMPORARY SLOPE DRAINS					
					6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					