

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+92.40)	Lump Sum	L.S.	
0004	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0005	0057000000-M	226	UNDERCUT EXCAVATION	1,000 M3		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-M	230	BORROW EXCAVATION	88,000 M3		
0008	0134000000-M	240	DRAINAGE DITCH EXCAVATION	336 M3		
0009	0195000000-M	265	SELECT GRANULAR MATERIAL	2,000 M3		
0010	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	2,000 M2		
0011	0199000000-M	SP	TEMPORARY SHORING	700 M2		
0012	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	52 MTN		
0013	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	7.2 M		
0014	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	62.4 M		
0015	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (1650MM)	18 M		
0016	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (750MM)	50.4 M		
0017	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	26.4 M		
0018	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	4 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-M	340	PIPE REMOVAL	6 M		
0020	1121000000-M	520	AGGREGATE BASE COURSE	151 MTN		
0021	1220000000-M	545	INCIDENTAL STONE BASE	300 MTN		
0022	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,640 MTN		
0023	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,095 MTN		
0024	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,476 MTN		
0025	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	451 MTN		
0026	2220000000-M	838	REINFORCED ENDWALLS	4.8 M3		
0027	2253000000-M	840	PIPE COLLARS	2.68 M3		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0029	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0030	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0031	2619000000-M	850	100MM CONCRETE PAVED DITCH	18 M2		
0032	3030000000-M	862	STEEL BM GUARDRAIL	803.91 M		
0033	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	60.96 M		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3345000000-M	864	REMOVE & RESET EXISTING GUARD-RAIL	15.24 M		
0039	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	2 EA		
0040	3559000000-M	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	360 M		
0041	3569000000-M	867	BARBED WIRE FENCE RESET	360 M		
0042	3649000000-M	876	PLAIN RIP RAP, CLASS B	26.3 MTN		
0043	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	200 M2		
0044	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	30 M2		
0045	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	9 M2		
0046	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	10 M2		
0047	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0048	4430000000-N	1130	DRUMS	61 EA		
0049	4445000000-M	1145	BARRICADES (TYPE III)	50 M		
0050	4450000000-N	1150	FLAGGER	32 HR		
0051	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0052	4485000000-M	1170	PORTABLE CONCRETE BARRIER	95 M		
0053	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	1,157 M		
0054	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	2,322 M		
0055	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	73 M		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	18 M		
0057	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	7 EA		
0058	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	80 EA		
0059	5300000000-M	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	220 MTN		
0060	5306000000-M	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	220 MTN		
0061	5318000000-M	1505	PAVEMENT REPAIR FOR UTILITY WORK	7.6 MTN		
0062	5324000000-M	1510	***MM DI WATER PIPE, CLASS ***** WP (250MM, 52 2.41MPA)	396.8 M		
0063	5414000000-M	1510	20MM COPPER WATER PIPE, TYPE K	45 M		
0064	5444000000-M	1510	150MM PVC WATER PIPE, SDR 21, 1.38MPA WP	4.5 M		
0065	5456000000-M	1510	250MM PVC WATER PIPE, SDR 21, 1.38MPA WP	615.7 M		
0066	5480000000-M	1510	DUCTILE IRON WATER PIPE FITTINGS, 1.72MPA MIN WP	680 KG		
0067	5510000000-M	1510	20MM CORPORATION STOP	3 EA		
0068	5540000000-M	1510	150MM GATE VALVE & VALVE BOX, 1.38MPA WP	1 EA		
0069	5552000000-M	1510	250MM GATE VALVE & VALVE BOX, ****MPA WP (1.38MPA)	4 EA		
0070	5612000000-M	1510	***MM TRANSITION COUPLING, ***** (250MM, AC TO PVC)	2 EA		
0071	5648000000-N	1510	RELOCATE EXISTING WATER METER	3 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1	EA	
0073	5798000000-M	1530	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (250MM, AC WATER LINE)	979	M	
0074	5888000000-M	SP	GENERIC UTILITY ITEM 600MM STEEL ENCASEMENT PIPE, 9.52MM THICK, BY BORING & JACKING	55	M	
0075	6000000000-M	1605	TEMPORARY SILT FENCE	1,020	M	
0076	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	70	MTN	
0077	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	795	MTN	
0078	6012000000-M	1610	SEDIMENT CONTROL STONE	260	MTN	
0079	6015000000-M	1615	TEMPORARY MULCHING	1	HA	
0080	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	125	KG	
0081	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	1	MTN	
0082	6024000000-M	1622	TEMPORARY SLOPE DRAINS	310	M	
0083	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	14	EA	
0084	6030000000-M	1630	SILT EXCAVATION	4,745	M3	
0085	6036000000-M	1631	MATTING FOR EROSION CONTROL	2,370	M2	
0086	6042000000-M	1632	6.4MM HARDWARE CLOTH	20	M	
0087	6084000000-M	1660	SEEDING & MULCHING	3	HA	
0088	6087000000-M	1660	MOWING	0.5	HA	
0089	6090000000-M	1661	SEED FOR REPAIR SEEDING	25	KG	

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25	MTN	
0091	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	100	KG	
0092	6108000000-M	1665	FERTILIZER TOPDRESSING	5	MTN	
0093	6114000000-N	SP	SPECIALIZED HAND MOWING	6.5	HR	
0094	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	
0095	6123000000-M	1670	REFORESTATION	0.61	HA	
STRUCTURE ITEMS						
0096	8042000000-N	402	REMOVAL OF EXISTING STRUCTURES AT STATION ***** (14+94.156-L-)	Lump Sum	L.S.	
0097	8105500000-M	SP	****MM DIA DRILLED PIERS IN SOIL (1220MM)	23.5	M	
0098	8105600000-M	SP	****MM DIA DRILLED PIERS NOT IN SOIL (1220MM)	17	M	
0099	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1	EA	
0100	8116000000-M	SP	CSL TUBES	182.4	M	
0101	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	930.5	M2	
0102	8161000000-M	420	GROOVING BRIDGE FLOORS	985.3	M2	
0103	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	138.5	M3	
0104	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+94.156-L-)	Lump Sum	L.S.	
0105	8217000000-M	425	REINFORCING STEEL (BRIDGE)	18,607	KG	

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,920 KG		
0107	8280000000-M	440	APPROX KG STRUCTURAL STEEL	116,900 LS		
0108	8364000000-M	450	HP310X79 STEEL PILES	168 M		
0109	8503000000-M	460	CONCRETE BARRIER RAIL	136.92 M		
0110	8531000000-M	462	100MM SLOPE PROTECTION	2,070 M2		
0111	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0112	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0842/Aug16/Q266407.27/D492683600000/E112

Total Amount Of Bid For Entire Project :

C200954
ANSON COUNTY

2/16/99

Contract No: **C200954**

Counties: **Anson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General