

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (20+93.60)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	500 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	155 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	16 LF		
0014	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	236 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	344 LF		
0016	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	296 LF		
0017	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	136 LF		
0018	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	112 LF		

County: Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	304 LF		
0020	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6 EA		
0021	0986000000-E	SP	GENERIC PIPE ITEM 30" RC PIPE CULVERTS, CLASS IV (BY BORING& JACKING)	40 LF		
0022	0995000000-E	340	PIPE REMOVAL	38 LF		
0023	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,300 TON		
0025	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	800 TON		
0026	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	900 TON		
0027	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	150 TON		
0028	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0029	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0030	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0031	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0032	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0033	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0034	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0035	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0036	2220000000-E	838	REINFORCED ENDWALLS	4.1 CY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2264000000-E	840	PIPE PLUGS	0.36 CY		
0038	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	11 EA		
0039	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0040	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	8 EA		
0041	2462000000-E	SP	*** SLUICE GATE (22")	2 EA		
0042	2474000000-N	SP	GENERIC DRAINAGE ITEM HAZARDOUS SPILL BASIN	Lump Sum	L.S.	
0043	2556000000-E	846	SHOULDER BERM GUTTER	950 LF		
0044	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	300 LF		
0045	3030000000-E	862	STEEL BM GUARDRAIL	1,175 LF		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0048	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0049	3649000000-E	876	PLAIN RIP RAP, CLASS B	125 TON		
0050	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,000 SY		
0051	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0052	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	169 SF		
0053	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0054	4430000000-N	1130	DRUMS	39 EA		
0055	4435000000-N	1135	CONES	39 EA		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4455000000-N	1150	FLAGGER	60 MD		
0057	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0058	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	1 EA		
0059	4485000000-E	1170	PORTABLE CONCRETE BARRIER	300 LF		
0060	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	49 EA		
0061	4730000000-E	1205	EPOXY PAVEMENT MARKING LINES (4")	7,800 LF		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,600 LF		
0063	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	300 LF		
0064	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	4 EA		
0065	4905000000-N	1253	SNOWPLOWABLE RAISED PAVEMENT MARKERS	20 EA		
0066	6000000000-E	1605	TEMPORARY SILT FENCE	1,425 LF		
0067	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0068	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	430 TON		
0069	6012000000-E	1610	SEDIMENT CONTROL STONE	450 TON		
0070	6015000000-E	1615	TEMPORARY MULCHING	7 ACR		
0071	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0072	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0073	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75 LF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0075	6030000000-E	1630	SILT EXCAVATION	1,445	CY	
0076	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000	SY	
0077	6042000000-E	1632	1/4" HARDWARE CLOTH	200	LF	
0078	6070000000-N	SP	SPECIAL STILLING BASINS	12	EA	
0079	6084000000-E	1660	SEEDING & MULCHING	9	ACR	
0080	6087000000-E	1660	MOWING	4	ACR	
0081	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0082	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0083	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175	LB	
0084	6108000000-E	1665	FERTILIZER TOPDRESSING	6.5	TON	
0085	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5	HR	
0086	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8	EA	

STRUCTURE ITEMS

0087	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (20+93.60 -L-)	Lump Sum	L.S.	
0088	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (20+93.60 -L-)	Lump Sum	L.S.	
0089	8084000000-N	410	FOUNDATION EXCAVATION FOR END BENT ** AT STATION ***** (1, 20+93.60 -L-)	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8105500000-E	SP	***_*** DIA DRILLED PIERS IN SOIL (6'-0")	5.08	LF	
0091	8105600000-E	SP	***_*** DIA DRILLED PIERS NOT IN SOIL (6'-0")	18	LF	
0092	8111000000-E	SP	PERMANENT STEEL CASING FOR ***_*** DIA DRILLED PIER (6'-0")	7.08	LF	
0093	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2	EA	
0094	8116000000-E	SP	CSL TUBES	150	LF	
0095	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,612	SF	
0096	8161000000-E	420	GROOVING BRIDGE FLOORS	11,497	SF	
0097	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	204	CY	
0098	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (20+93.60 -L-)	Lump Sum	L.S.	
0099	8217000000-E	425	REINFORCING STEEL (BRIDGE)	50,280	LB	
0100	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,691	LB	
0101	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	307,100	LS	
0102	8364000000-E	450	HP12X53 STEEL PILES	300	LF	
0103	8391000000-N	450	STEEL PILE POINTS	10	EA	
0104	8503000000-E	460	CONCRETE BARRIER RAIL	623.48	LF	
0105	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	890	TON	
0106	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	985	SY	
0107	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0109	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0110	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
1149/Aug11/Q429472.35/D466648600000/E110			Total Amount Of Bid For Entire Project :			

Contract No: **C200892**

Counties: **Ashe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General