

B-3623**Project Special Provisions
Erosion Control****Cabarrus County****Seeding And Mulching****(6)**

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

August 1 - June 1

100# (110kg) Tall Fescue
 15# (17kg) Kentucky Bluegrass
 15# (17kg) Hard Fescue
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

May 1 - September 1

100# (110kg) Tall Fescue
 15# (17kg) Kentucky Bluegrass
 15# (17kg) Hard Fescue
 25# (28kg) Kobe or Korean Lespedeza
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

Adventure	Adventure II	Amigo	Anthem
Apache	Apache II	Arid	Austin
Brookstone	Bonanza	Bonanza II	Chapel Hill
Chesapeake	Chieftain	Coronado	Crossfire II
Debutante	Duster	Falcon	Falcon II
Finelawn Petite	Finelawn	Finelawn I	Genesis
Grande	Guardian	Houndog	Jaguar
Jaguar III	Kentucky 31	Kitty Hawk	Monarch
Montauk	Mustang	Olympic	Pacer
Phoenix	Pixie	Pyramid	Rebel
Rebel Jr.	Rebel II	Renegade	Safari
Shenandoah	Tempo	Titan	Tomahawk
Trailblazer	Tribute	Vegas	Wolfpack
Wrangler			

Approved Kentucky Bluegrass Cultivars:

Adelphi	Baron	Bristol	Challenger
Columbia	Fylking	Glade	Kenblue
Merit	Plush	Ram I	Rugby
Sydspport	Touchdown	Vantage	

Approved Hard Fescue Cultivars:

Aurora	Bardur	Crystal	Reliant	Scaldis
--------	--------	---------	---------	---------

Spartan

Valda

Waldina

Warwick

On cut and fill slopes 2:1 or steeper add 25# (28kg) Rye Grain November 1 - March 1.

On cut and fill slopes 2:1 or steeper add 30# (35 kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.

Temporary Seeding:

Fertilizer shall be the same analysis as specified for "Seeding and Mulching" and applied at the rate of 400 pounds (450kg) and seeded at the rate of 50 pounds per acre (55kg per hectare). Kobe or Korean Lespedeza, German Millet, or Browntop Millet shall be used in summer months and rye grain during the remainder of the year. The Engineer will determine the exact dates for using each kind of seed.

Fertilizer Topdressing:

Fertilizer used for topdressing shall be 16-8-8 grade and shall be applied at the rate of 500 pounds per acre (560 kg per hectare). Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 2-1-1 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as 16-8-8 analysis.

Supplemental Seeding:

The kinds of seed and proportions shall be the same as specified for "Seeding and Mulching", and the rate of application may vary from 25# to 75# per acre (28kg to 85kg per hectare). The actual rate per acre (hectare) will be determined by the Engineer prior to the time of topdressing and the Contractor will be notified in writing of the rate per acre (hectare), total quantity needed, and areas on which to apply the supplemental seed. Minimum tillage equipment, consisting of a sod seeder shall be used for incorporating seed into the soil as to prevent disturbance of existing vegetation. A clodbuster (ball and chain) may be used where degree of slope prevents the use of a sod seeder.

Mowing:

The minimum mowing height on this project shall be six inches (150 mm).

Specialized Hand Mowing:

The work covered by this section consists of specialized hand mowing around or under fixed objects, including but not limited to guardrails, signs, barriers and slopes in a method acceptable to the Engineer.

The work of specialized hand mowing shall be completed with mechanically powered trimmers, string trimmers, hand operated rotary mowers, or self-propelled mowers of sufficient size and quality to perform the work timely and efficiently.

The quantity of mowing to be performed will be affected by the actual conditions which occur during the construction of the project. The quantity of mowing may be increased, decreased or eliminated entirely at the direction of the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

The quantity of specialized hand mowing to be paid for will be the actual number of man hours worked while hand mowing along the surface of the ground, at the direction of the Engineer. Where an area has been mowed more than once, at the direction of the Engineer, separate measurement will be made each time the area is mowed.

Payment will be made under:

Specialized Hand MowingHR

Minimize Removal Of Vegetation

The Contractor shall minimize removal of vegetation at stream banks and disturbed areas within the project limits as directed by the Engineer.

Stockpile Areas

The Contractor shall install and maintain erosion control devices sufficient to contain sediment around any erodible material stockpile areas as directed by the Engineer.

Reforestation:

Reforestation will be planted within pavement removal areas and in areas designated by the Engineer. Reforestation is not shown on the plan sheets. See the reforestation detail sheet.

Seasonal limitations: Seedlings shall be planted from November 15 through March 15.

Seedlings shall be planted as soon as practical following permanent Seeding and Mulching. Seedlings shall be planted in a 16 ft. (5 meters) wide swath adjacent to mowing pattern line.

Root dip: The roots of reforestation seedlings shall be coated with a slurry of water, and either a fine clay ("kaolin") or a superabsorbent that is made to be used as a bare root dip. The type, mixture ratio, method of application, and the time of application shall be submitted to the Engineer for approval. With the approval of the Engineer, seedlings may be coated before delivery to the job or at the time of planting, but at no time shall the

roots of the seedlings be allowed to dry out. The roots shall be moistened immediately prior to planting.

Waste Areas And Borrow Sources:

Payment for temporary erosion control measures, except those made necessary by the Contractor's own negligence or for his own convenience, will be paid for at the appropriate contract unit price for the devices or measures utilized in borrow sources and waste areas.

No additional payment will be made for erosion control devices or permanent seeding and mulching in any commercial borrow or waste pit. All erosion and sediment control practices which may be required on a commercial borrow or waste site will be done at the Contractor's expense.

Temporary Diversion:

The work by this section for installation, maintenance, and cleanout of temporary diversions shall be in accordance with Section 1630. The quantity of excavation for installation and cleanout measured as provided in Article 1630-4 will be paid for at the contract unit price per cubic yard (cubic meter) as provided in Article 1630-5 for "Silt Excavation".