

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+37.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	200 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	18 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	64 LF		
0015	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	44 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0017	0995000000-E	340	PIPE REMOVAL	86 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	72 TON		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,210 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	610 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	680 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	125 TON		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0027	3030000000-E	862	STEEL BM GUARDRAIL	387.5 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0030	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0031	3566000000-E	867	WOVEN WIRE FENCE RESET	250 LF		
0032	3569000000-E	867	BARBED WIRE FENCE RESET	340 LF		
0033	3649000000-E	876	PLAIN RIP RAP, CLASS B	220 TON		
0034	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	760 SY		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	52 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	50 SF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4430000000-N	1130	DRUMS	20 EA		
0039	4435000000-N	1135	CONES	40 EA		
0040	4445000000-E	1145	BARRICADES (TYPE III)	50 LF		
0041	4450000000-N	1150	FLAGGER	256 HR		
0042	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	3 EA		
0043	4485000000-E	1170	PORTABLE CONCRETE BARRIER	370 LF		
0044	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	94 EA		
0045	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,810 LF		
0046	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,810 LF		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	29,712 LF		
0048	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	36 EA		
0049	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	230 TON		
0050	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	230 TON		
0051	5360000000-E	1510	6" DI WATER PIPE, PC 350	100 LF		
0052	5384000000-E	1510	16" DI WATER PIPE, PC ***** (PC 350)	864 LF		
0053	5480000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	2,025 LB		
0054	5594000000-E	SP	*** AIR RELEASE VALVE & MAN-HOLE (2")	1 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1		EA
0056	5756000000-E	1520	DUCTILE IRON SEWER PIPE FITTINGS, ***** (PC 350)	440		LB
0057	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (8", PVC C-900 DR 18)	290		LF
0058	5810000000-E	1530	FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI WATER PIPE)	856		LF
0059	5882000000-N	SP	GENERIC UTILITY ITEM 6" RESTRAINED RETAINER GLAND	2		EA
0060	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI FORCE MAIN SEWER PIPE, CL 50	292		LF
0061	6000000000-E	1605	TEMPORARY SILT FENCE	1,795		LF
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	60		TON
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	380		TON
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	120		TON
0065	6015000000-E	1615	TEMPORARY MULCHING	5		ACR
0066	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200		LB
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75		TON
0068	6024000000-E	1622	TEMPORARY SLOPE DRAINS	175		LF
0069	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4		EA
0070	6030000000-E	1630	SILT EXCAVATION	575		CY
0071	6033000000-E	1631	SYNTHETIC ROVING	518		SY

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6036000000-E	1631	MATTING FOR EROSION CONTROL	830 SY		
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0074	6084000000-E	1660	SEEDING & MULCHING	6.5 ACR		
0075	6087000000-E	1660	MOWING	3 ACR		
0076	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0077	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0078	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0079	6108000000-E	1665	FERTILIZER TOPDRESSING	5 TON		
0080	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0081	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	2 EA		
0082	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

0083	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+37.50 -L-)	Lump Sum	L.S.	
0084	8105500000-E	SP	***.***" DIA DRILLED PIERS IN SOIL (4'-0")	55 LF		
0085	8105600000-E	SP	***.***" DIA DRILLED PIERS NOT IN SOIL (4'-0")	26 LF		
0086	8111000000-E	SP	PERMANENT STEEL CASING FOR ***.***" DIA DRILLED PIER (4'-0")	49.6 LF		
0087	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0088	8116000000-E	SP	CSL TUBES	364 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,789 SF		
0090	8161000000-E	420	GROOVING BRIDGE FLOORS	8,537 SF		
0091	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	132.4 CY		
0092	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+37.50 -L-)	Lump Sum	L.S.	
0093	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,897 LB		
0094	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,729 LB		
0095	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	903.34 LF		
0096	8364000000-E	450	HP12X53 STEEL PILES	570 LF		
0097	8475000000-E	460	TWO BAR METAL RAIL	350.67 LF		
0098	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 30")	365.67 LF		
0099	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	1,140 TON		
0100	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,267 SY		
0101	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0102	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0716/Aug10/Q109827.43/D47744960000/E102

Total Amount Of Bid For Entire Project :

Contract No: C200828

Counties: Cabarrus County

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General