

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200961					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200961					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200961					STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200961				
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	1560000000-E	620	91	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	4650000000-N	1251	216	EA	TEMPORARY RAISED PAVEMENT MARKERS	6117000000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING	1693000000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	4810000000-E	1205	51,600	LF	PAINT PAVEMENT MARKING LINES (4")	6120000000-E	SP	80	CY	CULVERT DIVERSION CHANNEL
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+65.00)	2000000000-N	806	25	EA	RIGHT OF WAY MARKERS	6000000000-E	1605	1,660	LF	TEMPORARY SILT FENCE	6123000000-E	1670	1.5	ACR	REFORESTATION
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING	2286000000-N	840	10	EA	MASONRY DRAINAGE STRUCTURES	6006000000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS A					
0057000000-E	226	1,000	CY	UNDERCUT EXCAVATION	2367000000-N	840	10	EA	FRAME WITH TWO GRATES, STD 840.29	6009000000-E	1610	1,020	TON	STONE FOR EROSION CONTROL, CLASS B					
0063000000-N	SP	Lump Sum		GRADING	2486000000-E	SP	1,000	SF	GENERIC DRAINAGE ITEM SANDBAG HEADWALL	6012000000-E	1610	850	TON	SEDIMENT CONTROL STONE					
0106000000-E	230	14,200	CY	BORROW EXCAVATION	2556000000-E	846	2,350	LF	SHOULDER BERM GUTTER	6015000000-E	1615	6.5	ACR	TEMPORARY MULCHING					
0134000000-E	240	219	CY	DRAINAGE DITCH EXCAVATION	3030000000-E	862	2,375	LF	STEEL BM GUARDRAIL	6018000000-E	1620	250	LB	SEED FOR TEMPORARY SEEDING					
0195000000-E	265	400	CY	SELECT GRANULAR MATERIAL	3150000000-N	862	10	EA	ADDITIONAL GUARDRAIL POSTS	6021000000-E	1620	1	TON	FERTILIZER FOR TEMPORARY SEEDING					
0196000000-E	270	400	SY	FABRIC FOR SOIL STABILIZATION	3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	6024000000-E	1622	40	LF	TEMPORARY SLOPE DRAINS					
0199000000-E	SP	200	SF	TEMPORARY SHORING	3270000000-N	SP	8	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS					
0318000000-E	300	60	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	3380000000-E	862	1,525	LF	TEMPORARY STEEL BM GUARDRAIL	6030000000-E	1630	2,455	CY	SILT EXCAVATION					
0343000000-E	310	28	LF	15" SIDE DRAIN PIPE	3387000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)	6036000000-E	1631	3,820	SY	MATTING FOR EROSION CONTROL					
0345000000-E	310	36	LF	24" SIDE DRAIN PIPE	3389100000-N	SP	13	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6038000000-E	SP	25	SY	PERMANENT SOIL REINFORCEMENT MAT					
0366000000-E	310	132	LF	15" RC PIPE CULVERTS, CLASS III	3628000000-E	876	200	TON	PLAIN RIP RAP, CLASS I	6042000000-E	1632	200	LF	1/4" HARDWARE CLOTH					
0576000000-E	310	60	LF	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	3649000000-E	876	6	TON	PLAIN RIP RAP, CLASS B	6048000000-E	SP	100	SY	FLOATING TURBIDITY CURTAIN					
0576000000-E	310	168	LF	*** CS PIPE CULVERTS, ***** THICK (96", 0.168")	3656000000-E	876	1,627	SY	FILTER FABRIC FOR DRAINAGE	6069000000-E	1638	40	CY	STILLING BASINS					
0708000000-E	310	96	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4400000000-E	1110	276	SF	WORK ZONE SIGNS (STATIONARY)	6070000000-N	SP	16	EA	SPECIAL STILLING BASINS					
0995000000-E	340	228	LF	PIPE REMOVAL	4405000000-E	1110	224	SF	WORK ZONE SIGNS (PORTABLE)	6084000000-E	1660	7	ACR	SEEDING & MULCHING					
1121000000-E	520	1,100	TON	AGGREGATE BASE COURSE	4410000000-E	1110	72	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	6087000000-E	1660	4	ACR	MOWING					
1220000000-E	545	200	TON	INCIDENTAL STONE BASE	4430000000-N	1130	50	EA	DRUMS	6090000000-E	1661	100	LB	SEED FOR REPAIR SEEDING					
1275000000-E	600	1,070	GAL	PRIME COAT	4435000000-N	1135	50	EA	CONES	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING					
1489000000-E	610	750	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	4445000000-E	1145	96	LF	BARRICADES (TYPE III)	6096000000-E	1662	150	LB	SEED FOR SUPPLEMENTAL SEEDING					
1525000000-E	SP	900	TON	ASPHALT CONC SURFACE COURSE, TYPE SP9.5A	4455000000-N	1150	50	MD	FLAGGER	6108000000-E	1665	5.25	TON	FERTILIZER TOPDRESSING					
					4480000000-N	1165	1	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	6111000000-E	SP	150	LF	IMPERVIOUS DIKE					
										6114000000-N	SP	6	HR	SPECIALIZED HAND MOWING					

5/28/99

27-MAY-2004 08:00
R:\Pro\163629\rcu_sum.dgn
JBGauthier AT