

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0004	0001000000-M	200	CLEARING & GRUBBING ... HEC-TARE(S)	Lump Sum	L.S.	
0005	0008000000-M	200	SUPPLEMENTARY CLEARING & GRUB-BING	2 HA		
0006	0022000000-M	225	UNCLASSIFIED EXCAVATION	297,100 M3		
0007	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+04.666)	Lump Sum	L.S.	
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+83.346-L-)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (27+85.488)	Lump Sum	L.S.	
0010	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (97+00.000-L-)	Lump Sum	L.S.	
0011	0036000000-M	225	UNDERCUT EXCAVATION	26,959 M3		
0012	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA-TION	650 MTN		
0013	0106000000-M	230	BORROW EXCAVATION	433,000 M3		
0014	0134000000-M	240	DRAINAGE DITCH EXCAVATION	4,966 M3		
0015	0141000000-M	240	BERM DITCH CONSTRUCTION	745 M		
0016	0156000000-M	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	20,500 M2		
0017	0192000000-N	260	PROOF ROLLING	61 HR		
0018	0195000000-M	265	SELECT GRANULAR MATERIAL	1,500 M3		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	2,500 M2		
0020	0318000000-M	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	2,690 MTN		
0021	0343000000-M	310	375MM SIDE DRAIN PIPE	82.8 M		
0022	0344000000-M	310	450MM SIDE DRAIN PIPE	25.2 M		
0023	0345000000-M	310	600MM SIDE DRAIN PIPE	6 M		
0024	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	4,382.4 M		
0025	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	2,205.6 M		
0026	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	777.6 M		
0027	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	296.4 M		
0028	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	105.6 M		
0029	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	36 M		
0030	0402000000-M	310	1200MM RC PIPE CULVERTS, CLASS III	133.2 M		
0031	0414000000-M	310	1500MM RC PIPE CULVERTS, CLASS III	15.6 M		
0032	0420000000-M	310	1650MM RC PIPE CULVERTS, CLASS III	10.2 M		
0033	0426000000-M	310	1800MM RC PIPE CULVERTS, CLASS III	21.6 M		
0034	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (375MM)	30 M		
0035	0448000000-M	310	****MM RC PIPE CULVERTS, CLASS IV (600MM)	70.8 M		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	0708000000-M	310	400MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	281.4 M		
0037	0714000000-M	310	450MM BIT COAT CS PIPE CULVERTS, TYPE B 1.63MM THICK	42 M		
0038	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	39 EA		
0039	0807000000-M	310	450MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	4 EA		
0040	0980000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B, INSTALLED BY BORING & JACKING (600MM, 6.35MM)	90.4 M		
0041	0980000000-M	SP	****MM WELDED STEEL PIPE, ****MM THICK, GRADE B, INSTALLED BY BORING & JACKING (750MM, 7.92MM)	22.8 M		
0042	0995000000-M	340	PIPE REMOVAL	981.22 M		
0043	0996000000-N	350	PIPE CLEAN-OUT	3 EA		
0044	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0045	1044000000-M	501	LIME TREATED SOIL (SLURRY METHOD)	158,187 M2		
0046	1066000000-M	501	LIME FOR LIME TREATED SOIL	1,820 MTN		
0047	1077000000-M	SP	#57 STONE	55 MTN		
0048	1110000000-M	510	STABILIZER AGGREGATE	1,100 MTN		
0049	1121000000-M	520	AGGREGATE BASE COURSE	124,400 MTN		
0050	1176000000-M	542	***MM SOIL CEMENT BASE (180MM)	80,390 M2		
0051	1187000000-M	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	2,430 MTN		
0052	1198000000-M	SP	AGGREGATE FOR SOIL CEMENT BASE	790 MTN		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	1209000000-M	543	ASPHALT CURING SEAL	162,350 L		
0054	1220000000-M	545	INCIDENTAL STONE BASE	500 MTN		
0055	1297000000-M	607	MILLING ASPHALT PAVEMENT, **MM DEPTH (60MM)	19,800 M2		
0056	1330000000-M	607	INCIDENTAL MILLING	1,650 M2		
0057	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	380 MTN		
0058	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	60,300 MTN		
0059	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,689 MTN		
0060	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	50,300 MTN		
0061	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,880 MTN		
0062	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	55,260 MTN		
0063	1525000000-M	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	106 MTN		
0064	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	5,281 MTN		
0065	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	3,316 MTN		
0066	1693000000-M	654	ASPHALT PLANT MIX PAVEMENT REPAIR	277 MTN		
0067	1840000000-M	665	MILLED RUMBLE STRIPS	36,840 M		
0068	2022000000-M	815	SUBDRAIN EXCAVATION	994 M3		
0069	2033000000-M	815	SUBDRAIN FINE AGGREGATE	497 M3		
0070	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	1,200 M		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	120 EA		
0072	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	9 EA		
0073	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	18 M		
0074	2099000000-M	816	SHOULDER DRAIN	3,900 M		
0075	2110000000-M	816	100MM SHOULDER DRAIN PIPE	3,900 M		
0076	2121000000-M	816	100MM OUTLET PIPE (SHOULDER DRAINS)	150 M		
0077	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	18 EA		
0078	2143000000-M	818	BLOTTING SAND	45 MTN		
0079	2209000000-M	838	ENDWALLS	9.2 M3		
0080	2220000000-M	838	REINFORCED ENDWALLS	14 M3		
0081	2253000000-M	840	PIPE COLLARS	29.98 M3		
0082	2275000000-M	SP	FLOWABLE FILL	43.46 M3		
0083	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	218 EA		
0084	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	10.44 M		
0085	2354000000-N	840	FRAME WITH GRATE, STD 840.22	3 EA		
0086	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0087	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	25 EA		
0088	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	186 EA		
0089	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		

County: Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0091	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0092	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0093	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0094	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	1 EA		
0095	2549000000-M	846	750MM CONCRETE CURB & GUTTER	215 M		
0096	2556000000-M	846	SHOULDER BERM GUTTER	2,130 M		
0097	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0098	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	145 M		
0099	2619000000-M	850	100MM CONCRETE PAVED DITCH	49 M2		
0100	2647000000-M	852	125MM MONOLITHIC CONCRETE IS- LANDS (SURFACE MOUNTED)	1,090 M2		
0101	2724000000-M	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	73 M		
0102	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0103	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0104	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	4 EA		
0105	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	10 EA		
0106	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	4 EA		
0108	3030000000-M	862	STEEL BM GUARDRAIL	6,198.87 M		
0109	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	125.73 M		
0110	3075000000-M	862	TRIPLE CORRUGATED STEEL BM GUARDRAIL	41.056 M		
0111	3120000000-M	862	508MM TUBULAR TRIPLE CORRUGA- TED STEEL BM GUARDRAIL	478.22 M		
0112	3135000000-N	862	W-TR STEEL BM GUARDRAIL TRAN- SITION SECTIONS	16 EA		
0113	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	20 EA		
0114	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	9 EA		
0115	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	3 EA		
0116	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	27 EA		
0117	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	13 EA		
0118	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	26 EA		
0119	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	16 EA		
0120	3360000000-M	863	REMOVE EXISTING GUARDRAIL	3,458 M		
0121	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FAB- RIC	37,901 M		
0122	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	8,149 EA		
0123	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	1,446 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	3557000000-M	866	ADDITIONAL BARBED WIRE	3,790 M		
0125	3628000000-M	876	PLAIN RIP RAP, CLASS I	980.5 MTN		
0126	3642000000-M	876	PLAIN RIP RAP, CLASS A	121 MTN		
0127	3649000000-M	876	PLAIN RIP RAP, CLASS B	4,086.4 MTN		
0128	3651000000-M	SP	BOULDERS	155.5 MTN		
0129	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	13,962.3 M2		
0130	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	9 EA		
0131	3684000000-M	SP	GENERIC EROSION CONTROL ITEM BOULDERS (0.9M LENGTH)	49 MTN		
0132	3684000000-M	SP	GENERIC EROSION CONTROL ITEM FOOTER ROCKS (0.9M LENGTH)	84 MTN		
0133	4048000000-M	902	REINFORCED CONCRETE SIGN FOOT- INGS	5 M3		
0134	4054000000-M	902	PLAIN CONCRETE SIGN FOOTINGS	3 M3		
0135	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,948 KG		
0136	4066000000-M	903	SUPPORTS, SIMPLE STEEL BEAM	1,233 KG		
0137	4072000000-M	903	SUPPORTS, 4.5KG STEEL U-CHANNEL	2,129 M		
0138	4096000000-N	904	SIGN ERECTION, TYPE D	18 EA		
0139	4102000000-N	904	SIGN ERECTION, TYPE E	340 EA		
0140	4108000000-N	904	SIGN ERECTION, TYPE F	33 EA		
0141	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	12 EA		

County: Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0142	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	9 EA		
0143	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	4 EA		
0144	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	3 EA		
0145	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	244 EA		
0146	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0147	4425000000-N	1125	WARNING FLAG SETS	48 EA		
0148	4430000000-N	1130	DRUMS	653 EA		
0149	4435000000-N	1135	CONES	214 EA		
0150	4445000000-M	1145	BARRICADES (TYPE III)	648 M		
0151	4450000000-N	1150	FLAGGER	1,952 HR		
0152	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0153	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	4 EA		
0154	4595000000-M	SP	GENERIC TRAFFIC CONTROL ITEM WORK ZONE SIGNS FLUORESCENT ORANGE SHEETING (BARRICADE MOUNTED)	55 M2		
0155	4595000000-M	SP	GENERIC TRAFFIC CONTROL ITEM WORK ZONE SIGNS FLUORESCENT ORANGE SHEETING (PORTABLE)	38 M2		
0156	4595000000-M	SP	GENERIC TRAFFIC CONTROL ITEM WORK ZONE SIGNS FLUORESCENT ORANGE SHEETING (STATIONARY)	225 M2		
0157	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	7,596 EA		
0158	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	80,010 M		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0159	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	12,987 M		
0160	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	7,792 M		
0161	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	339 M		
0162	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	4 EA		
0163	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	263 EA		
0164	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	415,166 M		
0165	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	31,168 M		
0166	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	1,562 M		
0167	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	24 EA		
0168	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	1,140 EA		
0169	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	2,075 M		
0170	4905000000-N	1253	SNOWPLOWABLE RAISED PAVEMENT MARKERS	2,831 EA		
0171	6000000000-M	1605	TEMPORARY SILT FENCE	4,025 M		
0172	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	1,650 MTN		
0173	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	21,000 MTN		
0174	6012000000-M	1610	SEDIMENT CONTROL STONE	8,675 MTN		
0175	6015000000-M	1615	TEMPORARY MULCHING	97 HA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0176	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	4,450 KG		
0177	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	36 MTN		
0178	6024000000-M	1622	TEMPORARY SLOPE DRAINS	725 M		
0179	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	57 EA		
0180	6030000000-M	1630	SILT EXCAVATION	77,525 M3		
0181	6033000000-M	1631	SYNTHETIC ROVING	19,500 M2		
0182	6036000000-M	1631	MATTING FOR EROSION CONTROL	26,050 M2		
0183	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	910 M2		
0184	6042000000-M	1632	6.4MM HARDWARE CLOTH	1,875 M		
0185	6045000000-M	SP	***MM TEMPORARY PIPE (600MM)	125 M		
0186	6069000000-M	1638	STILLING BASINS	80 M3		
0187	6070000000-N	SP	SPECIAL STILLING BASINS	15 EA		
0188	6084000000-M	1660	SEEDING & MULCHING	104 HA		
0189	6087000000-M	1660	MOWING	54 HA		
0190	6090000000-M	1661	SEED FOR REPAIR SEEDING	1,175 KG		
0191	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	4.25 MTN		
0192	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	2,950 KG		
0193	6108000000-M	1665	FERTILIZER TOPDRESSING	180 MTN		
0194	6109000000-M	SP	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS)	0.7 HA		

County: Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0195	6111000000-M	SP	IMPERVIOUS DIKE	15 M		
0196	6114000000-N	SP	SPECIALIZED HAND MOWING	36 HR		
0197	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	40 EA		
0198	6118000000-N	SP	ROOTWADS	3 EA		
0199	6123000000-M	1670	REFORESTATION	19.5 HA		
0200	6126000000-M	SP	STREAMBANK REFORESTATION	0.13 HA		
0201	6147000000-M	SP	GENERIC EROSION CONTROL ITEM SAFETY FENCE	1,440 M		
0202	7060000000-M	1705	SIGNAL CABLE	270 M		
0203	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	10 EA		
0204	7264000000-M	1710	MESSENGER CABLE (9.52MM)	180 M		
0205	7300000000-M	1715	TRENCHING (UNPAVED)	250 M		
0206	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	8 EA		
0207	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	270 M		
0208	7456000000-M	1726	LEAD-IN CABLE	645 M		
0209	7576000000-N	1740	METAL STRAIN SIGNAL POLE	4 EA		
0210	7613000000-N	SP	SOIL TEST	4 EA		
0211	7614000000-M	SP	DRILLED PIER FOUNDATION (***MM DIA) (1067MM)	18 M		
0212	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0213	7688000000-N	SP	CABINET BASE ADAPTER	1 EA		
0214	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0215	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	5 EA		

CULVERT ITEMS

0216	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+28.500-L-)	Lump Sum	L.S.	
0217	8126000000-N	414	CULVERT EXCAVATION, STA ***** (52+75.440-L-)	Lump Sum	L.S.	
0218	8126000000-N	414	CULVERT EXCAVATION, STA ***** (62+33.970-L-)	Lump Sum	L.S.	
0219	8133000000-M	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	127 MTN		
0220	8196000000-M	420	CLASS A CONCRETE (CULVERT)	188.8 M3		
0221	8245000000-M	425	REINFORCING STEEL (CULVERT)	15,424 KG		
0222	8590000000-M	876	PLAIN RIP RAP, CLASS ** (1)	3 MTN		

STRUCTURE ITEMS

0223	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22+83.400-L-)	Lump Sum	L.S.	
0224	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (97+00.000-L-)	Lump Sum	L.S.	
0225	8105540000-M	SP	1066MM DIA DRILLED PIERS IN SOIL	112.4 M		
0226	8105560000-M	SP	1220MM DIA DRILLED PIERS IN SOIL	12.5 M		
0227	8105640000-M	SP	1066MM DIA DRILLED PIERS NOT IN SOIL	56.4 M		

County: Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0228	8105660000-M	SP	1220MM DIA DRILLED PIERS NOT IN SOIL	16.1 M		
0229	8111400000-M	SP	PERMANENT STEEL CASING FOR 1066MM DRILLED PIER	15.2 M		
0230	8111600000-M	SP	PERMANENT STEEL CASING FOR 1220MM DRILLED PIER	13 M		
0231	8113000000-N	SP	SID INSPECTION	8 EA		
0232	8114000000-N	SP	SPT TESTING	10 EA		
0233	8115000000-N	SP	CROSSHOLE SONIC LOGGING	6 EA		
0234	8116000000-M	SP	CSL TUBES	856.9 M		
0235	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	2,385.6 M2		
0236	8161000000-M	420	GROOVING BRIDGE FLOORS	2,165.5 M2		
0237	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	419.5 M3		
0238	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+04.666-L-)	Lump Sum	L.S.	
0239	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+83.400-L-)	Lump Sum	L.S.	
0240	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+85.488-L-)	Lump Sum	L.S.	
0241	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (97+00.000-L-)	Lump Sum	L.S.	
0242	8217000000-M	425	REINFORCING STEEL (BRIDGE)	63,649 KG		
0243	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	9,760 KG		
0244	8259000000-M	430	914MM PRESTRESSED CONCRETE GIRDERS	143.4 M		

County: Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0245	8262000000-M	430	1143MM PRESTRESSED CONCRETE GIRDERS	195.32 M		
0246	8265000000-M	430	1372MM PRESTRESSED CONCRETE GIRDERS	241.952 M		
0247	8280000000-M	440	APPROX KG STRUCTURAL STEEL	103,500 LS		
0248	8364000000-M	450	HP310X79 STEEL PILES	565.5 M		
0249	8391000000-N	450	STEEL PILE POINTS	30 EA		
0250	8503000000-M	460	CONCRETE BARRIER RAIL	405.798 M		
0251	8531000000-M	462	100MM SLOPE PROTECTION	2,030 M2		
0252	8608000000-M	876	PLAIN RIP RAP CLASS II (600MM THICK)	681 MTN		
0253	8622000000-M	876	FILTER FABRIC FOR DRAINAGE	694 M2		
0254	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0255	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
			Total Amount Of Bid For Entire Project :			

1132/Aug20/Q2618755.276/D101914480000/E255

C201282
CHATHAM COUNTY

2/16/99

Contract No: C201282

Counties: Chatham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General