

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT R-2610A

COUNTY Chatham

DATE: REV. 2/20/03

SHEET 4 OF 5 SHEETS

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE			
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 15%		ROCK	SUITABLE	UNSUIT.	
-L- RT	28+60	31+60	160	0	0	0	160	1,431	0	1,431	1,646	1,486	0	0	0	
-Y9- FULL	10+00	11+80	1,653	0	0	0	1,653	79	0	79	91	0	0	1,562	0	
SUBTOTAL			1,813	0	0	0	1,813	1,510	0	1,510	1,737	1,486	0	1,562	0	
-L- RT	37+40	39+80	702	0	0	0	702	2,300	0	2,300	2,645	1,943	0	0	0	
-L- RT	41+80	42+40	0	0	0	0	0	126	0	126	145	145	0	0	0	
-L- RT-	43+40	46+00	441	0	0	0	441	0	0	0	0	0	0	441	0	
SUBTOTAL			1,143	0	0	0	1,143	2,426	0	2,426	2,790	2,088	0	441	0	
-L- RT	46+00	49+80	853	0	0	0	853	0	0	0	0	0	0	853	0	
-L- RT	51+60	53+40	0	0	0	0	0	534	0	534	614	614	0	0	0	
SUBTOTAL			853	0	0	0	853	534	0	534	614	614	0	853	0	
-L- RT	61+60	62+20	0	0	0	0	0	55	0	55	63	63	0	0	0	
NBL OUTSIDE SHLDR WIDENING																
-L-	41+40.000	43+96.780	128				128								128	
-L-	50+50.151	71+80.000	1,061				1,061								1,061	
-L-	73+16.783	78+47.000	264				264								264	
-L-	79+20.000	85+79.544	329				329								329	
SUBTOTAL			1,782				1,782								1,782	
SHEET TOTAL			5,591	0	0		1,782	3,809	4,525	0	4,525	5,204	4,251	0	2,856	1,782