

3C/40

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT R-2610A

COUNTY Chatham

DATE: REV. 2/20/03

SHEET 1 OF 5 SHEETS

RD10S01C

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 15%		ROCK	SUITABLE	UNSUIT.
-L- MED	10+20	11+85	280	0	0	0	280	15	0	15	17	0	0	263	0
-L- LT	12+06	17+90.080 BEG BRDG	3,972	0	0	0	3,972	63,172	0	63,172	72,648	68,676	0	0	0
		SUBTOTAL	4,252	0	0	0	4,252	63,187	0	63,187	72,665	68,676	0	263	0
-L- LT	18+22.156	21+20 END BRDG	577	0	1,519	0	577	17,600	0	17,600	20,240	19,663	0	0	1,519
-L- LT	21+20	24+80	12,257	0	1,354	0	12,257	8,609	0	8,609	9,900	0	0	2,357	1,354
-Y3REV FULL	11+20	13+24.861	1,417	0	1,888	0	1,417	3,551	0	3,551	4,084	2,667	0	0	1,888
		SUBTOTAL	13,674	0	3,242	0	13,674	12,160	0	12,160	13,984	2,667	0	2,357	3,242
-L- LT	24+80	27+78.167 BEG BRDG	1,384	0	0	0	1,384	48,710	0	48,710	56,017	54,633	0	0	0
-Y5- LT	10+20	11+15	218	0	0	0	218	12	0	12	14	0	0	204	0
-Y5- RT	10+20	11+15	462	0	0	0	462	22	0	22	25	0	0	437	0
		SUBTOTAL	2,064	0	0	0	2,064	48,744	0	48,744	56,056	54,633	0	641	0
-L- LT	28+15.167	38+60 END BRDG	14,708	0	0	0	14,708	46,920	0	46,920	53,958	39,250	0	0	0
-Y9- FULL	12+40	12+80	130	0	0	0	130	160	0	160	184	54	0	0	0
		SUBTOTAL	14,838	0	0	0	14,838	47,080	0	47,080	54,142	39,304	0	0	0
SHEET TOTAL			35,405	0	4,761	0	35,405	188,771	0	188,771	217,087	184,943	0	3,261	4,761