R:\xsc\earthwork\R2610A_EWSUM.XLS

RD10S01C

PROJ. REFERENCE NO.	SHEET NO.
R-2610 A	X-A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Station (MEDIAN) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
10+20.000	0	0	0	0
10+40.000	25	4	0	0
10+60.000	23	6	0	0
10+80.000	26	3	0	0
11+00.000	29	1	0	0
11+20.000	30	1	0	0
11+40.000	36	0	0	0
11+60.000	45	0	0	0
11+80.000	58	0	0	0
11+85.000	8	0	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
12+06.000	0	0	0	0
12+20.000		0	0	0
12+40.000	64	8	0	0
12+60.000	108	365	0	0
12+80.000	157	797	0	0
13+00.000	185	805	0	0
13+20.000	205	629	0	0
13+40.000	228	441	0	0
13+60.000	242	299	0	0
13+80.000	255	221	0	0
14+00.000	251	141	0	0
14+20.000	237	245	0	0
14+40.000	237	324	0	0
14+60.000	272	120	0	0
14+80.000	266	338	0	0
15+00.000	215	817	0	0
15+20.000	187	1298	0	0
15+40.000	145	1897	0	0
15+60.000	106	2479	0	0
15+80.000	74	3110	0	0
16+00.000	48	3772	0	0
16+20.000	45	4355	0	0
16+40.000	46	4782	0	0
16+60.000	40	5111	0	0
16+80.000	41	5105	0	0
17+00.000	45	4895	0	0
17+20.000	44	4761	0	0
17+40.000	44	4589	0	0
17+60.000	50	4438	0	0
17+80.000	64	4137	0	0
17+89.846	36	1909	0	0
18+00.000	19	984	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
18+05.000	0	0	0	0
18+22.245	22	783	0	0
18+40.000	45	1613	0	0
18+60.000	48	1348	0	0
18+80.000	45	740	0	0
19+00.000	41	746	0	0
19+20.000	38	919	0	0
19+40.000	38	1087	0	0
19+60.000	36	1343	0	0
19+80.000	28	1387	0	0
20+00.000	24	1191	0	0
20+20.000	34	979	0	0
20+40.000	55	877	0	0
20+60.000	47	866	0	0
20+80.000	25	798	0	0
21+00.000	24	798	842	0
21+20.000	27	606	677	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
21+40.000	38	446	800	0
21+60.000	34	611	554	0
21+80.000	33	369	0	0
22+00.000	264	38	0	0
22+20.000	758	11	0	0
22+40.000	1417	10	0	0
22+60.000	2152	8	0	0
22+80.000	2682	13	0	0
23+00.000	2552	11	0	0
23+20.000	1329	24	0	0
23+40.000	220	656	0	0
23+60.000	20	1780	0	0
23+80.000	20	1791	0	0
24+00.000	92	694	0	0
24+20.000	248	53	0	0
24+40.000	258	26	0	0
24+60.000	110	343	0	0
24+80.000	30	371	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
25+00.000	23	137	0	0
25+20.000	357	88	0	0
25+40.000	505	2	0	0
25+60.000	173	371	0	0
25+80.000	30	1370	0	0
26+00.000	34	2392	0	0
26+20.000	31	3404	0	0
26+40.000	30	4227	0	0
26+60.000	32	4562	0	0
26+80.000	35	4801	0	0
27+00.000	36	5217	0	0
27+20.000	37	5554	0	0
27+40.000	40	5371	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
27+60.000	21	5313	0	0
27+78.167	0	4967	0	0
27+85.000	0	934	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
28+05.000	0	0	0	0
28+15.167	0	784	0	0
28+20.000	6	745	0	0
28+40.000	42	2771	0	0
28+60.000	36	2401	0	0
28+80.000	31	2453	0	0
29+00.000	29	2642	0	0
29+20.000	33	2857	0	0
29+40.000	36	3139	0	0
29+60.000	38	3294	0	0
29+80.000	38	3146	0	0
30+00.000	33	2907	0	0
30+20.000	25	2503	0	0
30+40.000	24	1829	0	0
30+60.000	28	1246	0	0
30+80.000	33	734	0	0
31+00.000	35	443	0	0
31+20.000	34	558	0	0
31+40.000	27	864	0	0

Station (LT.) L	Suitable Uncl. Exc. (cu. meters)	Embt. (cu. meters)	Undercut (cu. meters)	DDE LT. Uncl. Exc. (cu. meters)
31+60.000	16	774	0	0
31+80.000	14	869	0	0
32+00.000	17	1148	0	0
32+20.000	17	924	0	0
32+40.000	21	652	0	0
32+60.000	27	390	0	0
32+80.000	35	193	0	0
33+00.000	129	57	0	0
33+20.000	177	11	0	0
33+40.000	145	25	0	0
33+60.000	140	96	0	0
33+80.000	136	98	0	0
34+00.000	251	20	0	0
34+20.000	560	4	0	0
34+40.000	799	1	0	0
34+60.000	731	0	0	0
34+80.000	732	0	0	0
35+00.000	834	0	0	0
35+20.000	789	0	0	0
35+40.000	894	0	0	0
35+60.000	1089	0	0	0
35+80.000	1157	1	0	0
36+00.000	1253	1	0	0