PROJ. REFERENCE NO.	SHEET NO.
R-2610B	PM-1

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM/QUANTITY BREAKDOWN	TOTAL QUANTITY
	PAVEMENT MARKING LINES		
	THERMOPLASTIC (100mm, 2.3mm)		
TA	WHITE EDGELINE	25,416 m	
TB	YELLOW EDGELINE	23,008 m	
			TOTAL 48,424 m
	THERMOPLASTIC (100mm, 3.1mm)		
TC	3M WHITE SKIP	5875 m	
TD	0.5M WHITE MINISKIP	336 m	
TE	WHITE SOLID LANE LINE	364 m	
TI	YELLOW DOUBLE CENTER LINE	876 m	
			TOTAL 7451 m
	THERMOPLASTIC (200mm, 2.3mm)		
TP	WHITE GORE	4485 m	
TQ	WHITE DIAGONAL	451 m	
			TOTAL 4936 m
	THERMOPLASTIC (100mm,6.2mm)		
T2	WHITE STOP BAR	223 m	
			TOTAL 223 m
	THERMOPLASTIC SYMBOLS (2.3mm)		
UA	LEFT TURN ARROW	73 EA	
UB	RIGHT TURN ARROW	24 EA	
UC	STRAIGHT ARROW	84 EA	
			TOTAL 181 EA
	SNOWPLOWABLE PAVEMENT MARKERS		
ME	YELLOW AND YELLOW	11 EA	
MF	CRYSTAL AND RED	1541 EA	
			TOTAL 1552 EA

APPROVED: Mitchell Henkel DATE: 10/30/03

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 027791 ENGINEER MITCHELL J. HENDEE

PAV'T MARKING SCHEDULE

SCALE:	NONE
DATE:	04/03
DWG. BY:	DER
DESIGN BY:	DER
REVIEWED BY:	

DIVISION OF HIGHWAYS ENGINEERING BRANCH TRANSPORTATION MANAGEMENT UNIT TRAFFIC CONTROL

REVISIONS

CADD FILE R2610B_PM_BASE01.DGN

30-OCT-2003 09:54
F:\TCP\r2610b_pm_base01.dgn
derichardson AT TET206432