

EARTHWORK SUMMARIES

Volumes in Cubic Meters

PROJECT R-2610B

COUNTY Chatham

DATE 3/18/03

SHEET 3 OF 5 SHEETS

RD10S01C

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 20%		ROCK	SUITABLE	UNSUIT.
-L- RT	21+50.000	22+29.584	3	0	0	0	3	59	0	59	71	68	0	0	0
-L- RT	36+28.121	37+40.000	276	0	0	0	276	164	0	164	197	0	0	79	0
-Y10A -	10+82.744	11+19.290	48	0	0	0	48	0	0	0	0	0	0	48	0
-Y11 -	11+10.000	11+55.191	42	0	0	0	42	10	0	10	12	0	0	30	0
-L- RT	44+20.000	45+20.000	108	0	0	0	108	163	0	163	196	88	0	0	0
SUBTOTAL			474	0	0	0	474	337	0	337	405	88	0	157	0
-L- RT	51+45.443	53+20.000	868	0	0	0	868	312	0	312	374	0	0	494	0
-Y12 -	10+50.000	11+08.515	8	0	0	0	8	34	0	34	41	33	0	0	0
SUBTOTAL			876	0	0	0	876	346	0	346	415	33	0	494	0
-L- RT	68+90.000	70+60.000	19	0	0	0	19	972	0	972	1,166	1,147	0	0	0
-L- RT	74+20.000	75+00.000	184	0	0	0	184	43	0	43	52	0	0	132	0
-Y14 -	10+00.000	10+61.647	70	0	0	0	70	21	0	21	25	0	0	45	0
SUBTOTAL			273	0	0	0	273	1,036	0	1,036	1,243	1,147	0	177	0
-L- RT	97+60.000	98+00.000	0	0	0	0	0	28	0	28	34	34	0	0	0
-L- RT	114+00.000	116+00.000	0	0	0	0	0	1,363	0	1,363	1,636	1,636	0	0	0
-L- RT	118+39.315	119+40.000	103	0	0	0	103	324	0	324	389	286	0	0	0
-Y18 -	10+30.000	10+63.080	31	0	0	0	31	16	0	16	19	0	0	12	0
-L- RT	120+60.000	121+90.000	0	0	0	0	0	165	0	165	198	198	0	0	0
-NBL- RT	124+00.000LA	127+80.000	3,167	0	0	0	3,167	12	0	12	14	0	0	3,153	0
-NBL- RT	128+20.000	129+80.000	463	0	0	0	463	424	0	424	509	46	0	0	0
SUBTOTAL			3,764	0	0	0	3,764	2,304	0	2,304	2,765	2,166	0	3,165	0
SHEET TOTALS:			5,390	0	0	0	5,390	4,110	0	4,110	4,933	3,536	0	3,993	0