

EARTHWORK SUMMARIES
Volumes in Cubic Meters

PROJECT R-2610B

COUNTY Chatham

DATE 3/20/03

SHEET 1 OF 5 SHEETS

RD10S01C

LINE	STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE		
			TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. 20%		ROCK	SUITABLE	UNSUIT.
-L- LT.	10+00.000	19+00.000	12,372	0	0	0	12,372	13,123	0	13,123	15,748	3,376	0	0	0
-L- LT.	19+00.000	(BEG. BRDG.) 22+54.430	4,685	0	0	0	4,685	2,330	0	2,330	2,796	0	0	1,889	0
-L- LT.	(END BRDG.) 23+14.500	32+00.000	13,761	0	2,056	0	13,761	7,851	0	7,851	9,421	0	0	4,340	2,056
-Y9A-	10+14.422	10+60.000	402	0	0	0	402	0	0	0	0	0	0	402	0
		SUBTOTAL	31,220	0	2,056	0	31,220	23,304	0	23,304	27,965	3,376	0	6,631	2,056
-L- LT.	32+00.000	41+00.000	6,720	0	0	0	6,720	6,637	0	6,637	7,964	1,244	0	0	0
-L- LT.	41+00.000	50+00.000	21,357	0	0	0	21,357	34,829	0	34,829	41,795	20,438	0	0	0
-Y11-	11+87.210	12+31.501	40	0	0	0	40	2,078	0	2,078	2,494	2,454	0	0	0
		SUBTOTAL	21,397	0	0	0	21,397	36,907	0	36,907	44,289	22,892	0	0	0
-L- LT.	50+00.000	59+00.000	18,783	0	689	2,288	16,495	29,098	0	29,098	34,918	18,423	0	0	2,977
-Y12-	11+37.276	11+90.000	144	0	0	0	144	218	0	218	262	118	0	0	0
		SUBTOTAL	18,927	0	689	2,288	16,639	29,316	0	29,316	35,180	18,541	0	0	2,977
-L- LT.	59+00.000	68+00.000	47,883	0	1,898	7,952	39,931	15,304	0	15,304	18,365	0	0	21,566	9,850
-Y13-	11+30.666	11+80.000	99	0	0	0	99	39	0	39	47	0	0	52	0
		SUBTOTAL	47,982	0	1,898	7,952	40,030	15,343	0	15,343	18,412	0	0	21,618	9,850
-L- LT.	68+00.000	77+00.000	14,922	0	0	0	14,922	20,846	0	20,846	25,015	10,093	0	0	0
-Y14-	10+99.503	11+60.000	38	0	0	0	38	268	0	268	322	284	0	0	0
		SUBTOTAL	14,960	0	0	0	14,960	21,114	0	21,114	25,337	10,377	0	0	0
-L- LT.	77+00.000	86+00.000	13,799	0	560	3,010	10,789	18,574	0	18,574	22,289	11,500	0	0	3,570
SHEET TOTALS:			155,005	0	5,203	13,250	141,755	151,195	0	151,195	181,436	67,930	0	28,249	18,453