



- NOTES:**
1. ALL NCDOT ATTACHMENTS ARE 40" BELOW POWER, FRONT SIDE OF POLE UNLESS OTHERWISE NOTED
  2. CONTRACTOR TO INSTALL INTERCONNECT CENTER, PATCH PANEL AND JUMPERS AS SHOWN ON SPLICE DETAILS.
  3. CONTRACTOR TO REMOVE SEGMENTS A & B OF THE COMMUNICATIONS CABLE FROM EXISTING CABINET (06-0610). SEGMENT "A" CONNECTS TO 06-0230. SEGMENT "B" CONNECTS TO 06-0357. REROUTE SEGMENT "A" TO POLE NO#1 AND THEN DOWN THE POLE TO THE CONTROLLER CABINET. REROUTE SEGMENT "B" BACK TO POLE ES25AE AND THEN DOWN THE POLE TO THE CONTROLLER CABINET AS SHOWN. STORE ANY SPARE CABLE FROM SEGMENTS "A & B" ON SNOWSHOES AS SHOWN.

<p>Prepared in the Office of          Statewide and Local Roadways          Division of Transportation          Traffic Management Systems          222 N. McDowell St., Raleigh, NC 27603</p>	<b>COMMUNICATION CABLE          ROUTING PLANS</b>		SEAL 	
	DIVISION 6 CUMBERLAND CO. HOPE MILLS PLAN DATE: NOVEMBER 2003 PREPARED BY: C. BUTLER REVISIONS: _____ INIT.: _____ DATE: _____	REVIEWED BY: G. MULDRON REVIEWED BY: G.G. MURR, JR.	SCALE 	SIGNATURE 
	CADD File Name:			