R:\Roadway\Xsc\EARTHWORK\U0620_RDY_EW_L1L.LOG

PROJ. REFERENCE NO.	SHEET NO.
U-0620	X-B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	19	42
15+00.00	25	48
15+50.00	14	69
16+00.00	2	94
16+50.00	0	98
17+00.00	0	100
17+50.00	0	129
18+00.00	0	184
18+50.00	0	227
19+00.00	0	233
19+50.00	0	172
20+00.00	0	120
20+50.00	5	83
21+00.00	7	55
21+50.00	4	51
22+00.00	5	40
22+50.00	5	57
23+00.00	5	72
23+50.00	5	89
24+00.00	4	116
24+50.00	4	124
25+00.00	3	143
25+50.00	1	184
26+00.00	0	216
26+50.00	0	205
27+00.00	0	241
27+50.00	0	367
28+00.00	0	452
28+50.00	0	492
29+00.00	0	480
29+50.00	0	497
30+00.00	0	503
30+50.00	0	468
31+00.00	0	498
31+47.00	0	572

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
14+00.00	0	0
14+50.00	85	0
15+00.00	104	0
15+50.00	117	0
16+00.00	116	0
16+50.00	120	0
17+00.00	105	10
17+50.00	65	24
18+00.00	25	38
18+50.00	3	52
19+00.00	1	71
19+50.00	0	105
20+00.00	0	142

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+50.00	0	240
21+00.00	0	376
21+50.00	0	692
22+00.00	0	957
22+50.00	0	980
23+00.00	0	971
23+50.00	0	897
24+00.00	0	808
24+50.00	0	782
25+00.00	0	891
25+50.00	0	1016
26+00.00	0	1064
26+50.00	0	1186
27+00.00	0	1355
27+50.00	0	1414
28+00.00	0	1373
28+50.00	0	1309
29+00.00	0	1331
29+50.00	0	1118
30+00.00	0	765
30+50.00	0	930
31+00.00	0	1171
31+47.00	0	1361

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
32+88.00	0	0	0
33+50.00	0	3506	0
34+00.00	0	2845	0
34+50.00	0	2765	0
35+01.00	0	2600	0
35+51.00	0	2499	0
36+00.00	0	2474	0
36+50.00	0	2707	0
37+00.00	0	2975	0
37+50.00	0	3169	0
38+00.00	0	3408	0
38+50.00	0	3605	0
39+00.00	0	4732	318
39+50.00	0	6036	318
40+00.00	0	6027	0
40+50.00	0	5135	0
41+00.00	268	2910	0
41+50.00	1363	701	0
42+00.00	3211	390	390
42+50.00	4311	738	738
43+00.00	4372	694	694
43+50.00	4426	695	695
44+00.00	4496	349	349
44+50.00	4622	0	0
45+00.00	4410	0	0
45+50.00	3969	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
46+00.00	3724	0	0
46+50.00	3440	0	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
46+50.00	0	0
47+00.00	1568	0
47+50.00	1620	0
48+00.00	1555	0
48+50.00	1127	0
49+00.00	751	0
49+50.00	534	0
50+00.00	276	0
50+50.00	63	32
51+00.00	2	156
51+50.00	0	325
52+00.00	0	492
52+50.00	0	565
53+00.00	0	530
53+50.00	0	512
54+00.00	0	451
54+50.00	0	345
55+00.00	0	250
55+50.00	32	112
56+00.00	91	13
56+50.00	103	0
57+00.00	67	0
57+50.00	48	4
58+00.00	34	16
58+50.00	9	35
59+00.00	0	69
59+50.00	1	86
60+00.00	1	89
60+51.00	12	102
61+00.00	33	93
61+50.00	45	71
62+00.00	52	44
62+50.00	58	28
63+00.00	84	16
63+50.00	84	10
64+00.00	45	12
64+50.00	26	22
65+00.00	17	37
65+50.00	18	35
66+00.00	15	38
66+50.00	6	48
67+00.00	4	55
67+50.00	8	74
68+00.00	17	76
68+50.00	13	60
69+00.00	2	56
69+50.00	5	57

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
70+00.00	18	45
70+50.00	23	40
71+00.00	13	57
71+50.00	8	114
72+00.00	25	175
72+50.00	30	224
73+00.00	10	269
73+50.00	0	290
74+00.00	0	265
75+00.00	0	232
75+50.00	0	53
76+00.00	0	115
76+50.00	0	107
77+00.00	0	100
77+50.00	0	119
78+00.00	1	124
78+50.00	2	120
79+00.00	3	109
79+50.00	4	99
80+00.00	4	83
80+50.00	3	65
81+00.00	3	59
81+50.00	3	57
82+00.00	4	51
82+50.00	5	46
83+00.00	5	45
83+50.00	5	28
84+00.00	3	32
84+50.00	3	43
85+00.00	4	38
85+50.00	4	33
86+00.00	3	33
86+50.00	3	37
87+00.00	2	37
87+50.00	1	46
88+00.00	0	54
88+50.00	0	55
89+00.00	0	62
89+50.00	2	58
90+00.00	7	40
90+50.00	14	24
91+00.00	13	26
91+50.00	8	37
92+00.00	5	45
92+50.00	1	70
93+00.00	0	103
93+50.00	0	140
94+00.00	0	202
94+50.00	0	254
95+00.00	0	269
95+50.00	0	223
96+00.00	0	156
96+50.00	0	108