

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0001000000-E | 200 | CLEARING & GRUBBING .. ACRE(S) | Lump Sum | L.S. | |
| 0004 | 0008000000-E | 200 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 0005 | 0022000000-E | 225 | UNCLASSIFIED EXCAVATION | 15,000 CY | | |
| 0006 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (29+18.42) | Lump Sum | L.S. | |
| 0007 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (29+18.63) | Lump Sum | L.S. | |
| 0008 | 0036000000-E | 225 | UNDERCUT EXCAVATION | 1,500 CY | | |
| 0009 | 0106000000-E | 230 | BORROW EXCAVATION | 96,000 CY | | |
| 0010 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 25,500 CY | | |
| 0011 | 0156000000-E | 250 | REMOVAL OF EXISTING ASPHALT PAVEMENT | 10,500 SY | | |
| 0012 | 0177000000-E | 250 | BREAKING OF EXISTING ASPHALT PAVEMENT | 6,400 SY | | |
| 0013 | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 2,500 CY | | |
| 0014 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 1,000 SY | | |
| 0015 | 0206000000-E | SP | TEMPORARY SHORING - BARRIER SUPPORTED | 3,200 SF | | |
| 0016 | 0241000000-E | SP | GENERIC GRADING ITEM ROCK PLATING | 1,125 SY | | |
| 0017 | 0312000000-E | 300 | SELECT MATERIAL, CLASS IV | 1,000 TON | | |
| 0018 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 560 TON | | |

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0019 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 2,612 LF | | |
| 0020 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 1,204 LF | | |
| 0021 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 220 LF | | |
| 0022 | 0384000000-E | 310 | 30" RC PIPE CULVERTS, CLASS III | 420 LF | | |
| 0023 | 0414000000-E | 310 | 60" RC PIPE CULVERTS, CLASS III | 64 LF | | |
| 0024 | 0522000000-E | 310 | *** X *** X *** RC PIPE TEES, CLASS III (18" X 18" X 15") | 1 EA | | |
| 0025 | 0588000000-E | 310 | 18" CS PIPE CULVERTS, 0.064" THICK | 56 LF | | |
| 0026 | 0708000000-E | 310 | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 444 LF | | |
| 0027 | 0714000000-E | 310 | 18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 70 LF | | |
| 0028 | 0768000000-E | 310 | 72" BIT COAT CS PIPE CULVERTS, TYPE B 0.138" THICK | 172 LF | | |
| 0029 | 0806000000-E | 310 | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 18 EA | | |
| 0030 | 0807000000-E | 310 | 18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 2 EA | | |
| 0031 | 0980000000-E | SP | *** WELDED STEEL PIPE, ***** THICK, GRADE B, INSTALLED BY BORING & JACKING (72", 1.000") | 216 LF | | |
| 0032 | 0995000000-E | 340 | PIPE REMOVAL | 2,575 LF | | |
| 0033 | 1000000000-E | 462 | 6" SLOPE PROTECTION | 260 SY | | |
| 0034 | 1011000000-N | 500 | FINE GRADING | Lump Sum | L.S. | |
| 0035 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 1,850 TON | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0036 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0037 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 5,400 TON | | |
| 0038 | 1491000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0C | 10,600 TON | | |
| 0039 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 4,650 TON | | |
| 0040 | 1503000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C | 4,900 TON | | |
| 0041 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 3,500 TON | | |
| 0042 | 1539000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S12.5C | 4,900 TON | | |
| 0043 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 1,365 TON | | |
| 0044 | 1565000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22 | 270 TON | | |
| 0045 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 200 TON | | |
| 0046 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 25 EA | | |
| 0047 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 157 CY | | |
| 0048 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 118 CY | | |
| 0049 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 700 LF | | |
| 0050 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 21 EA | | |
| 0051 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 2 EA | | |
| 0052 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 12 LF | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0053 | 2190000000-N | 828 | TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE | 6 | EA | |
| 0054 | 2220000000-E | 838 | REINFORCED ENDWALLS | 48.6 | CY | |
| 0055 | 2253000000-E | 840 | PIPE COLLARS | 2.36 | CY | |
| 0056 | 2264000000-E | 840 | PIPE PLUGS | 0.32 | CY | |
| 0057 | 2275000000-E | SP | FLOWABLE FILL | 250 | CY | |
| 0058 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 61 | EA | |
| 0059 | 2308000000-E | 840 | MASONRY DRAINAGE STRUCTURES | 7.4 | LF | |
| 0060 | 2364200000-N | 840 | FRAME WITH TWO GRATES, STD 840.20 | 22 | EA | |
| 0061 | 2365000000-N | 840 | FRAME WITH TWO GRATES, STD 840.22 | 14 | EA | |
| 0062 | 2366000000-N | 840 | FRAME WITH TWO GRATES, STD 840.24 | 1 | EA | |
| 0063 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F) | 7 | EA | |
| 0064 | 2374000000-N | 840 | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 9 | EA | |
| 0065 | 2396000000-N | 840 | FRAME WITH COVER, STD 840.54 | 1 | EA | |
| 0066 | 2407000000-N | 840 | STEEL FRAME WITH TWO GRATES, STD 840.37 | 2 | EA | |
| 0067 | 2418000000-E | SP | FRAME WITH GRATES, DRIVEWAY DROP INLET | 52 | LF | |
| 0068 | 2489000000-E | SP | GENERIC DRAINAGE ITEM FABRIC FOR TEMPORARY FABRIC WALL, TYPE 1 | 5,556 | SY | |
| 0069 | 2489000000-E | SP | GENERIC DRAINAGE ITEM FABRIC FOR TEMPORARY FABRIC WALL, TYPE 2 | 16,667 | SY | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0070 | 2516000000-E | SP | SELECT GRANULAR MATERIAL FOR TEMPORARY FABRIC WALL | 2,300 CY | | |
| 0071 | 2549000000-E | 846 | 2'-6" CONCRETE CURB & GUTTER | 3,000 LF | | |
| 0072 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 350 LF | | |
| 0073 | 2577000000-E | 846 | CONCRETE EXPRESSWAY GUTTER | 3,200 LF | | |
| 0074 | 2612000000-E | 848 | 6" CONCRETE DRIVEWAY | 35 SY | | |
| 0075 | 2619000000-E | 850 | 4" CONCRETE PAVED DITCH | 225 SY | | |
| 0076 | 2655000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) | 125 SY | | |
| 0077 | 2703000000-E | 854 | CONCRETE BARRIER, TYPE ***** (TYPE III, DOUBLE FACED) | 1,799 LF | | |
| 0078 | 2710000000-N | 854 | CONCRETE BARRIER TRANSITION SECTION | 2 EA | | |
| 0079 | 2724000000-E | 857 | PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED | 650 LF | | |
| 0080 | 2800000000-N | 858 | ADJUSTMENT OF CATCH BASINS | 1 EA | | |
| 0081 | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 5 EA | | |
| 0082 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 5,925 LF | | |
| 0083 | 3045000000-E | 862 | STEEL BM GUARDRAIL, SHOP CURVED | 375 LF | | |
| 0084 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0085 | 3180000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** (BP) | 3 EA | | |
| 0086 | 3180000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD) | 3 EA | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|---------------|-----------|--------|
| 0087 | 3180000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** (NJ-25) | 2 EA | | |
| 0088 | 3195000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE AT-1 | 2 EA | | |
| 0089 | 3210000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE CAT-1 | 2 EA | | |
| 0090 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0091 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 6 EA | | |
| 0092 | 3317000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE B-77 | 1 EA | | |
| 0093 | 3360000000-E | 863 | REMOVE EXISTING GUARDRAIL | 3,703.5 LF | | |
| 0094 | 3628000000-E | 876 | PLAIN RIP RAP, CLASS I | 425 TON | | |
| 0095 | 3642000000-E | 876 | PLAIN RIP RAP, CLASS A | 10 TON | | |
| 0096 | 3649000000-E | 876 | PLAIN RIP RAP, CLASS B | 230 TON | | |
| 0097 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 3,990 SY | | |
| 0098 | 4054000000-E | 902 | PLAIN CONCRETE SIGN FOOTINGS | 2 CY | | |
| 0099 | 4060000000-E | 903 | SUPPORTS, BREAKAWAY STEEL BEAM | 1,015 LB | | |
| 0100 | 4066000000-E | 903 | SUPPORTS, SIMPLE STEEL BEAM | 464 LB | | |
| 0101 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 847 LF | | |
| 0102 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 4 EA | | |
| 0103 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 18 EA | | |
| 0104 | 4108000000-N | 904 | SIGN ERECTION, TYPE F | 9 EA | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|-------------|-----------|--------|
| 0105 | 4110000000-N | 904 | SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A) | 4 EA | | |
| 0106 | 4129000000-N | 906 | RELOCATE SIGN, TYPE ***** (E) | 1 EA | | |
| 0107 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 82 EA | | |
| 0108 | 4158000000-N | 907 | DISPOSAL OF SIGN SYSTEM, WOOD | 5 EA | | |
| 0109 | 4238000000-N | 907 | DISPOSAL OF SIGN, D, E OR F | 1 EA | | |
| 0110 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 3,729 SF | | |
| 0111 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 544 SF | | |
| 0112 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 137 SF | | |
| 0113 | 4415000000-N | 1115 | FLASHING ARROW PANELS, TYPE C | 2 EA | | |
| 0114 | 4420000000-N | 1120 | CHANGEABLE MESSAGE SIGNS | 2 EA | | |
| 0115 | 4430000000-N | 1130 | DRUMS | 250 EA | | |
| 0116 | 4435000000-N | 1135 | CONES | 60 EA | | |
| 0117 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 220 LF | | |
| 0118 | 4450000000-N | 1150 | FLAGGER | 3,600 HR | | |
| 0119 | 4460000000-N | 1155 | WARNING LIGHTS (TYPE B) | 6 EA | | |
| 0120 | 4465000000-N | 1160 | TEMPORARY CRASH CUSHIONS | 6 EA | | |
| 0121 | 4470000000-N | 1160 | RESET TEMPORARY CRASH CUSHIONS | 6 EA | | |
| 0122 | 4480000000-N | 1165 | TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH) | 2 EA | | |
| 0123 | 4485000000-E | 1170 | PORTABLE CONCRETE BARRIER | 2,920 LF | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0124 | 4490000000-E | 1170 | PORTABLE CONCRETE BARRIER (ANCHORED) | 1,410 LF | | |
| 0125 | 4500000000-E | 1170 | RESET PORTABLE CONCRETE BARRIER | 1,900 LF | | |
| 0126 | 4505000000-E | 1170 | RESET PORTABLE CONCRETE BARRIER (ANCHORED) | 1,320 LF | | |
| 0127 | 4615000000-E | 1205 | REMOVABLE TAPE PAVEMENT MARKING LINES (4") | 874 LF | | |
| 0128 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 356 EA | | |
| 0129 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 14,287 LF | | |
| 0130 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 10,416 LF | | |
| 0131 | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 1,346 LF | | |
| 0132 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 454 LF | | |
| 0133 | 4721000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL) | 8 EA | | |
| 0134 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 47 EA | | |
| 0135 | 4770000000-E | 1205 | COLD APPLIED PLASTIC PAVEMENT MARKING LINES (4") | 795 LF | | |
| 0136 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 86,292 LF | | |
| 0137 | 4820000000-E | 1205 | PAINT PAVEMENT MARKING LINES (8") | 4,354 LF | | |
| 0138 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 644 LF | | |
| 0139 | 4840000000-N | 1205 | PAINT PAVEMENT MARKING CHARACTER | 16 EA | | |
| 0140 | 4845000000-N | 1205 | PAINT PAVEMENT MARKING SYMBOL | 42 EA | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0141 | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 15,848 LF | | |
| 0142 | 4860000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (8") | 519 LF | | |
| 0143 | 4875000000-N | 1205 | REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS | 4 EA | | |
| 0144 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 329 EA | | |
| 0145 | 5300000000-E | 1505 | FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI) | 128 TON | | |
| 0146 | 5306000000-E | SP | BEDDING MATERIAL, UTILITIES CLASS ***** (IV) | 128 TON | | |
| 0147 | 5318000000-E | 1505 | PAVEMENT REPAIR FOR UTILITY WORK | 80 TON | | |
| 0148 | 5360000000-E | 1510 | 6" DI WATER PIPE, PC 350 | 48 LF | | |
| 0149 | 5366000000-E | 1510 | 8" DI WATER PIPE, PC 350 | 290 LF | | |
| 0150 | 5378000000-E | 1510 | 12" DI WATER PIPE, PC 350 | 244 LF | | |
| 0151 | 5396000000-E | 1510 | *** DI RESTRAINED JOINT WATER PIPE, CLASS ***** (12", 50) | 65 LF | | |
| 0152 | 5402000000-E | 1510 | DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP | 1,075 LB | | |
| 0153 | 5480000000-E | 1510 | DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP | 2,490 LB | | |
| 0154 | 5540000000-E | 1510 | 6" GATE VALVE & VALVE BOX, 200# WP | 2 EA | | |
| 0155 | 5672000000-N | 1510 | RELOCATE EXISTING FIRE HYDRANT | 2 EA | | |
| 0156 | 5720000000-E | 1520 | *** DI SEWER PIPE, PC ***** (16", 350) | 757.12 LF | | |
| 0157 | 5726000000-E | 1520 | 8" DI SEWER PIPE, PC 350 | 549.06 LF | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0158 | 5732000000-E | 1520 | 10" DI SEWER PIPE, PC 350 | 383.71 | LF | |
| 0159 | 5775000000-E | 1525 | 4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH | 8 | EA | |
| 0160 | 5776000000-E | 1525 | 5' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH | 2 | EA | |
| 0161 | 5780000000-E | 1525 | PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (4') | 72 | LF | |
| 0162 | 5780000000-E | 1525 | PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (5') | 19 | LF | |
| 0163 | 5798000000-E | 1530 | FILL OR REMOVE ABANDONED *** PIPE, ***** (10", DI SEWER) | 171 | LF | |
| 0164 | 5804000000-E | 1530 | FILL OR REMOVE ABANDONED 12" PIPE, ***** (DI WATER) | 215 | LF | |
| 0165 | 5810000000-E | 1530 | FILL OR REMOVE ABANDONED 16" PIPE, ***** (DI SEWER) | 679 | LF | |
| 0166 | 5816000000-N | 1530 | BREAK DOWN, PLUG, & FILL ABANDONED UTILITY MANHOLE | 6 | EA | |
| 0167 | 5822000000-N | 1530 | BREAK DOWN & REBUILD EXISTING MANHOLE | 3 | EA | |
| 0168 | 5888000000-E | SP | GENERIC UTILITY ITEM 10" DI RESTRAINED JOINT SEWER PIPE, PC 350 | 40 | LF | |
| 0169 | 5888000000-E | SP | GENERIC UTILITY ITEM 16" DI RESTRAINED JOINT SEWER PIPE, PC 350 | 40 | LF | |
| 0170 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 4,745 | LF | |
| 0171 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 400 | TON | |
| 0172 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 3,845 | TON | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|--------------|-----------|--------|
| 0173 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 1,915 TON | | |
| 0174 | 6015000000-E | 1615 | TEMPORARY MULCHING | 4 ACR | | |
| 0175 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 0176 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.5 TON | | |
| 0177 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 600 LF | | |
| 0178 | 6027000000-N | 1622 | INLET PROTECTION AT TEMPORARY SLOPE DRAINS | 17 EA | | |
| 0179 | 6030000000-E | 1630 | SILT EXCAVATION | 11,175 CY | | |
| 0180 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 5,775 SY | | |
| 0181 | 6037000000-E | SP | COIR FIBER MAT | 2,200 SY | | |
| 0182 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 500 SY | | |
| 0183 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 1,060 LF | | |
| 0184 | 6045000000-E | SP | *** TEMPORARY PIPE (24") | 700 LF | | |
| 0185 | 6069000000-E | 1638 | STILLING BASINS | 1,020 CY | | |
| 0186 | 6070000000-N | SP | SPECIAL STILLING BASINS | 10 EA | | |
| 0187 | 6084000000-E | 1660 | SEEDING & MULCHING | 31.5 ACR | | |
| 0188 | 6087000000-E | 1660 | MOWING | 1.5 ACR | | |
| 0189 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0190 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0191 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 0192 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 23.75 TON | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0193 | 6109000000-E | SP | SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS) | 0.6 | ACR | |
| 0194 | 6111000000-E | SP | IMPERVIOUS DIKE | 250 | LF | |
| 0195 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 12 | HR | |
| 0196 | 6117000000-N | 1675 | RESPONSE FOR EROSION CONTROL | 16 | EA | |
| 0197 | 6126000000-E | SP | STREAMBANK REFORESTATION | 1.2 | ACR | |
| 0198 | 6132000000-N | SP | GENERIC EROSION CONTROL ITEM NATURAL STONE, BOULDER-2000LB | 345 | EA | |
| 0199 | 6132000000-N | SP | GENERIC EROSION CONTROL ITEM NATURAL STONE, BOULDER-4000LB | 600 | EA | |
| 0200 | 6147000000-E | SP | GENERIC EROSION CONTROL ITEM SAFETY FENCE | 2,000 | LF | |
| 0201 | 7060000000-E | 1705 | SIGNAL CABLE | 2,010 | LF | |
| 0202 | 7120000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 3 SECTION) | 22 | EA | |
| 0203 | 7144000000-E | 1705 | VEHICLE SIGNAL HEAD (12", 5 SECTION) | 13 | EA | |
| 0204 | 7252000000-E | 1710 | MESSENGER CABLE (1/4") | 140 | LF | |
| 0205 | 7264000000-E | 1710 | MESSENGER CABLE (3/8") | 1,500 | LF | |
| 0206 | 7279000000-E | 1715 | TRACER WIRE | 1,285 | LF | |
| 0207 | 7300000000-E | 1715 | TRENCHING (UNPAVED) | 2,620 | LF | |
| 0208 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 22 | EA | |
| 0209 | 7336000000-N | 1716 | JUNCTION BOX (OVER-SIZED) | 7 | EA | |
| 0210 | 7360000000-N | 1720 | WOOD POLE | 4 | EA | |
| 0211 | 7372000000-N | 1721 | GUY ASSEMBLY | 8 | EA | |

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-------------|-----------|--------|
| 0212 | 7408000000-E | 1722 | 1" RISER WITH WEATHERHEAD | 1 EA | | |
| 0213 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 1 EA | | |
| 0214 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 3,270 LF | | |
| 0215 | 7456000000-E | 1726 | LEAD-IN CABLE | 5,280 LF | | |
| 0216 | 7481000000-N | SP | SITE SURVEY | 1 EA | | |
| 0217 | 7481200000-N | SP | LUMINAIRE ARM FOR VIDEO SYSTEM | 4 EA | | |
| 0218 | 7516000000-E | 1730 | COMMUNICATIONS CABLE (**FIBER) (12) | 1,285 LF | | |
| 0219 | 7552000000-N | 1731 | INTERCONNECT CENTER | 3 EA | | |
| 0220 | 7564000000-N | 1732 | FIBER-OPTIC TRANSCEIVER | 3 EA | | |
| 0221 | 7566000000-N | 1733 | DELINEATOR MARKER | 7 EA | | |
| 0222 | 7576000000-N | 1740 | METAL STRAIN SIGNAL POLE | 12 EA | | |
| 0223 | 7613000000-N | SP | SOIL TEST | 12 EA | | |
| 0224 | 7614000000-E | SP | DRILLED PIER FOUNDATION (**" DIA) (42") | 180 LF | | |
| 0225 | 7684000000-N | 1750 | SIGNAL CABINET FOUNDATION | 3 EA | | |
| 0226 | 7688000000-N | SP | CABINET BASE ADAPTER | 3 EA | | |
| 0227 | 7756000000-N | 1751 | CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED) | 3 EA | | |
| 0228 | 7780000000-N | SP | DETECTOR CARD (TYPE 2070L) | 24 EA | | |

***** BEGIN SCHEDULE HA *****
 ***** (2 ALTERNATES) *****

| | | | | | | |
|------|--------------|----|---|---------|--|--|
| 0229 | 7481220000-N | SP | CAMERA WITH INTERNAL LOOP EMU- LATOR PROCESSING UNIT | 1 EA | | |
|------|--------------|----|---|---------|--|--|

*** OR ***

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|-------------|--------------|-------|---|----------|-----------|--------|
| 0230 HA2 | 7481240000-N | SP | CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT | 1 EA | | |
| 0231 HA2 | 7481260000-N | SP | EXTERNAL LOOP EMULATOR PROCESSING UNIT | 1 EA | | |

***** END SCHEDULE HA *****

CULVERT ITEMS

| | | | | | | |
|------|--------------|-----|---|---------------|------|--|
| 0232 | 8126000000-N | 414 | CULVERT EXCAVATION, STA ***** (17+48.00-Y1-) | Lump Sum | L.S. | |
| 0233 | 8126000000-N | 414 | CULVERT EXCAVATION, STA ***** (20+81.50-Y6-) | Lump Sum | L.S. | |
| 0234 | 8133000000-E | 414 | FOUNDATION CONDITIONING MATERIAL, BOX CULVERT | 888 TON | | |
| 0235 | 8196000000-E | 420 | CLASS A CONCRETE (CULVERT) | 1,619.3 CY | | |
| 0236 | 8245000000-E | 425 | REINFORCING STEEL (CULVERT) | 237,893 LB | | |

WALL ITEMS

| | | | | | | |
|------|--------------|----|--|----------|------|--|
| 0237 | 8832000000-N | SP | GENERIC RETAINING WALL ITEM SOIL NAIL RETAINING WALL AT STA 18+50.00 -L- | Lump Sum | L.S. | |
|------|--------------|----|--|----------|------|--|

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|-----|---|--------------|------|--|
| 0238 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (29+25.37-L- LT) | Lump Sum | L.S. | |
| 0239 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (29+25.37-L- RT) | Lump Sum | L.S. | |
| 0240 | 8147000000-E | 420 | REINFORCED CONCRETE DECK SLAB | 14,620 SF | | |
| 0241 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 17,468 SF | | |

County : Davidson

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0242 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 233 CY | | |
| 0243 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (29+25.37-L- LT) | Lump Sum | L.S. | |
| 0244 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (29+25.37-L- RT) | Lump Sum | L.S. | |
| 0245 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 28,062 LB | | |
| 0246 | 8280000000-E | 440 | APPROX LBS STRUCTURAL STEEL | 469,022 LS | | |
| 0247 | 8384000000-E | 450 | HP14X73 STEEL PILES | 2,495 LF | | |
| 0248 | 8503000000-E | 460 | CONCRETE BARRIER RAIL | 543.96 LF | | |
| 0249 | 8531000000-E | 462 | 4" SLOPE PROTECTION | 970 SY | | |
| 0250 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0251 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

0904/Aug24/Q1252173.71/D1104424620000/E251

Total Amount Of Bid For Entire Project :

C200781
DAVIDSON COUNTY

2/16/99

Contract No: C200781

Counties: Davidson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General