

STATE OF NORTH CAROLINA SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201266

| ItemNumber | Sec # | Quantity | Unit | Description | ItemNumber | Sec # | Quantity | Unit | Description |
|-------------|-------|----------|------|---|-------------|-------|----------|------|--|
| 000010000-N | 800 | Lump Sum | | MOBILIZATION | 250000000-E | 842 | 70 | CY | CONCRETE RETAINING WALLS |
| 000040000-N | 801 | Lump Sum | | CONSTRUCTION SURVEYING | 253500000-E | 846 | 305 | LF | ***X*** CONCRETE CURB (8" x 18") |
| 000093000-E | SP | 100 | LF | GENERIC MISCELLANEOUS ITEM STEEL PIPE HANDRAIL FOR RETAINING WALL | 254900000-E | 846 | 4,350 | LF | 2'-6" CONCRETE CURB & GUTTER |
| 004300000-N | 226 | Lump Sum | | GRADING | 259100000-E | 848 | 1,790 | SY | 4" CONCRETE SIDEWALK |
| 005000000-E | 226 | 1 | ACR | SUPPLEMENTARY CLEARING & GRUBBING | 259800000-E | 848 | 155 | SY | CONCRETE WHEELCHAIR RAMPS |
| 005700000-E | 226 | 1,500 | CY | UNDERCUT EXCAVATION | 261200000-E | 848 | 400 | SY | 6" CONCRETE DRIVEWAY |
| 008000000-E | SP | 325 | TON | CLASS IV SUBGRADE STABILIZATION | 264700000-E | 852 | 570 | SY | 5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED) |
| 013400000-E | 240 | 2 | CY | DRAINAGE DITCH EXCAVATION | 265500000-E | 852 | 30 | SY | 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) |
| 019500000-E | 265 | 500 | CY | SELECT GRANULAR MATERIAL | 280000000-N | 858 | 2 | EA | ADJUSTMENT OF CATCH BASINS |
| 019600000-E | 270 | 500 | SY | FABRIC FOR SOIL STABILIZATION | 283000000-N | 858 | 22 | EA | ADJUSTMENT OF MANHOLES |
| 024500000-E | SP | 500 | GAL | GENERIC GRADING ITEM DISPOSAL OF DECONTAMINATION WATER | 284500000-N | 858 | 3 | EA | ADJUSTMENT OF METER BOXES OR VALVE BOXES |
| 025500000-E | SP | 270 | TON | GENERIC GRADING ITEM DISPOSAL OF CONTAMINATED SOIL | 353600000-E | 866 | 25 | LF | CHAIN LINK FENCE, 48" FABRIC |
| 031800000-E | 300 | 245 | TON | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 354200000-E | 866 | 2 | EA | METAL LINE POSTS FOR 48" CHAIN LINK FENCE |
| 036600000-E | 310 | 1,036 | LF | 15" RC PIPE CULVERTS, CLASS III | 354800000-E | 866 | 2 | EA | METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE |
| 037200000-E | 310 | 60 | LF | 18" RC PIPE CULVERTS, CLASS III | 364900000-E | 876 | 10 | TON | PLAIN RIP RAP, CLASS B |
| 037800000-E | 310 | 1,160 | LF | 24" RC PIPE CULVERTS, CLASS III | 365600000-E | 876 | 255 | SY | FILTER FABRIC FOR DRAINAGE |
| 070800000-E | 310 | 48 | LF | 15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK | 402500000-E | 901 | 78.58 | SF | CONTRACTOR FURNISHED, TYPE *** SIGN (D) |
| 080600000-E | 310 | 6 | EA | 15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK | 402500000-E | 901 | 165.65 | SF | CONTRACTOR FURNISHED, TYPE *** SIGN (E) |
| 099500000-E | 340 | 1,200 | LF | PIPE REMOVAL | 402500000-E | 901 | 120.81 | SF | CONTRACTOR FURNISHED, TYPE *** SIGN (F) |
| 102200000-E | SP | 500 | LB | SEALING EXISTING PAVEMENT CRACKS | 407200000-E | 903 | 865 | LF | SUPPORTS, 3-LB STEEL U-CHANNEL |
| 111000000-E | 510 | 500 | TON | STABILIZER AGGREGATE | 409600000-N | 904 | 6 | EA | SIGN ERECTION, TYPE D |
| 112100000-E | 520 | 179 | TON | AGGREGATE BASE COURSE | 410200000-N | 904 | 31 | EA | SIGN ERECTION, TYPE E |
| 122000000-E | 545 | 75 | TON | INCIDENTAL STONE BASE | 410800000-N | 904 | 6 | EA | SIGN ERECTION, TYPE F |
| 130800000-E | 607 | 5,320 | SY | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (2-1/2" TO 3") | 412900000-N | 906 | 8 | EA | RELOCATE SIGN, TYPE ***** (E) |
| 133000000-E | 607 | 2,750 | SY | INCIDENTAL MILLING | 415500000-N | 907 | 30 | EA | DISPOSAL OF SIGN SYSTEM, U-CHANNEL |
| 148900000-E | 610 | 1,885 | TON | ASPHALT CONC BASE COURSE, TYPE B25.0B | 419200000-N | 907 | 7 | EA | DISPOSAL OF SUPPORT, U-CHANNEL |
| 149800000-E | 610 | 2,160 | TON | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 440000000-E | 1110 | 436 | SF | WORK ZONE SIGNS (STATIONARY) |
| 151900000-E | 610 | 3,365 | TON | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 440500000-E | 1110 | 240 | SF | WORK ZONE SIGNS (PORTABLE) |
| 156000000-E | 620 | 385 | TON | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 441000000-E | 1110 | 88 | SF | WORK ZONE SIGNS (BARRICADE MOUNTED) |
| 169300000-E | 654 | 550 | TON | ASPHALT PLANT MIX, PAVEMENT REPAIR | 441500000-N | 1115 | 2 | EA | FLASHING ARROW PANELS, TYPE C |
| 200000000-N | 806 | 36 | EA | RIGHT OF WAY MARKERS | 442500000-N | 1125 | 2 | EA | WARNING FLAG SETS |
| 202200000-E | 815 | 112 | CY | SUBDRAIN EXCAVATION | 443000000-N | 1130 | 130 | EA | DRUMS |
| 203300000-E | 815 | 84 | CY | SUBDRAIN FINE AGGREGATE | 443500000-N | 1135 | 110 | EA | CONES |
| 204400000-E | 815 | 500 | LF | 6" PERFORATED SUBDRAIN PIPE | 444000000-E | 1145 | 174 | LF | BARRICADES (TYPE II) |
| 205500000-E | 815 | 15 | EA | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 444500000-E | 1145 | 96 | LF | BARRICADES (TYPE III) |
| 206600000-N | 815 | 1 | EA | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 445500000-N | 1150 | 180 | MD | FLAGGER |
| 207700000-E | 815 | 6 | LF | 6" OUTLET PIPE (SUBDRAINS) | 452000000-N | 1266 | 35 | EA | TUBULAR MARKERS (FIXED) |
| 219000000-N | 828 | 3 | EA | TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE | 459000000-E | SP | 650 | LF | GENERIC TRAFFIC CONTROL ITEM DEPARTMENT FURNISHED WATER-FILLED BARRIER |
| 225300000-E | 840 | 1 | CY | PIPE COLLARS | 460000000-N | SP | 2 | EA | GENERIC TRAFFIC CONTROL ITEM DEPARTMENT FURNISHED CMS'S |
| 226400000-E | 840 | 1 | CY | PIPE PLUGS | 465000000-N | 1251 | 266 | EA | TEMPORARY RAISED PAVEMENT MARKERS |
| 228600000-N | 840 | 36 | EA | MASONRY DRAINAGE STRUCTURES | 468500000-E | 1205 | 325 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) |
| 236400000-N | 840 | 9 | EA | FRAME WITH TWO GRATES, STD 840.16 | 468600000-E | 1205 | 5,423 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) |
| 237400000-N | 840 | 13 | EA | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F) | 469500000-E | 1205 | 53 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) |
| 237400000-N | 840 | 11 | EA | FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G) | 469700000-E | 1205 | 1,185 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) |
| 239600000-N | 840 | 4 | EA | FRAME WITH COVER, STD 840.54 | 470500000-E | 1205 | 172 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS) |
| 245100000-N | 840 | 2 | EA | CONCRETE APRON FOR DROP INLETS | 471000000-E | 1205 | 402 | LF | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) |
| | | | | | 472100000-E | 1205 | 12 | EA | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL) |