


PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1 1/2" IN DEPTH.
D1	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2 1/4" IN DEPTH OR GREATER THAN 4" IN DEPTH.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E2	PROP. APPROX. 4 1/2" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD.
E3	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5 1/2" IN DEPTH.
J1	PROP. 6" AGGREGATE BASE COURSE
R1	2'-6" CONCRETE CURB & GUTTER
R2	5" MONOLITHIC CONCRETE ISLAND.
S	4" CONCRETE SIDEWALK.


T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
V	MILLING SEE SHEET 3A FOR LOCATIONS OF MILLING OF THE EXISTING PAVEMENT
W	WEDGING

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




TYPICAL SECTION NO. 1A


USE TYPICAL NO. 1A AS FOLLOWS:
 -L- STA. 21+50.00 TO STA. 24+36.86
 -L- STA. 24+95.11 TO STA. 27+00.00
 SEE TRAFFIC CONTROL PLANS



Detail Showing Method Of Wedging



Wedging Detail For Resurfacing



TYPICAL SECTION NO. 1

USE TYPICAL NO. 1 AS FOLLOWS:
 -L- STA. 10+00.00 TO STA. 29+70.00
 -RPD- STA. 10+08.00 TO STA. 11+00.17

NOTES:
 * SEE PLANS FOR PAVEMENT TRANSITIONS
 ** 4 ft CONC. ISLAND LOCATION VARIES SEE PLANS
 † SHARED BICYCLE - VEHICLE LANE