PROJ. REFERENCE NO.	SHEET NO.
U-4010	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.000	0	0
10+50.000	12	3
11+00.000	5	3
11+50.000	0	0
12+00.000	60	0
12+50.000	192	0
13+00.000	225	0
13+50.000	180	0
14+00.000	153	0
14+50.000	115	0
15+00.000	50	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+00.000	0	0
15+50.000	58	2
16+00.000	69	3
16+50.000	56	6
17+00.000	47	13
17+50.000	60	13
18+00.000	73	8
18+50.000	70	9
19+00.000	67	12
19+50.000	35	8
20+00.000	4	2

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+00.000	0	0
20+50.000	43	11
21+00.000	47	26
21+50.000	19	36
22+00.000	28	24
22+50.000	27	21
23+00.000	19	30
23+50.000	15	48
24+00.000	6	30

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+00.000	0	0
24+50.000	34	12
25+00.000	38	0
25+50.000	34	7
26+00.000	18	25
26+50.000	19	23
27+00.000	22	11
27+50.000	15	32
28+00.000	14	34
28+50.000	17	14

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
29+00.000	16	6
29+50.000	14	2
29+70.000	5	0
30+00.000	4	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.000	0	0
10+50.000	11	45
11+00.000	11	61
11+50.000	11	40
12+00.000	9	36
12+50.000	9	19
13+00.000	9	12
13+50.000	10	9
14+00.000	10	10
14+50.000	14	6
15+00.000	16	2
15+50.000	12	2
16+00.000	11	2
16+50.000	12	2
17+00.000	11	3
17+50.000	18	3
18+00.000	25	0
18+50.000	34	0
19+00.000	47	0
19+50.000	24	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+50.000	0	0
20+00.000	0	0
20+50.000	7	2
21+00.000	13	2
21+50.000	13	1
22+00.000	11	4
22+50.000	11	5
23+00.000	12	3
23+50.000	6	1

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
24+00.000	6	8
24+50.000	13	13
25+00.000	14	6
25+50.000	12	5
26+00.000	11	5
26+50.000	11	4
27+00.000	11	10
27+50.000	9	17

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
28+00.000	9	21
28+50.000	9	18
29+00.000	11	8
29+50.000	12	1
29+70.000	5	0
30+00.000	4	0

Station Rpd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.000	0	0
10+10.000	3	1
10+20.000	6	3
10+30.000	7	3
10+40.000	9	3
10+50.000	11	4
10+60.000	13	4
10+70.000	16	4
10+80.000	21	3
10+90.000	12	1

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.000	0	0
11+00.000	46	8
11+50.000	42	11
11+80.000	20	2

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.000	0	0
10+50.000	5	9
11+00.000	9	15
11+50.000	18	12
12+00.000	59	6

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.000	0	0
14+00.000	19	60
14+50.000	22	66
15+00.000	9	26

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.000	0	0
11+00.000	19	58
11+50.000	11	61
12+00.000	25	47

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+50.000	28	37
13+00.000	30	32
13+50.000	22	27
14+00.000	10	59
14+50.000	11	95
15+00.000	8	48
15+10.000	0	0
15+20.000	0	0