

**SUMMARY OF EARTHWORK**

LINE	STATION	STATION	EXCAV. (UNCL.)	UNDERCUT EXCAV.	EMB. +%	BORROW	TOTAL WASTE
	SUMMARY No.1						
-L-	13+00 LT	16+78 LT	148		30		118
-L-	18+58 LT	24+00 LT	127		240	113	
	SUBTOTAL		275		270		118
	WASTE IN LIEU OF BORROW					-113	-113
	TOTAL SUMMARY No.1		275		270		5
	SUMMARY No.2						
-L-	13+00 RT	16+78 RT	1,385		8		1,376
-L-	18+58 RT	24+00 RT	2,021		164		1,857
	TOTAL SUMMARY No.2		3,406		172		3,233
	PROJECT TOTAL		3,681		442		3,238
	UNDERCUT CONTINGENCY ITEM FILLED WITH SELECT GRANULAR MATERIAL			500			500
	PROJECT GRAND TOTALS		3,681	500	442		3,738
	SAY		3,700	500			
	DDE = 12 CY						
	-L- PAVEMENT STRUCTURE VOLUME = 100 CY						

**SUMMARY OF EXISTING ASPHALT  
PAVEMENT REMOVAL**

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
-DET-	12+54.69	15+09.16	RT	254.47	12	339
-DET-	15+09.16	17+06	RT	196.84	24	525
-DET-	18+61	21+03.53	RT	242.53	24	647
-DET-	21+03.53	23+94.99	RT	4,249.43	1	472
-L-	16+67	16+78	CL	11	24	29
-L-	18+58	18+69	CL	11	24	29
					TOTAL	2,042
					SAY	2,070