PROJ. REFERENCE NO.	SHEET NO.
B-4139	X-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	0	0
14+00.00	13	0
14+50.00	67	0
15+00.00	60	2
15+50.00	0	9
16+00.00	0	11
16+50.00	1	3

Station -L- LEFT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+00.00	0	0
19+50.00	9	12
20+00.00	12	16
20+50.00	13	18
21+00.00	18	8
21+50.00	9	0
22+00.00	0	36
22+50.00	2	56
23+00.00	6	27
23+50.00	22	10
24+00.00	29	4

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	0	0
14+00.00	39	0
14+50.00	87	0
15+00.00	177	0
15+50.00	257	2
16+00.00	288	3
16+50.00	311	2

Station -L- RIGHT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
19+00.00	0	0
19+50.00	274	12
20+00.00	261	19
20+50.00	272	29
21+00.00	298	32
21+50.00	287	21
22+00.00	199	6
22+50.00	95	0
23+00.00	27	1
23+50.00	10	2
24+00.00	25	4