

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200847

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL STATION ***** (16+67.50)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0195000000-E	265	200	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	40	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	16	LF	15" SIDE DRAIN PIPE
0366000000-E	310	306	LF	15" RC PIPE CULVERTS, CLASS III
0582000000-E	310	32	LF	15" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	4	EA	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")
0995000000-E	340	351	LF	PIPE REMOVAL
1220000000-E	545	6	TON	INCIDENTAL STONE BASE
1330000000-E	607	340	SY	INCIDENTAL MILLING
1489000000-E	610	400	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	330	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B
1519000000-E	610	480	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	62	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	6	EA	MASONRY DRAINAGE STRUCTURES
2364000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.16
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	170	LF	SHOULDER BERM GUTTER
3030000000-E	862	450	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS

ItemNumber	Sec #	Quantity	Unit	Description
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3649000000-E	876	5	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	165	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4400000000-E	1110	303	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	2	EA	WARNING FLAG SETS
4445000000-E	1145	56	LF	BARRICADES (TYPE III)
4810000000-E	1205	6,202	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	10	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	750	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	125	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6030000000-E	1630	275	CY	SILT EXCAVATION
6036000000-E	1631	675	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	250	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	0.5	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.5	TON	FERTILIZER TOPDRESSING

ItemNumber	Sec #	Quantity	Unit	Description
6114000000-N	SP	0.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

10-FEB-2004 09:53
R:\Roadway\PROJECTS\3871-RD\SUMMARIES.dgn
R:\Roadway\PROJECTS\3871-RD\SUMMARIES.dgn