PROJ. REFERENCE NO.	SHEET NO.
B-3504	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	DDE (cu. yd.)
12+45.00	0	0	
12+50.00	5	0	
13+00.00	56	10	
13+50.00	45	10	
14+00.00	112	12	
14+50.00	160	24	
15+00.00	148	41	
15+50.00	129	64	
16+00.00	102	96	6
16+50.00	68	127	19
17+00.00	54	163	19
17+50.00	61	220	
18+00.00	104	339	
18+18.00	50	153	
18+50.00	0	0	67

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	DDE (cu. yd.)
19+23.00	0	757	
19+50.00	0	757	306
20+00.00	0	1460	125
20+50.00	0	1633	39
21+00.00	0	1792	40
21+50.00	0	1741	32
22+00.00	0	1548	23
22+50.00	0	1373	24
23+00.00	6	667	
23+04.81	1	2	