

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200962

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+41.00)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	300	CY	UNDERCUT EXCAVATION
0134000000-E	240	90	CY	DRAINAGE DITCH EXCAVATION
0318000000-E	300	19	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0372000000-E	310	52	LF	18" RC PIPE CULVERTS, CLASS III
0396000000-E	310	96	LF	42" RC PIPE CULVERTS, CLASS III
0708000000-E	310	24	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0995000000-E	340	88	LF	PIPE REMOVAL
1121000000-E	520	130	TON	AGGREGATE BASE COURSE
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1275000000-E	600	100	GAL	PRIME COAT
1489000000-E	610	430	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	350	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	42	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	15	LF	SHOULDER BERM GUTTER
3030000000-E	862	375	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350

ItemNumber	Sec #	Quantity	Unit	Description
3503000000-E	866	900	LF	WOVEN WIRE FENCE, 47" FABRIC
3509000000-E	866	55	EA	4" TIMBER FENCE POSTS, 7'-6" LONG
3515000000-E	866	25	EA	5" TIMBER FENCE POSTS, 8'-0" LONG
3575000000-E	SP	400	LF	GENERIC FENCING ITEM THREE STRAND ELECTRIC FENCE (COMPLETE WITH POSTS)
3649000000-E	876	35	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	960	SY	FILTER FABRIC FOR DRAINAGE
4400000000-E	1110	96	SF	WORK ZONE SIGNS (STATIONARY)
4410000000-E	1110	90	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	30	EA	DRUMS
4445000000-E	1145	96	LF	BARRICADES (TYPE III)
4810000000-E	1205	17,600	LF	PAINT PAVEMENT MARKING LINES (4")
6000000000-E	1605	370	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	325	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	460	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	0.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
6024000000-E	1622	190	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	6	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6030000000-E	1630	835	CY	SILT EXCAVATION
6036000000-E	1631	1,170	SY	MATting FOR EROSION CONTROL
6070000000-N	SP	16	EA	SPECIAL STILLING BASINS
6084000000-E	1660	0.5	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING

ItemNumber	Sec #	Quantity	Unit	Description
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.25	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

23-APR-2004 10:06  
R:\Pro\3690\sum  
RWDum AT R0188656