Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
B-3690	X-1A

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+50.00	12	20
13+00.00	27	54
13+50.00	36	91
14+00.00	68	132
14+50.00	87	93
15+00.00	49	548
15+50.00	10	851
16+00.00	0	894
16+21.58	0	497

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+60.42	0	0
19+00.00	0	632
19+50.00	0	627
20+00.00	0	459
20+50.00	5	387
21+00.00	11	223
21+50.00	45	111
22+00.00	63	55
22+50.00	72	16
23+00.00	63	5

Station L	Uncl. Exc. EMB REM (cu. yd.)	Embt (cu. yd.)
18+50.00	0	0
19+00.00	159	0
19+50.00	33	0
20+00.00	16	0

Station DR1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+20.00	0	25
10+40.00	0	117
10+60.00	0	177
10+80.00	0	160
11+00.00	0	107
11+20.00	0	45
11+40.00	2	8
11+50.00	2	0

Station DDE LT L	DDE Exc. (cu. yd.)	
15+20.00	0	
15+50.00	14	
16+00.00	42	
16+38.00	29	