

FINAL PAVEMENT MARKING SCHEDULE



PROJ. REFERENCE NO.	SHEET NO.
B-3256	PM-1

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY BREAKDOWN		TOTAL QUANTITY	
FINAL PAVEMENT MARKINGS					
THERMOPLASTIC (100MM, 2.3MM)					
TA	WHITE EDGELINE	328	M		
				TOTAL	328 M
THERMOPLASTIC (100MM, 3.1MM)					
TD	0.5 M. WHITE MINISKIP	7	M		
TE	WHITE SOLID LANE LINE	59	M		
TF	3 M. YELLOW SKIP	140	M		
TH	YELLOW SINGLE CENTER	554	M		
TI	YELLOW DOUBLE CENTER	988	M		
				TOTAL	1748 M
THERMOPLASTIC (200MM, 2.3MM)					
TT	YELLOW DIAGONAL	56	M		
				TOTAL	56 M
THERMOPLASTIC (400MM, 3.1MM)					
T1	WHITE LINE, RR CROSSB	14	M		
				TOTAL	14 M
THERMOPLASTIC (600MM, 3.1MM)					
T2	WHITE STOPBAR	8	M		
				TOTAL	8 M
THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)					
UI	ALPHANUMERIC CHAR.	2	EA		
				TOTAL	2 EA
THERMOPLASTIC PAVEMENT MARKING SYMBOLS (2.3MM)					
UA	LEFT TURN ARROW	9	EA		
UE	COMBO. STRAIGHT/RIGHT	3	EA		
				TOTAL	12 EA
COLD APPLIED PLASTIC (100MM)					
CA	WHITE EDGELINE	64	M		
CF	3 M. YELLOW SKIP	16	M		
CH	YELLOW SINGLE CENTER	64	M		
				TOTAL	144 M
MARKERS					
PERMANENT RAISED PAVEMENT MARKERS					
MA	YELLOW & YELLOW	116	EA		
MB	CRYSTAL & RED	28	EA		
				TOTAL	144 EA

09-JAN-2004 10:42
 G:\TCP\B3256-TS\PMPl.dgn
 Kbroodwell AT TETC207913

APPROVED: <i>J.W. Woolard, Jr.</i>	DATE: 1/12/04	FINAL PAVEMENT MARKING SCHEDULE	
	SCALE: NONE	REVISIONS	
	DATE: 1/8/04		
	DESIGN BY: KPB		
	REVIEWED BY: JWW		
			CADD FILE: