

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM ROADWAY CONSTRUCTION	Lump Sum	L.S.	
0003	7060000000-E	1705	SIGNAL CABLE	4,195 LF		
0004	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	44 EA		
0005	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		
0006	7252000000-E	1710	MESSENGER CABLE (1/4")	400 LF		
0007	7264000000-E	1710	MESSENGER CABLE (3/8")	1,210 LF		
0008	7279000000-E	1715	TRACER WIRE	5,500 LF		
0009	7300000000-E	1715	TRENCHING (UNPAVED)	6,395 LF		
0010	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)	945 LF		
0011	7302000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, 1-1/4" (** CONDUIT) (1)	400 LF		
0012	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	23 EA		
0013	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	18 EA		
0014	7360000000-N	1720	WOOD POLE	6 EA		
0015	7372000000-N	1721	GUY ASSEMBLY	18 EA		
0016	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0017	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0018	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	4 EA		
0019	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,325 LF		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	7456000000-E	1726	LEAD-IN CABLE	2,825 LF		
0021	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	7,500 LF		
0022	7552000000-N	1731	INTERCONNECT CENTER	3 EA		
0023	7566000000-N	1733	DELINEATOR MARKER	8 EA		
0024	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORA- TION KIT	1 EA		
0025	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
0026	7575160000-E	SP	REMOVE EXISTING COMMUNICATIONS CABLE	500 LF		
0027	7588000000-N	1741	SIGNAL SUPPORT MAST ARM WITH METAL POLE	10 EA		
0028	7590000000-N	SP	DOUBLE MAST ARM WITH METAL POLE	1 EA		
0029	7613000000-N	SP	SOIL TEST	11 EA		
0030	7614000000-E	SP	DRILLED PIER FOUNDATION (***) DIA) (42")	165 LF		
0031	7631000000-N	1744	MAST ARM WITH METAL POLE DE- SIGN	11 EA		
0032	7636000000-N	1745	SIGN FOR SIGNALS	18 EA		
0033	7684000000-N	1750	SIGNAL CABINET FOUNDATION	5 EA		
0034	7720000000-N	1751	CONTROLLER WITH CABINET (TYPE 170E, BASE MOUNTED)	3 EA		
0035	7744000000-N	SP	DETECTOR CARD (TYPE 170)	13 EA		
0036	7980000000-N	SP	GENERIC SIGNAL ITEM FIBER-OPTIC TRANSCEIVER - SELF HEALING RING	4 EA		

County : Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0037	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+99.30 -L-)	Lump Sum	L.S.	
0038	8105500000-E	SP	***_*** DIA DRILLED PIERS IN SOIL (3'-0")	70.9 LF		
0039	8105600000-E	SP	***_*** DIA DRILLED PIERS NOT IN SOIL (3'-0")	43.1 LF		
0040	8111000000-E	SP	PERMANENT STEEL CASING FOR ***_*** DIA DRILLED PIER (3'-0")	69 LF		
0041	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0042	8116000000-E	SP	CSL TUBES	516 LF		
0043	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	823 CY		
0044	8364000000-E	450	HP12X53 STEEL PILES	240 LF		
0045	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	435 TON		
0046	8765000000-N	SP	CONSTRUCTION OF SUBSTRUCTURE	Lump Sum	L.S.	
0047	8766000000-N	SP	CONSTRUCTION OF SUPERSTRUCTURE	Lump Sum	L.S.	
0048	8990000000-N	SP	CONTRACT TIME	1,000 DOL		

0936/Dec08/Q35776.0/D353926260000/E48

Total Amount Of Bid For Entire Project :

C200852 (B-3451)  
DURHAM COUNTY

2/16/99

Contract No: C200852

County: Durham

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General