

ItemNumber	Sec #	Quantity	Unit	Description
5576000000-M	1510	2	EA	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (200MM X 150MM, 1.38MPA WP)
5576000000-M	1510	1	EA	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (200MM X 200MM, 1.38MPA WP)
5576000000-M	1510	1	EA	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (300MM X 300MM, 1.38MPA WP)
5576000000-M	1510	1	EA	*** X ***MM TAPPING SLEEVE, VALVE & VALVE BOX, ****MPA WP (400MM X 150MM, 1.38MPA WP)
5582000000-M	1510	5	EA	*** X ***MM TAPPING SADDLE (150MM X 20MM)
5582000000-M	1510	1	EA	*** X ***MM TAPPING SADDLE (150MM X 50MM)
5582000000-M	1510	49	EA	*** X ***MM TAPPING SADDLE (200MM X 20MM)
5582000000-M	1510	1	EA	*** X ***MM TAPPING SADDLE (200MM X 25MM)
5582000000-M	1510	2	EA	*** X ***MM TAPPING SADDLE (200MM X 50MM)
5582000000-M	1510	10	EA	*** X ***MM TAPPING SADDLE (300MM X 20MM)
5582000000-M	1510	6	EA	*** X ***MM TAPPING SADDLE (300MM X 25MM)
5582000000-M	1510	2	EA	*** X ***MM TAPPING SADDLE (300MM X 50MM)
5582000000-M	1510	8	EA	*** X ***MM TAPPING SADDLE (400MM X 20MM)
5624000000-M	1510	1	EA	200MM TRANSITION COUPLING, ***** (DI TO AC)
5642000000-M	1510	1	EA	400MM TRANSITION COUPLING, ***** (DI TO AC)
5648000000-N	1510	84	EA	RELOCATE EXISTING WATER METER
5654000000-M	SP	4	EA	RELOCATE EXISTING ***MM WATER METER & METER VAULT (50MM)
5660000000-N	SP	3	EA	REMOVE EXISTING WATER METER
5666000000-M	1510	1	EA	FIRE HYDRANT, ****MPA WP (1.03 MPA WP)

ItemNumber	Sec #	Quantity	Unit	Description
5672000000-N	1510	23	EA	RELOCATE EXISTING FIRE HYDRANT
5690000000-M	1520	272	M	***MM PVC SEWER PIPE, SDR ** (100MM, SDR 21)
5690000000-M	1520	55	M	***MM PVC SEWER PIPE, SDR ** (150MM, SDR 21)
5708000000-M	1520	12	M	***MM PVC FORCE MAIN SEWER PIPE, ***** (150MM, C900, DR 18, 1.03MPA WP)
5714000000-M	1520	355	M	***MM DI SEWER PIPE, CLASS *** (200MM, CLASS 51)
5714000000-M	1520	36	M	***MM DI SEWER PIPE, CLASS *** (500MM, CLASS 51)
5756000000-M	1520	136	KG	DUCTILE IRON SEWER PIPE FITTINGS, 1.72MPA MIN WP
5768000000-N	1520	46	EA	SANITARY SEWER CLEAN-OUT
5775000000-M	1525	8	EA	1200MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH
5776000000-M	1525	1	EA	1500MM DIA PRECAST CONC SEWER MANHOLE 0-1.8M DEPTH
5780000000-M	1525	7.5	M	PRECAST CONC MANHOLE WALL, ****MM DIA, OVER 1.8M HT (1200MM)
5780000000-M	1525	6.2	M	PRECAST CONC MANHOLE WALL, ****MM DIA, OVER 1.8M HT (1500MM)
5786000000-M	1525	0.81	M	SEWER MANHOLE OUTSIDE DROP ASSEMBLY
5798000000-M	1530	368	M	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (200MM CI WATER PIPE)
5798000000-M	1530	80	M	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (200MM, AC WATER PIPE)
5798000000-M	1530	304	M	FILL OR REMOVE ABANDONED ***MM PIPE, ***** (200MM, TCP SEWER PIPE)
5804000000-M	1530	69	M	FILL OR REMOVE ABANDONED 300MM PIPE, ***** (CI WATER PIPE)
5810000000-M	1530	150	M	FILL OR REMOVE ABANDONED 400MM PIPE, ***** (AC WATER PIPE)

ItemNumber	Sec #	Quantity	Unit	Description
5810000000-M	1530	18	M	FILL OR REMOVE ABANDONED 400MM PIPE, ***** (CI WATER PIPE)
5810000000-M	1530	14	M	FILL OR REMOVE ABANDONED 400MM PIPE, ***** (DI WATER PIPE)
5816000000-N	1530	1	EA	BREAK DOWN, PLUG, & FILL ABANDONED UTILITY MANHOLE
5822000000-N	1530	15	EA	BREAK DOWN & REBUILD EXISTING MANHOLE
5882000000-N	SP	6	EA	GENERIC UTILITY ITEM 200MM TRANSITION COUPLING, DI TO TC
5882000000-N	SP	30	EA	GENERIC UTILITY ITEM CUT IN SANITARY SEWER CLEAN OUT
5882000000-N	SP	1	EA	GENERIC UTILITY ITEM RELOCATE EXISTING 150MM DRAIN VALVE
5882000000-N	SP	10	EA	GENERIC UTILITY ITEM RELOCATE EXISTING SANITARY SEWER CLEAN OUT
5912000000-N	SP	Lump Sum		GENERIC UTILITY ITEM WGP-TRANSCO / REMOVAL OF PIPE-LINE CASINGS
6000000000-M	1605	3,095	M	TEMPORARY SILT FENCE
6006000000-M	1610	740	MTN	STONE FOR EROSION CONTROL, CLASS A
6009000000-M	1610	3,915	MTN	STONE FOR EROSION CONTROL, CLASS B
6012000000-M	1610	2,875	MTN	SEDIMENT CONTROL STONE
6015000000-M	1615	5	HA	TEMPORARY MULCHING
6018000000-M	1620	300	KG	SEED FOR TEMPORARY SEEDING
6021000000-M	1620	2.5	MTN	FERTILIZER FOR TEMPORARY SEEDING
6024000000-M	1622	250	M	TEMPORARY SLOPE DRAINS
6027000000-N	1622	12	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-M	SP	360	M	SAFETY FENCE
6030000000-M	1630	11,255	M3	SILT EXCAVATION
6036000000-M	1631	11,115	M2	MATting FOR EROSION CONTROL

ItemNumber	Sec #	Quantity	Unit	Description
6042000000-M	1632	1,485	M	6.4MM HARDWARE CLOTH
6084000000-M	1660	7	HA	SEEDING & MULCHING
6087000000-M	1660	3	HA	MOWING
6090000000-M	1661	75	KG	SEED FOR REPAIR SEEDING
6093000000-M	1661	0.25	MTN	FERTILIZER FOR REPAIR SEEDING
6096000000-M	1662	200	KG	SEED FOR SUPPLEMENTAL SEEDING
6108000000-M	1665	11.25	MTN	FERTILIZER TOPDRESSING
6109000000-M	SP	0.2	HA	SPECIALIZED SEEDING UNDER GUIDERAIL & GUARDRAIL (HARD FESCUE/BUEGRASS)
6114000000-N	SP	10	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	16	EA	RESPONSE FOR EROSION CONTROL
7036000000-M	1705	12	EA	PEDESTRIAN SIGNAL HEAD (300MM, 1 SECTION)
7060000000-M	1705	5,605	M	SIGNAL CABLE
7120000000-M	1705	91	EA	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)
7132000000-M	1705	7	EA	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)
7144000000-M	1705	32	EA	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)
7252000000-M	1710	3,900	M	MESSENGER CABLE (6.35MM)
7264000000-M	1710	965	M	MESSENGER CABLE (9.52MM)
7279000000-M	1715	500	M	TRACER WIRE
7288000000-M	1715	210	M	TRENCHING (PAVED)
7300000000-M	1715	2,060	M	TRENCHING (UNPAVED)
7301000000-M	SP	170	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ****MM (** CONDUIT) (50MM, 1)
7301000000-M	SP	710	M	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ****MM (** CONDUIT) (50MM, 2)
7324000000-N	1716	62	EA	JUNCTION BOX (STANDARD SIZE)
7336000000-N	1716	28	EA	JUNCTION BOX (OVER-SIZED)
7360000000-N	1720	25	EA	WOOD POLE

ItemNumber	Sec #	Quantity	Unit	Description
7372000000-N	1721	87	EA	GUY ASSEMBLY
7408000000-M	1722	4	EA	25MM RISER WITH WEATHERHEAD
7420000000-M	1722	28	EA	50MM RISER WITH WEATHERHEAD
7432000000-M	1722	19	EA	50MM RISER WITH HEAT SHRINK TUBING
7444000000-M	1725	4,765	M	INDUCTIVE LOOP SAWCUT
7456000000-M	1726	10,250	M	LEAD-IN CABLE
7484000000-N	SP	1	EA	MICROWAVE VEHICLE DETECTOR
7516000000-M	1730	2,200	M	COMMUNICATIONS CABLE (**FIBER) (12)
7516000000-M	1730	3,500	M	COMMUNICATIONS CABLE (**FIBER) (24)
7552000000-N	1731	9	EA	INTERCONNECT CENTER
7566000000-N	1733	19	EA	DELINEATOR MARKER
7568000000-N	SP	1	EA	FURNISH FIBER-OPTIC RESTORATION KIT
7570000000-N	SP	1	EA	FURNISH FIBER-OPTIC POWER METER
7572000000-N	SP	1	EA	FURNISH OPTICAL LIGHT GENERATOR
7574000000-N	SP	1	EA	FURNISH FIBER-OPTIC TRANSCIVER
7575140000-N	SP	1	EA	FIBER-OPTIC SPLICE CABINET (BASE MOUNTED)
7588000000-N	1741	19	EA	SIGNAL SUPPORT MAST ARM WITH METAL POLE
7590000000-N	SP	5	EA	DOUBLE MAST ARM WITH METAL POLE
7613000000-N	SP	24	EA	SOIL TEST
7614000000-M	SP	110	M	DRILLED PIER FOUNDATION (**MM DIA) (1220MM)
7624000000-N	1743	2	EA	SIGNAL PEDESTAL WITH FOUNDATION
7631000000-N	1744	24	EA	MAST ARM WITH METAL POLE DESIGN
7636000000-N	1745	21	EA	SIGN FOR SIGNALS

ItemNumber	Sec #	Quantity	Unit	Description
7675000000-N	SP	12	EA	LED BLANKOUT SIGN
7684000000-N	1750	9	EA	SIGNAL CABINET FOUNDATION
7688000000-N	SP	8	EA	CABINET BASE ADAPTER
7756000000-N	1751	8	EA	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)
7780000000-N	SP	82	EA	DETECTOR CARD (TYPE 2070L)
7980000000-N	SP	8	EA	GENERIC SIGNAL ITEM FIBER-OPTIC TRANSCIVER, SELF HEALING RING
8049000000-N	SP	Lump Sum		REMOVAL OF EXISTING STRUCTURE AT STATION ***** (51+20-L-)
8800000000-N	SP	Lump Sum		MSE RETAINING WALL, STA ***** (51+83-L-)