

SURFACING SCHEDULE

ITEM NO	DESCRIPTION
C1	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 140 LBS. PER SQ. YD. (1 1/4")
C2	ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. (1 1/2")
C3	PROPOSED VARIABLE DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. (LEVELING COURSE)
C4	PROPOSED VARIABLE DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. (LEVELING COURSE)
D1	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B AT AN AVERAGE RATE OF 257 LBS. PER SQ. YD. (2 1/4")
D2	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD. (3")
V1	MILLING ASPHALT PAVEMENT 3" IN DEPTH & 4 ft. OR GREATER IN WIDTH IN DISTRESSED AREAS AS DIRECTED BY THE PROJECT ENGINEER.
V2	VARIABLE DEPTH MILLING, 1 1/2" TO 3", AS DIRECTED BY PROJECT ENGINEER.
V3	VARIABLE DEPTH MILLING, 3 3/4" TO 5", AS DIRECTED BY PROJECT ENGINEER.
T	SHOULDER RECONSTRUCTION WITH ABCM - SEE SPECIAL PROVISIONS

PROJECT REFERENCE NO.		SHEET NO.
14CR.10441.1		9 OF 9
STATE PROJECT	F.A. PROJECT NO.	DESCRIPTION
14CL10441.1		
14CL20441.2		
14CR.304404.2		
14CR.304422.2		

