

County : Transylvania

| Line #               | Item Number  | Sec # | Description   | Quantity    | Unit Cost | Amount |
|----------------------|--------------|-------|---|-------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |   |             |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION  | Lump Sum    | L.S.      |        |
| 0002                 | 0022000000-E | 225   | UNCLASSIFIED EXCAVATION   | 2,000<br>CY |           |        |
| 0003                 | 0029000000-N | SP    | REINFORCED BRIDGE APPROACH<br>FILL, STATION *****<br>(14+59.00) | Lump Sum    | L.S.      |        |
| 0004                 | 0050000000-E | 226   | SUPPLEMENTARY CLEARING & GRUB-<br>BING                          | 1<br>ACR    |           |        |
| 0005                 | 0057000000-E | 226   | UNDERCUT EXCAVATION   | 50<br>CY    |           |        |
| 0006                 | 0063000000-N | SP    | GRADING   | Lump Sum    | L.S.      |        |
| 0007                 | 0134000000-E | 240   | DRAINAGE DITCH EXCAVATION                                       | 15<br>CY    |           |        |
| 0008                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATE-<br>RIAL, MINOR STRS               | 6<br>TON    |           |        |
| 0009                 | 0343000000-E | 310   | 15" SIDE DRAIN PIPE   | 32<br>LF    |           |        |
| 0010                 | 0708000000-E | 310   | 15" BIT COAT CS PIPE CULVERTS,<br>TYPE B 0.064" THICK           | 24<br>LF    |           |        |
| 0011                 | 0995000000-E | 340   | PIPE REMOVAL  | 41<br>LF    |           |        |
| 0012                 | 1121000000-E | 520   | AGGREGATE BASE COURSE   | 590<br>TON  |           |        |
| 0013                 | 1220000000-E | 545   | INCIDENTAL STONE BASE   | 100<br>TON  |           |        |
| 0014                 | 1275000000-E | 600   | PRIME COAT  | 460<br>GAL  |           |        |
| 0015                 | 1525000000-E | SP    | ASPHALT CONC SURFACE COURSE,<br>TYPE SF9.5A                     | 340<br>TON  |           |        |
| 0016                 | 1560000000-E | 620   | ASPHALT BINDER FOR PLANT MIX,<br>GRADE PG 64-22                 | 23<br>TON   |           |        |
| 0017                 | 2286000000-N | 840   | MASONRY DRAINAGE STRUCTURES                                     | 1<br>EA     |           |        |
| 0018                 | 2367000000-N | 840   | FRAME WITH TWO GRATES, STD<br>840.29                            | 1<br>EA     |           |        |
| 0019                 | 2556000000-E | 846   | SHOULDER BERM GUTTER  | 100<br>LF   |           |        |

| Line # | Item Number  | Sec # | Description                            | Quantity     | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0020   | 3030000000-E | 862   | STEEL BM GUARDRAIL                     | 75<br>LF     |           |        |
| 0021   | 3045000000-E | 862   | STEEL BM GUARDRAIL, SHOP<br>CURVED     | 100<br>LF    |           |        |
| 0022   | 3150000000-N | 862   | ADDITIONAL GUARDRAIL POSTS             | 5<br>EA      |           |        |
| 0023   | 3195000000-N | 862   | GUARDRAIL ANCHOR UNITS, TYPE<br>AT-1   | 2<br>EA      |           |        |
| 0024   | 3215000000-N | 862   | GUARDRAIL ANCHOR UNITS, TYPE<br>III    | 4<br>EA      |           |        |
| 0025   | 3270000000-N | SP    | GUARDRAIL ANCHOR UNITS, TYPE<br>350    | 2<br>EA      |           |        |
| 0026   | 3649000000-E | 876   | PLAIN RIP RAP, CLASS B                 | 30<br>TON    |           |        |
| 0027   | 3656000000-E | 876   | FILTER FABRIC FOR DRAINAGE             | 400<br>SY    |           |        |
| 0028   | 4412000000-E | SP    | WORK ZONE SIGNS (STATIONARY)           | 211<br>SF    |           |        |
| 0029   | 4412100000-E | SP    | WORK ZONE SIGNS (PORTABLE)             | 192<br>SF    |           |        |
| 0030   | 4412200000-E | SP    | WORK ZONE SIGNS (BARRICADE<br>MOUNTED) | 70<br>SF     |           |        |
| 0031   | 4425000000-N | 1125  | WARNING FLAG SETS                      | 2<br>EA      |           |        |
| 0032   | 4430000000-N | 1130  | DRUMS                                  | 10<br>EA     |           |        |
| 0033   | 4435000000-N | 1135  | CONES                                  | 25<br>EA     |           |        |
| 0034   | 4446100000-E | SP    | BARRICADES (TYPE III)                  | 96<br>LF     |           |        |
| 0035   | 4450000000-N | 1150  | FLAGGER                                | 160<br>HR    |           |        |
| 0036   | 4465000000-N | 1160  | TEMPORARY CRASH CUSHIONS               | 1<br>EA      |           |        |
| 0037   | 4485000000-E | 1170  | PORTABLE CONCRETE BARRIER              | 30<br>LF     |           |        |
| 0038   | 4810000000-E | 1205  | PAINT PAVEMENT MARKING LINES<br>(4")   | 13,600<br>LF |           |        |

County : Transylvania

| Line # | Item Number  | Sec # | Description                           | Quantity    | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|-------------|-----------|--------|
| 0039   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                  | 325<br>LF   |           |        |
| 0040   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS A | 75<br>TON   |           |        |
| 0041   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS B | 250<br>TON  |           |        |
| 0042   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE                | 150<br>TON  |           |        |
| 0043   | 6015000000-E | 1615  | TEMPORARY MULCHING                    | 1.5<br>ACR  |           |        |
| 0044   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING            | 50<br>LB    |           |        |
| 0045   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY SEED-<br>ING | 0.25<br>TON |           |        |
| 0046   | 6029000000-E | SP    | SAFETY FENCE                          | 150<br>LF   |           |        |
| 0047   | 6030000000-E | 1630  | SILT EXCAVATION                       | 310<br>CY   |           |        |
| 0048   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL           | 760<br>SY   |           |        |
| 0049   | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH                   | 25<br>LF    |           |        |
| 0050   | 6070000000-N | SP    | SPECIAL STILLING BASINS               | 4<br>EA     |           |        |
| 0051   | 6084000000-E | 1660  | SEEDING & MULCHING                    | 1.5<br>ACR  |           |        |
| 0052   | 6087000000-E | 1660  | MOWING                                | 1<br>ACR    |           |        |
| 0053   | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING               | 50<br>LB    |           |        |
| 0054   | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING         | 0.25<br>TON |           |        |
| 0055   | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING         | 50<br>LB    |           |        |
| 0056   | 6108000000-E | 1665  | FERTILIZER TOPDRESSING                | 1.25<br>TON |           |        |
| 0057   | 6114000000-N | SP    | SPECIALIZED HAND MOWING               | 1<br>HR     |           |        |
| 0058   | 6117000000-N | 1675  | RESPONSE FOR EROSION CONTROL          | 8<br>EA     |           |        |

| Line #                 | Item Number  | Sec # | Description  | Quantity     | Unit Cost | Amount |
|------------------------|--------------|-------|--|--------------|-----------|--------|
| 0059                   | 6123000000-E | 1670  | REFORESTATION  | 0.1<br>ACR   |           |        |
| <b>STRUCTURE ITEMS</b> |              |       |  |              |           |        |
| 0060                   | 8021000000-N | SP    | REMOVAL OF EXISTING STRUCTURE<br>AT STATION *****<br>(14+59.00-L-) | Lump Sum     | L.S.      |        |
| 0061                   | 8105520000-E | SP    | 3'-0" DIA DRILLED PIERS IN SO<br>IL                                | 16.86<br>LF  |           |        |
| 0062                   | 8105620000-E | SP    | 3'-0" DIA DRILLED PIERS NOT IN<br>SOIL                             | 38<br>LF     |           |        |
| 0063                   | 8115000000-N | SP    | CROSSHOLE SONIC LOGGING  | 2<br>EA      |           |        |
| 0064                   | 8116000000-E | SP    | CSL TUBES  | 259.4<br>LF  |           |        |
| 0065                   | 8182000000-E | 420   | CLASS A CONCRETE (BRIDGE)  | 45<br>CY     |           |        |
| 0066                   | 8210000000-N | 422   | BRIDGE APPROACH SLABS, STATION<br>*****<br>(14+59.00-L-)           | Lump Sum     | L.S.      |        |
| 0067                   | 8217000000-E | 425   | REINFORCING STEEL (BRIDGE)   | 8,680<br>LB  |           |        |
| 0068                   | 8238000000-E | 425   | SPIRAL COLUMN REINFORCING<br>STEEL (BRIDGE)                        | 1,057<br>LB  |           |        |
| 0069                   | 8503000000-E | 460   | CONCRETE BARRIER RAIL  | 95.3<br>LF   |           |        |
| 0070                   | 8608000000-E | 876   | PLAIN RIP RAP CLASS II (2'-0"<br>THICK)                            | 263<br>TON   |           |        |
| 0071                   | 8622000000-E | 876   | FILTER FABRIC FOR DRAINAGE   | 293<br>SY    |           |        |
| 0072                   | 8657000000-N | 430   | ELASTOMERIC BEARINGS   | Lump Sum     | L.S.      |        |
| 0073                   | 8762000000-E | 430   | 3'-0" X 1'-9" PRESTRESSED CONC<br>CORED SLABS                      | 524.85<br>LF |           |        |

C200966 (B-3914)  
TRANSYLVANIA COUNTY

2/16/99

Contract No: C200966

County: Transylvania

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General