

PROJECT NO.	SHEET NO.	TOTAL NO.
37489	12	16

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LENGTH	WIDTH	BORROW	FOUNDATION CONDITIONING MATERIAL TON	18" RC PIPE CULVERT, CLASS III LF	24" RC PIPE CULVERT, CLASS III LF	18" CAA PIPE CULVERT, 0.060" TH LF	24" CAA PIPE CULVERT, 0.079" TH LF	36" CAA PIPE CULVERT, 0.105" TH LF	42" CAA PIPE CULVERT, 0.105" TH LF	60" CAA PIPE CULVERT, 0.105" TH LF	54" CS PIPE CULVERT, 0.109" TH LF	73"X55" CAA ARCH, 0.105" TH LF	SEALING PAVEMENT CRACKS LBS	SHOULDER RECONSTRUCTION SMI	MILLING ASPHALT PAVMT, 1 1/4" DEPT SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS
37489	Tyrrell	1	NC 94	TYRELL/HYDE COUNTY LINE TO MP 5.3 NORTH	1	5.3	22	515	164	8		88	278	194	100	50	4	50	1,950	10.6		4,780		10,634
		2	NC 94	FROM MP 5.3 NORTH TO SR 1309 (N. GUM NECK RD.)	2	5.7	22	467	128					500	100				35	11.4		5,141	13,805	5,692
		3	NC 94	FROM SR 1309 (N. GUM NECK RD.) TO MP 20.1 NORTH	3	9.1	22	323	104		4		300	60				120	95	18.2			16,711	9,087
		4	NC 94	FROM MP 20.1 NORTH TO BRIDGE #9 AT MP 23.6	4	3.5	22	460	90				60	360						7				3,495
		5	NC 94	FROM BRIDGE #9 AT MP 23.6 TO US 64	5	0.2	36														4,250			326
TOTAL FOR PROJ NO. 37489						23.8		1,765	486	8	4	88	638	1,114	200	50	4	170	2,080	47.2	4,250	9,921	30,516	29,234
GRAND TOTAL						23.8		1,765	486	8	4	88	638	1,114	200	50	4	170	2,080	47.2	4,250	9,921	30,516	29,234

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LENGTH	WIDTH	PG 64-22 PLANT MIX	AC PLANT MIX (REPAIR)	PATCHING EXISTING PAVEMENT	REINFORCED CONCRETE ENDWALL	MANHOLES	GUARDRAIL	20" TUBULAR 3C GUARDRAIL	GUARDRAIL ANCHOR TYPE III	GUARDRAIL ANCHOR TYPE BP-II	GUARDRAIL ANCHOR TYPE 350	TEMPORARY SILT FENCE	SEED & MULCHING	INCIDENTAL STONE
37489	Tyrrell	1	NC 94	TYRELL/HYDE COUNTY LINE TO MP 5.3 NORTH	1	5.3	22	844	160	300	5.2							1,800	5.1	270
		2	NC 94	FROM MP 5.3 NORTH TO SR 1309 (N. GUM NECK RD.)	2	5.7	22	1,211	120	250			450			4	4	8,600	5.5	300
		3	NC 94	FROM SR 1309 (N. GUM NECK RD.) TO MP 20.1 NORTH	3	9.1	22	1,331	70	980								600	8.8	455
		4	NC 94	FROM MP 20.1 NORTH TO BRIDGE #9 AT MP 23.6	4	3.5	22	210	85	340			575	266.6	4		4	700	3.4	175
		5	NC 94	FROM BRIDGE #9 AT MP 23.6 TO US 64	5	0.2	36	20		100		1								
TOTAL FOR PROJ NO. 37489						23.8		3,616	435	1,970	5.2	1	1,025	266.6	4	4	8	11,700	22.9	1,200
GRAND TOTAL						23.8		3,616	435	1,970	5.2	1	1,025	266.6	4	4	8	11,700	22.9	1,200