

EROSION CONTROL**Seeding And Mulching:**

(2B)

The kinds of seed and fertilizer, and the rates of application of seed, fertilizer, and limestone, shall be as stated below. During periods of overlapping dates, the kind of seed to be used shall be determined by the Engineer. All rates are in pounds per acre (kilograms per hectare).

All Roadway Areas

| March 1 - August 31 | September 1 - February 28 |
|----------------------------------|------------------------------------|
| 50# (55kg) Tall Fescue | 50# (55kg) Tall Fescue |
| 5# (6kg) Centipede | 5# (6kg) Centipede |
| 25# (28kg) Bermudagrass (hulled) | 35# (40kg) Bermudagrass (unhulled) |
| 500# (560kg) Fertilizer | 500# (560kg) Fertilizer |
| 4000# (4500kg) Limestone | 4000# (4500kg) Limestone |

Waste and Borrow Locations**January 1 - December 31**

75# (85kg) Tall Fescue
 50# (55kg) Bahia
 500# (560kg) Fertilizer
 4000# (4500kg) Limestone

Approved Tall Fescue Cultivars:

| | | | |
|-----------------|--------------|------------|--------------|
| Adventure | Adventure II | Amigo | Anthem |
| Apache | Apache II | Arid | Austin |
| Brookstone | Bonanza | Bonanza II | Chapel Hill |
| Chesapeake | Chieftain | Coronado | Crossfire II |
| Debutante | Duster | Falcon | Falcon II |
| Finelawn Petite | Finelawn | Finelawn I | Genesis |
| Grande | Guardian | Houndog | Jaguar |
| Jaguar III | Kentucky 31 | Kitty Hawk | Monarch |
| Montauk | Mustang | Olympic | Pacer |
| Phoenix | Pixie | Pyramid | Rebel |
| Rebel Jr. | Rebel II | Renegade | Safari |
| Shenandoah | Tempo | Titan | Tomahawk |
| Trailblazer | Tribute | Vegas | Wolfpack |

On cut and fill slopes 2:1 or steeper add 30# (35kg) Sericea Lespedeza January 1 - December 31.

Fertilizer shall be 10-20-20 analysis. Upon written approval of the Engineer, a different analysis of fertilizer may be used provided the 1-2-2 ratio is maintained and the rate of application adjusted to provide the same amount of plant food as a 10-20-20 analysis.