

County : Tyrrell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0106000000-E | 230 | BORROW EXCAVATION | 1,765 CY | | |
| 0003 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 486 TON | | |
| 0004 | 0372000000-E | 310 | 18" RC PIPE CULVERTS, CLASS III | 8 LF | | |
| 0005 | 0378000000-E | 310 | 24" RC PIPE CULVERTS, CLASS III | 4 LF | | |
| 0006 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (18", 0.060") | 88 LF | | |
| 0007 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (24", 0.079") | 638 LF | | |
| 0008 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (36", 0.105") | 1,114 LF | | |
| 0009 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (42", 0.105") | 200 LF | | |
| 0010 | 0546000000-E | 310 | *** CAA PIPE CULVERTS, ***** THICK (60", 0.105") | 50 LF | | |
| 0011 | 0576000000-E | 310 | *** CS PIPE CULVERTS, ***** THICK (54", 0.109") | 4 LF | | |
| 0012 | 0987000000-E | 310 | GENERIC PIPE ITEM 73" X 55" CAA PIPE ARCH, 0.105" THICK | 170 LF | | |
| 0014 | 1022000000-E | SP | SEALING EXISTING PAVEMENT CRACKS | 2,080 LB | | |
| 0015 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 1,200 TON | | |
| 0016 | 1245000000-E | SP | SHOULDER RECONSTRUCTION | 47.2 SMI | | |

County : Tyrrell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0017 | 1297000000-E | 607 | MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/4") | 4,250 | SY | |
| 0018 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 9,921 | TON | |
| 0019 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 30,516 | TON | |
| 0020 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 29,234 | TON | |
| 0021 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 3,616 | TON | |
| 0022 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 435 | TON | |
| 0023 | 1704000000-E | SP | PATCHING EXISTING PAVEMENT | 1,970 | TON | |
| 0024 | 2220000000-E | 838 | REINFORCED ENDWALLS | 5.2 | CY | |
| 0025 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 1 | EA | |
| 0026 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 1,025 | LF | |
| 0027 | 3120000000-E | 862 | 20" TUBULAR TRIPLE CORRUGATED STEEL BM GUARDRAIL | 266.6 | LF | |
| 0028 | 3180000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** (BP-III) | 4 | EA | |
| 0029 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 | EA | |
| 0030 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 8 | EA | |
| 0031 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 249,216 | LF | |
| 0032 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 126,720 | LF | |
| 0033 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 375,936 | LF | |

County : Tyrrell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------|-----------|--------|
| 0034 | 4900000000-N | 1252 | PERMANENT RAISED PAVEMENT MARKERS | 1,571 | EA | |
| 0035 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 11,700 | LF | |
| 0036 | 6084000000-E | 1660 | SEEDING & MULCHING | 22.9 | ACR | |
| | | | Total Amount Of Bid For Entire Project : | | | |

1505/Jan10/Q854276.9/D71744100000/E35

C201350
Tyrrell County

2/16/99

Contract No: C201350
County: Tyrrell

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General