

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201140

SUMMARY OF QUANTITIES

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+10.50)
0036000000-E	225	500	CY	UNDERCUT EXCAVATION
0043000000-N	226	Lump Sum		GRADING
0134000000-E	240	155	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0199000000-E	SP	245	SF	TEMPORARY SHORING
0318000000-E	300	23	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	60	LF	15" SIDE DRAIN PIPE
0582000000-E	310	144	LF	15" CS PIPE CULVERTS, 0.064" THICK
0636000000-E	310	4	EA	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")
0708000000-E	310	64	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	220	LF	PIPE REMOVAL
1121000000-E	520	1,325	TON	AGGREGATE BASE COURSE
1220000000-E	545	45	TON	INCIDENTAL STONE BASE
1275000000-E	600	700	GAL	PRIME COAT
1489000000-E	610	1,060	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	750	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	510	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1525000000-E	SP	285	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	129	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	20	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	12	EA	RIGHT OF WAY MARKERS
2286000000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
2355000000-N	840	2	EA	FRAME WITH GRATE, STD 840.29
2556000000-E	846	320	LF	SHOULDER BERM GUTTER
3030000000-E	862	625	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3180000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (TEMPORARY RETROFIT)
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3380000000-E	862	650	LF	TEMPORARY STEEL BM GUARDRAIL
3387000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (III)
3389100000-N	SP	6	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
3635000000-E	876	1,180	TON	PLAIN RIP RAP, CLASS II
3649000000-E	876	4	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,939	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	5	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4412000000-E	SP	160	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	36	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	50	EA	DRUMS
4435000000-N	1135	25	EA	CONES
4446100000-E	SP	48	LF	BARRICADES (TYPE III)

ItemNumber	Sec #	Quantity	Unit	Description
4450000000-N	1150	1,600	HR	FLAGGER
4460000000-N	1155	4	EA	WARNING LIGHTS (TYPE B)
4475000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)
4650000000-N	1251	76	EA	TEMPORARY RAISED PAVEMENT MARKERS
4685000000-E	1205	2,800	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	2,800	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
4810000000-E	1205	20,444	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	18	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-E	1505	70	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
5306000000-E	SP	70	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)
5714000000-E	1520	800	LF	*** DI SEWER PIPE, CLASS ***** (12", 50)
5775000000-E	1525	2	EA	4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH
5776000000-E	1525	1	EA	5' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH
5780000000-E	1525	14	LF	PRECAST CONC MANHOLE WALL, * DIA, OVER 6' HT (4')
5780000000-E	1525	17	LF	PRECAST CONC MANHOLE WALL, * DIA, OVER 6' HT (5')
6000000000-E	1605	870	LF	TEMPORARY SILT FENCE
6006000000-E	1610	175	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	465	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	200	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	3	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	150	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	4	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	500	LF	SAFETY FENCE
6030000000-E	1630	1,500	CY	SILT EXCAVATION
6036000000-E	1631	1,755	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	200	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	3.5	ACR	SEEDING & MULCHING
6087000000-E	1660	2	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	2.5	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	12	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.8	ACR	REFORESTATION

REVISIONS