

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26+10.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	155 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	245 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	23 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	60 LF		
0012	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	144 LF		
0013	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0014	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	64 LF		
0015	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		
0016	0995000000-E	340	PIPE REMOVAL	220 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,325 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	45 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1275000000-E	600	PRIME COAT	700		GAL
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,060		TON
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	750		TON
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	510		TON
0023	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	285		TON
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	129		TON
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20		TON
0026	2000000000-N	806	RIGHT OF WAY MARKERS	12		EA
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2		EA
0028	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2		EA
0029	2556000000-E	846	SHOULDER BERM GUTTER	320		LF
0030	3030000000-E	862	STEEL BM GUARDRAIL	625		LF
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0032	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TEMPORARY RETROFIT)	1		EA
0033	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0035	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	650		LF
0036	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III) TEMPORARY	4		EA

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0038	3635000000-E	876	PLAIN RIP RAP, CLASS II	1,180 TON		
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	4 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,939 SY		
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	5 EA		
0042	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	160 SF		
0043	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	96 SF		
0044	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0045	4430000000-N	1130	DRUMS	50 EA		
0046	4435000000-N	1135	CONES	25 EA		
0047	4446100000-E	SP	BARRICADES (TYPE III)	48 LF		
0048	4450000000-N	1150	FLAGGER	1,600 HR		
0049	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0050	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)	2 EA		
0051	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	76 EA		
0052	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,800 LF		
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,800 LF		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,444 LF		
0055	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	18 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	70 TON		
0057	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	70 TON		
0058	5714000000-E	1520	*** DI SEWER PIPE, CLASS ***** (12", 50)	800 LF		
0059	5775000000-E	1525	4' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH	2 EA		
0060	5776000000-E	1525	5' DIA PRECAST CONC SEWER MANHOLE 0-6' DEPTH	1 EA		
0061	5780000000-E	1525	PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (4')	14 LF		
0062	5780000000-E	1525	PRECAST CONC MANHOLE WALL, ** DIA, OVER 6' HT (5')	17 LF		
0063	6000000000-E	1605	TEMPORARY SILT FENCE	870 LF		
0064	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	175 TON		
0065	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	465 TON		
0066	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0067	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0068	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0069	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0070	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150 LF		
0071	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0072	6029000000-E	SP	SAFETY FENCE	500 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	603000000-E	1630	SILT EXCAVATION	1,500 CY		
0074	603600000-E	1631	MATTING FOR EROSION CONTROL	1,755 SY		
0075	604200000-E	1632	1/4" HARDWARE CLOTH	200 LF		
0076	608400000-E	1660	SEEDING & MULCHING	3.5 ACR		
0077	608700000-E	1660	MOWING	2 ACR		
0078	609000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0079	609300000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0080	609600000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0081	610800000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
0082	611400000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0083	611700000-N	1675	RESPONSE FOR EROSION CONTROL	12 EA		
0084	612300000-E	1670	REFORESTATION	0.8 ACR		

---

**STRUCTURE ITEMS**


---

0085	800700000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** ( 26+10.50-L-)	Lump Sum	L.S.	
0086	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** ( 26+10.50-L-)	Lump Sum	L.S.	
0087	811900000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,200 CY		
0088	816100000-E	420	GROOVING BRIDGE FLOORS	4,883 SF		
0089	818200000-E	420	CLASS A CONCRETE (BRIDGE)	39.1 CY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** ( 26+10.50-L-)	Lump Sum	L.S.	
0091	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,510 LB		
0092	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0093	8391000000-N	450	STEEL PILE POINTS	22 EA		
0094	8475000000-E	460	TWO BAR METAL RAIL	180.5 LF		
0095	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-2" X 2' -10 1/2")	97.67 LF		
0096	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-2" X 3'-3 1/2")	97.67 LF		
0097	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	329 TON		
0098	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	366 SY		
0099	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0100	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0101	8753200000-E	SP	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,270.75 LF		
0102	8892000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE WEARING SURFACE	3,568 SF		

1500/Dec07/Q65992.24/D455682800000/E102

Total Amount Of Bid For Entire Project :

C201140 (B-3522)  
WAKE COUNTY

2/16/99

Contract No: C201140

County: Wake

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General