

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C200960

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	468500000-E	1205	24,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+83.00)	207700000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)	468600000-E	1205	24,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
004300000-N	226	Lump Sum		GRADING	220900000-E	838	4	CY	ENDWALLS	481000000-E	1205	48,000	LF	PAINT PAVEMENT MARKING LINES (4")
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	490000000-N	1252	320	EA	PERMANENT RAISED PAVEMENT MARKERS
005700000-E	226	200	CY	UNDERCUT EXCAVATION	236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	600000000-E	1605	1,155	LF	TEMPORARY SILT FENCE
019500000-E	265	100	CY	SELECT GRANULAR MATERIAL	255600000-E	846	45	LF	SHOULDER BERM GUTTER	600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
019600000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	303000000-E	862	350	LF	STEEL BM GUARDRAIL	600900000-E	1610	220	TON	STONE FOR EROSION CONTROL, CLASS B
031800000-E	300	30	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	304500000-E	862	37.5	LF	STEEL BM GUARDRAIL, SHOP CURVED	601200000-E	1610	170	TON	SEDIMENT CONTROL STONE
036600000-E	310	44	LF	15" RC PIPE CULVERTS, CLASS III	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	601500000-E	1615	1.5	ACR	TEMPORARY MULCHING
039600000-E	310	200	LF	42" RC PIPE CULVERTS, CLASS III	319500000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1	601800000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
112100000-E	520	75	TON	AGGREGATE BASE COURSE	321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III	602100000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
122000000-E	545	45	TON	INCIDENTAL STONE BASE	327000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	602900000-E	SP	350	LF	SAFETY FENCE
125300000-E	SP	4.2	MI	SHOULDER RECONSTRUCTION	365600000-E	876	330	SY	FILTER FABRIC FOR DRAINAGE	603000000-E	1630	435	CY	SILT EXCAVATION
133000000-E	607	300	SY	INCIDENTAL MILLING	365900000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	603600000-E	1631	970	SY	MATTING FOR EROSION CONTROL
148900000-E	610	500	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	402500000-E	901	5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	603800000-E	SP	500	SY	PERMANENT SOIL REINFORCEMENT MAT
149800000-E	610	500	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	407200000-E	903	13	LF	SUPPORTS, 3-LB STEEL U-CHANNEL	604200000-E	1632	60	LF	1/4" HARDWARE CLOTH
151900000-E	610	2,700	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	410200000-N	904	1	EA	SIGN ERECTION, TYPE E	607000000-N	SP	4	EA	SPECIAL STILLING BASINS
156000000-E	620	230	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	415500000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	608400000-E	1660	1.5	ACR	SEEDING & MULCHING
169300000-E	654	75	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	441200000-E	SP	490	SF	WORK ZONE SIGNS (STATIONARY)	608700000-E	1660	1	ACR	MOWING
200000000-N	806	16	EA	RIGHT OF WAY MARKERS	441210000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
202200000-E	815	50	CY	SUBDRAIN EXCAVATION	441220000-E	SP	106	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
203300000-E	815	40	CY	SUBDRAIN FINE AGGREGATE	442500000-N	1125	4	EA	WARNING FLAG SETS	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
204400000-E	815	200	LF	6" PERFORATED SUBDRAIN PIPE	443500000-N	1135	70	EA	CONES	610800000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
205500000-E	815	6	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	444610000-E	SP	120	LF	BARRICADES (TYPE III)	611400000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
					445000000-N	1150	160	HR	FLAGGER	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL