


EDI MODEL 2010ECL CONFLICT MONITOR


PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



REMOVE DIODE JUMPERS 1-6, 1-15, 2-6, 2-13, 2-15, 4-8, 4-14, 4-16, 6-13, 6-15, 8-14, 8-16, 13-15 AND 14-16.

OPTIONS




REMOVE JUMPERS AS SHOWN

NOTES:

- CARD IS PROVIDED WITH ALL DIODE JUMPERS IN PLACE. REMOVAL OF ANY JUMPER ALLOWS ITS CHANNELS TO RUN CONCURRENTLY.
- MAKE SURE JUMPERS SEL1-SEL5 ARE PRESENT ON THE MONITOR BOARD.

INPUT FILE POSITION LAYOUT

(front view)



EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
1A	TB2-5,6	I2U	39	1	2	1	Y	Y	-	---	3
1B	TB2-7,8	I2L	43	5	12	1	Y	Y	-	---	--
2A	TB2-9,10	I3U	63	25	32	2	Y	Y	-	---	--
2B	TB2-11,12	I3L	76	38	42	2	Y	Y	-	---	--
4A	TB4-9,10	I6U	41	3	4	4	Y	Y	-	---	3
4B	TB4-11,12	I6L	45	7	14	4	Y	Y	-	---	10
6A	TB3-5,6	J2U	40	2	6	6	Y	Y	-	---	--
8A	TB5-9,10	J6U	42	4	8	8	Y	Y	-	---	--
8B	TB5-11,12	J6L	46	8	18	8	Y	Y	-	---	10
* S20	TB7-1,2	J7U	66	28	38	SYS	-	-	-	---	--
* S21	TB7-3,4	J7L	79	41	48	SYS	-	-	-	---	--
* S22	TB7-9,10	J9U	59	21	15	SYS	-	-	-	---	--
PED PUSH BUTTONS											
P21,P22	TB8-4,6	I12U	67	29	PED 2	2	PED				
P41,P42	TB8-5,6	I12L	69	31	PED 4	4	PED				
P61,P62	TB8-7,9	I13U	68	30	PED 6	6	PED				
P81,P82	TB8-8,9	I13L	70	32	PED 8	8	PED				

NOTE:
INSTALL DC ISOLATORS
IN INPUT FILE SLOTS
I12 AND I13.

* SYSTEM DETECTOR ONLY. REMOVE THE VEHICLE PHASE ASSIGNED TO THIS DETECTOR IN THE DEFAULT PROGRAMMING.

INPUT FILE POSITION LEGEND: J2L
FILE J
SLOT 2
LOWER

NOTES


- TO PREVENT "FLASH-CONFLICT" PROBLEMS, INSERT RED FLASH PROGRAM BLOCKS FOR ALL UNUSED VEHICLE LOAD SWITCHES IN THE OUTPUT FILE. THE INSTALLER SHALL VERIFY THAT SIGNAL HEADS FLASH IN ACCORDANCE WITH THE SIGNAL PLANS.
- ENSURE THAT RED ENABLE IS ACTIVE AT ALL TIMES DURING NORMAL OPERATION. TO PREVENT RED FAILURES ON UNUSED MONITOR CHANNELS, TIE UNUSED RED MONITOR INPUTS 3,5,7,9,10,11,12,13,14,15 & 16 TO LOAD SWITCH AC+ PER CABINET MANUFACTURER'S INSTRUCTIONS.
- PROGRAM CONTROLLER TO START UP IN PHASES 2 AND 6 GREEN.
- ENABLE SIMULTANEOUS GAP-OUT FEATURE, ON CONTROLLER UNIT, FOR ALL PHASES.
- PROGRAM PHASES 4 AND 8, ON CONTROLLER UNIT, FOR DUAL ENTRY.
- THE CONTROLLER AND CABINET ARE TO BE PROGRAMMED AND WIRED TO BE PART OF A CLOSED LOOP SIGNAL SYSTEM.
CONTROLLER ASSET: 0252
- PROGRAM PHASES 2,4,6 AND 8 FOR 'START-UP PED CALL'.

EQUIPMENT INFORMATION

CONTROLLER.....CONTRACTOR SUPPLIED 2070L
CABINETCONTRACTOR SUPPLIED 332
SOFTWAREECONOLITE OASIS
CABINET MOUNT.....BASE
OUTPUT FILE POSITIONS...12
LOAD SWITCHES USED.....S1,S2,S2P,S4,S4P,S6,S6P,S8,S8P
PHASES USED.....1,2,2PED,4,4PED,6,6PED,8,8PED
OVERLAPS.....NONE

PEDESTRIAN PUSH-BUTTON WIRING DETAIL

(wire push-buttons as shown below)



FIELD CONNECTION HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S2P	S3	S4	S4P	S5	S6	S6P	S7	S8	S8P
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	11,12	21,22	P21, P22	NU	41,42	P41, P42	NU	61,62	P61, P62	NU	81,82	P81, P82
GREEN		130			103			136			109	
YELLOW		129			102			135			108	
RED		128			101			134			107	
RED ARROW	125											
YELLOW ARROW	126											
GREEN ARROW	127											
PEDESTRIAN			115			106			121			112
START-UP			113			104			119			110

NU = NOT USED

BACK-UP PROTECTION PROGRAMMING DETAIL

(program controller as shown below)

- FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE DYNAMIC/BACKUP CONTROL FUNCTION 1.
- FROM PHASE CONTROL FUNCTIONS MENU PRESS '2' (DYNAMIC/BACKUP CONTROL FUNCTIONS).

DYNAMIC/BACKUP CONTROL FUNCTION #01
OVERLAPS: ABCDEFGHIJKLMNOP
IF OVERLAPS ARE ACTIVE: |
OR PHASES: 12345678910111213141516
IF PHASES ARE ON: | X
OMIT PHASES: | X
CALL PHASES: | X

BACKUP PROTECTION PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 13-0252
DESIGNED: APRIL 2004
SEALED: 12/17/04
REVISED: TBD

SIGNAL UPGRADE - FINAL

This Plan Shall Supersede The Plan Previously Signed and Sealed On 7/02/04

Prepared for the Offices of: Traffic Engineering and Signal Systems Planning
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
Special Management Section
122 N. McDowell St., Raleigh, NC 27603

US 25 (MERRIMON AVENUE / BROADWAY STREET) AT WOODFIN STREET

SEAL
NORTH CAROLINA PROFESSIONAL ENGINEER
SEAL 07438
JAMES O. DEATON

DIVISION 13 BUNCOMBE COUNTY ASHEVILLE
PLAN DATE: APRIL 2004 REVIEWED BY: J O DEATON
PREPARED BY: M W YALCH REVIEWED BY:
REVISIONS INIT. DATE
SIGNATURE DATE
SIG. INVENTORY NO. 13-0252 F

PLANS PREPARED BY :

Mattern & Craig
CONSULTING ENGINEERS • SURVEYORS
12 BROAD STREET
ASHEVILLE, NORTH CAROLINA 28801
(828) 254-2201
FAX (828) 254-4562