

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	200 TON		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	25 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	208 LF		
001C	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	4 LF		
0011	1121000000-E	520	AGGREGATE BASE COURSE	200 TON		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	2,500 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	515 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	860 TON		
0015	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,380 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	146 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2264000000-E	840	PIPE PLUGS	0.367 CY		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0019	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7 LF		
002C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0021	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0022	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0023	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0024	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,090 LF		
0025	2591000000-E	848	4" CONCRETE SIDEWALK	100 SY		
0026	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	50 SY		
0027	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	4 EA		
0028	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	280 SY		
0029	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	300 SY		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	667 LF		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	13 EA		
0033	4108000000-N	904	SIGN ERECTION, TYPE F	12 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	3 EA		
0035	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	28 EA		
0036	4237000000-N	907	STOCKPILE SIGN, D, E OR F	1 EA		
0037	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	361 SF		
0038	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	118 SF		
0039	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	68 SF		
004C	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0041	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	5 EA		
0042	4425000000-N	1125	WARNING FLAG SETS	1 EA		
0043	4430000000-N	1130	DRUMS	110 EA		
0044	4435000000-N	1135	CONES	110 EA		
0045	4446100000-E	SP	BARRICADES (TYPE III)	144 LF		
0046	4455000000-N	1150	FLAGGER	30 MD		
0047	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)	1 EA		
0048	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	1 EA		
0049	4507000000-E	SP	WATER FILLED BARRIER	349 LF		
005C	4508000000-E	SP	RESET WATER FILLED BARRIER	612 LF		
0051	4510000000-N	SP	POLICE	20 HR		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	64	EA	
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	756	LF	
0054	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,488	LF	
0055	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	313	LF	
0056	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	720	LF	
0057	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	169	LF	
0058	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	4	EA	
0059	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	22	EA	
0060	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,297	LF	
0061	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	2,066	LF	
0062	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	338	LF	
0063	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8	EA	
0064	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	46	EA	
0065	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	220	LF	
0066	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	84	LF	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0067	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	64 EA		
0068	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	35 EA		
0069	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	35 EA		
007C	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	5 EA		
0071	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	5 EA		
0072	5005000000-E	1401	80' HIGH MOUNT STANDARD	4 EA		
0073	5020000000-N	1401	PORTABLE DRIVE UNIT	1 EA		
0074	5025000000-E	1402	HIGH MOUNT FOUNDATIONS	12 CY		
0075	5070000000-N	1405	STANDARD FOUNDATIONS ***** (R1)	7 EA		
0076	5085000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE RDW 250W HPS	24 EA		
0077	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3#1/0, USE)	50 LF		
0078	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (240/480 VOLT)	1 EA		
0079	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	300 LF		
008C	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	530 LF		
0081	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	75 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0082	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	1,540	LF	
0083	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	990	LF	
0084	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	510	LF	
0085	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	320	LF	
0086	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	2,090	LF	
0087	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	260	LF	
0088	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	540	LF	
0089	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1.5")	690	LF	
009C	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	9	EA	
0091	5270000000-N	SP	GENERIC LIGHTING ITEM FOUNDATION COVER	2	EA	
0092	5270000000-N	SP	GENERIC LIGHTING ITEM HM LUMINAIRE 400W W/ GLARE SHIELD	16	EA	
0093	5270000000-N	SP	GENERIC LIGHTING ITEM LGT STD W/ BREAKAWAY BASE	7	EA	
0094	5270000000-N	SP	GENERIC LIGHTING ITEM POST-TOP LGT W/ BREAKAWAY BASE	7	EA	
0095	5270000000-N	SP	GENERIC LIGHTING ITEM REMOVE LGT STD	30	EA	

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0096	5270000000-N	SP	GENERIC LIGHTING ITEM STANDARD FOUNDATION POST-TOP, TYPE R1S	7 EA		
0097	5648000000-N	1510	RELOCATE EXISTING WATER METER	1 EA		
0098	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		
0099	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150 TON		
0100	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0101	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0102	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0103	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0104	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0105	6030000000-E	1630	SILT EXCAVATION	125 CY		
0106	6036000000-E	1631	MATting FOR EROSION CONTROL	570 SY		
0107	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
0108	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0109	6087000000-E	1660	MOWING	1 ACR		
0110	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0111	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0112	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0113	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0114	6114000000-N	SP	SPECIALIZED HAND MOWING	2		
				HR		
0115	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8		
				EA		
0116	6138000000-E	SP	GENERIC EROSION CONTROL ITEM SELECT BACKFILL	600		
				CY		
0117	7036000000-E	1705	PEDESTRIAN SIGNAL HEAD (12", 1 SECTION)	16		
				EA		
0118	7060000000-E	1705	SIGNAL CABLE	4,800		
				LF		
0119	7072000000-E	1705	VEHICLE SIGNAL HEAD (**, ** SECTION) (12", 3 SECTION, DARK GREEN)	21		
				EA		
012C	7072000000-E	1705	VEHICLE SIGNAL HEAD (**, ** SECTION) (12", 5 SECTION, DARK GREEN)	1		
				EA		
0121	7252000000-E	1710	MESSENGER CABLE (1/4")	250		
				LF		
0122	7279000000-E	1715	TRACER WIRE	1,210		
				LF		
0123	7300000000-E	1715	TRENCHING (UNPAVED)	420		
				LF		
0124	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 1)	1,210		
				LF		
0125	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)	850		
				LF		
0126	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	17		
				EA		
0127	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	12		
				EA		
0128	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,800		
				LF		
0129	7456000000-E	1726	LEAD-IN CABLE	3,790		
				LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013C	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	1,860 LF		
0131	7552000000-N	1731	INTERCONNECT CENTER	3 EA		
0132	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER	3 EA		
0133	7566000000-N	1733	DELINEATOR MARKER	4 EA		
0134	7613000000-N	SP	SOIL TEST	10 EA		
0135	7614000000-E	SP	DRILLED PIER FOUNDATION (**" DIA) (48")	150 LF		
0136	7631000000-N	1744	MAST ARM WITH METAL POLE DE- SIGN	10 EA		
0137	7636000000-N	1745	SIGN FOR SIGNALS	5 EA		
0138	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0139	7688000000-N	SP	CABINET BASE ADAPTER	3 EA		
014C	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0141	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	17 EA		
0142	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	8 EA		
0143	7972000000-N	SP	METAL POLE REMOVAL	8 EA		
0144	7980000000-N	SP	GENERIC SIGNAL ITEM DECORATIVE SIGNAL PEDESTAL WITH FOUNDATION	4 EA		
0145	7980000000-N	SP	GENERIC SIGNAL ITEM DECORATIVE SINGLE MAST ARM WITH METAL POLE	10 EA		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	7980000000-N	SP	GENERIC SIGNAL ITEM PEDESTRIAN SIGNAL HEAD - NO PUSHBUTTON (12", 1 SECTION)	4	EA	
0147	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR PEDESTRAIN PEDESTAL	4	EA	
0148	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE	10	EA	

0921/Sep09/Q54142.117/D725677900000/E148

Total Amount Of Bid For Entire Project :

C201504 (U-3302)
COUNTY: Buncombe County

2/16/99

Contract No: C201504
County: Buncombe

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General