


begun at 19.9 feet (elevation 1052.9) and terminated at 29.8 feet (elevation 1043.0). The Recoveries and RQD's were from 62 to 87% (75% average).

Static groundwater was recorded in EB2-A at 7.4 feet (elevation 1063.5). In EB2-B, it was recorded at 8.8 feet (elevation 1064.0).

Respectfully Submitted,



C. A. Dunnagan, TEG-III  
Project Engineering Geologist

CAD:mw

