

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201292

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION	6000000000-E	1605	535	LF	TEMPORARY SILT FENCE
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+30-L-)	6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
0043000000-N	226	Lump Sum		GRADING	6009000000-E	1610	135	TON	STONE FOR EROSION CONTROL, CLASS B
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING	6012000000-E	1610	145	TON	SEDIMENT CONTROL STONE
0057000000-E	226	500	CY	UNDERCUT EXCAVATION	6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
0080000000-E	SP	600	TON	CLASS IV SUBGRADE STABILIZA- TION	6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
0134000000-E	240	144	CY	DRAINAGE DITCH EXCAVATION	6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED- ING
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL	6029000000-E	SP	300	LF	SAFETY FENCE
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION	6030000000-E	1630	400	CY	SILT EXCAVATION
0318000000-E	300	30	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	6036000000-E	1631	520	SY	MATTING FOR EROSION CONTROL
0366000000-E	310	188	LF	15" RC PIPE CULVERTS, CLASS III	6038000000-E	SP	1,700	SY	PERMANENT SOIL REINFORCEMENT MAT
0372000000-E	310	60	LF	18" RC PIPE CULVERTS, CLASS III	6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH
0726000000-E	310	32	LF	30" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK	6070000000-N	SP	4	EA	SPECIAL STILLING BASINS
0995000000-E	340	253.1	LF	PIPE REMOVAL	6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
1220000000-E	545	20	TON	INCIDENTAL STONE BASE	6087000000-E	1660	1	ACR	MOWING
1489000000-E	610	325	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
1525000000-E	SP	245	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
1560000000-E	620	30	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
1693000000-E	654	25	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
2000000000-N	806	19	EA	RIGHT OF WAY MARKERS	6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
2022000000-E	815	112	CY	SUBDRAIN EXCAVATION	6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
2033000000-E	815	84	CY	SUBDRAIN FINE AGGREGATE					
2043000000-E	815	500	LF	4" PERFORATED SUBDRAIN PIPE					
2054000000-E	815	15	EA	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS					

5/28/99

IS:MAP-2005-11-43  
R:\Roadway\Proj\B4047-r.dwg-sum.dgn  
S:\shley\A\RD223233